

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Thos Dawson Hrs. 5355 Operator Well No.: 8131

LOCATION: Elevation: 1481' Quadrangle: Hundred 7.5'
District: Battelle County: Monongalia
Latitude: _____ Feet South of 39 Deg. 66 Min. 12.20 Sec.
Longitude: _____ Feet West of -80 Deg. 40 Min. 11.10 Sec.

Well Type: OIL _____ GAS X

Company West Virginia Land Resources, LLC. Coal Operator West Virginia Land Resources, LLC.
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Coal Operator _____
Agent David Roddy or Owner _____
Permit Issued Date 3/4/2024 _____

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Monongalia ss:

Matthew A. Yearsley and John Campbell being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 14th day of March, 2024, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic Cement w/ Green Dye and Gas Blocker	1565'	1277'	8 5/8" 507'	Unknown
Thixotropic Cement and Green Dye	1277'	1090'	16" 0'	20'
Expandable Cement	1090'	Surface		


Description of monument: 96" of 7" casing with Company Name, Well#, API#, and date cemented and that the work of plugging and filling said well was completed on the 8th day of May, 2024.

And further deponents saith not. Matthew A. Yearsley
John Campbell

Sworn and subscribe before me this 21st day of May, 2024

My commission expires: June 8, 2027

Christopher Andrew Willis
Notary Public



Affidavit reviewed by the Office of Oil and Gas: _____ Title: Inspector

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

WEST VIRGINIA LAND RESOURCES INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

COLUMBIA GAS TRANSMISSION CORP.
Lease or Property Owner
700 Louisiana St., Suite 1300, Houston, TX 77002
Address

WEST VIRGINIA LAND RESOURCES INC.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address

HUNDRED, WV 7.5'
Well Location
BATTELLE
District
MONONGALIA
County
8131
Well No.
THOS DAWSON HRS 5355
Farm

STATE INSPECTOR SUPERVISING PLUGGING _____

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:
MATTHEW A. YEARSLEY and John Campbell being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 3rd day of March, 2024 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
	Cleaned a 12 1/4" hole from surface to 230'. Reduced hole to 9 7/8" at 230'. Cleaned a 9 7/8" hole from 230' to 509'. Tagged existing 8 5/8" casing at 509'. Reduced hole to 7 7/8" at 509'. Cleaned a 7 7/8" hole through 8 5/8" casing from 509' to an approved depth of 1556'. Cleaned a 7 7/8" hole through Pittsburgh Coal Seam from 1290.5' to 1296.5'. Removed 507' of 8 5/8" casing from 509' to 1016' with extreme difficulty. Continue to clean a 9 7/8" hole from 509' to 1016'. Made a diligent effort to remove remaining 8 5/8" casing in well. All attempts were unsuccessful. Left unknown amount of 8 5/8" casing in well from 1016' to unknown. Cut remaining 8 5/8" casing from 1489', 1445', 1346', 1299', 1294', 1292.5', 1289', 1287', 1282', 1234.5' and 1185'. Perforated 8 5/8" casing with 6 shots each a 1496.5', 1446.5', 1346.5', 1306.5', 1301.5', 1296.5', 1290.5', 1285.5', 1280.5', 1240.5', and 1190.5'.	8 5/8"	507'	Unknown
		16"	0'	20'
	Cemented the hole from 1565' to surface as follows: Cemented bottom hole plug from 1565' to 1090' with 140 sacks of Thixotropic Cement with Green Dye and Gas blocker. Tag cement at 1277'. Cemented from 1277' to 1090' with 55 sacks of Thixotropic with Green Dye. Cemented from 1090' to surface with 535 sacks of Expandable Cement. Cement circulated at the surface.			
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	<u>1290.5' to 1296.5'</u>	96" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 8th day of May, 2024

And further deponents saith not.

Matthew A. Yearsley
Matthew A. Yearsley


John Campbell
John Campbell

Sworn to and subscribed before me this 21st day of May, 2024.

Christopher Willis
Notary Public

My commission expires:

June 8, 2027



Permit No. 47-061-01956-00-00
Well No. 8131
Latitude: 39° 66' 12.20"N
Longitude: -80° 40' 11.10"W