

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Harry M. Antill Operator Well No.: 4528

LOCATION: Elevation: 1246.76' Quadrangle: Hundred WV, PA 7.5'
District: Church County: Wetzel
Latitude: _____ Feet South of 39 Deg. 38 Min. 51.38 Sec.
Longitude: _____ Feet West of -80 Deg. 24 Min. 42.31 Sec.

Well Type: OIL _____ GAS X

Company Consolidation Coal Co. Coal Operator Consolidation Coal Co.
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Agent David Roddy Coal Operator _____
or Owner _____
Permit Issued Date 10/11/19

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 21st day of January, 2021, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye	1314'	901'		
Thixotropic	901'	884'		
Expandable Cement	884'	Surface		
2 3/8" Tubing			117'	0'
8 5/8" Casing	1182'	Unknown	184'	Unknown
16" Conductor Pipe	Surface	20'	0'	20'

Description of monument: 77' of 7" casing with company name, well #, API #, and date cemented. and that the work of plugging and filling said well was completed on the 12th day of February, 2021.

And further deponents saith not. Matthew A. Yearsley
Kevin S. Wright



Sworn and subscribe before me this 1st day of mar, 2021
My commission expires: 09/15/22 [Signature]
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Derek M Haught Title: Oil & Gas Inspector 09/20/2024

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

FLOYD & FRANCIS POSTLETHWAIT
Lease or Property Owner
517 POGUE RUN, BURTON, WV 26348
Address

CONSOLIDATION COAL CO.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address

HUNDRED WV, PA 7.5'
Well Location

GRANT
District

WETZEL
County

4528
Well No.

HARRY M. ANTILL
Farm

4528
Well No.

HARRY M. ANTILL
Farm

HARRY M. ANTILL
Farm

HARRY M. ANTILL
Farm

STATE INSPECTOR SUPERVISING PLUGGING Derek M Haught

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 21st day of January, 2021 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
Removed 117' of 2 3/8" tubing from the surface to 117'. Cleaned the hole with a 12 1/4" bit from the surface to 250'. Reduced the hole to 9 7/8" at 250'. Cleaned the hole with a 9 7/8" bit from 250' to the top of the existing 8 5/8" casing at 998'. Reduced the hole 7 7/8" at 998'. Cleaned the hole with a 7 7/8" bit from 998' to 1314'. Removed 184' of 8 5/8" casing from 998' to 1182'. Attempts to remove remaining 8 5/8" casing by pulling 120% of the string weight were unsuccessful. Left an unknown amount of 8 5/8" casing in the hole from 1184' to an unknown depth. Cut remaining 8 5/8" casing at 1291'. The 8 5/8" casing was previously parted from 1220' to 1226' and ripped at the following depths, 1262' to 1264' and 1285' to 1286'. Cleaned a 9 7/8" hole through the Pittsburgh Coal Seam (1084' - 1091'). Left 20' of 16" conductor pipe in the hole from the surface to 20'.	16" Conductor 8 5/8' Casing	0' 184'	40' Unknown	
Cemented the hole from 1314' to surface as follows:				
From 1314' to 884' with 215 sacks of Thixotropic Cement with Green Dye. Tagged top of Thixotropic plug at 901'. From 901' to 884' with 10 sacks of Thixotropic Cement. From 884' to surface with 455 sacks of Expandable Cement. Cement did circulate at surface. A total of 680 sacks of cement were used to cement the hole from 1314' to surface.				
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	<u>1084' - 1091'</u>	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 12th day of February, 2021

And further deponents saith not.



Matthew A. Yearsley

Matthew A. Yearsley

Kevin S. Wright

Kevin S. Wright

Sworn to and subscribed before me this 1st day of Mar, 2021

09/20/2024

[Signature]
Notary Public

My commission expires: 09/15/22

Permit No. 47-103-00026
Well No. 4528
Latitude: 39° 38' 51.38"N
Longitude: -80° 24' 42.31"W