

NOTICE OF PROPOSED LOCATION OF OIL AND GAS WELL
(REQUIRED BY SECTION 2, CHAPTER 86, ACTS 1929)
WEST VIRGINIA DEPARTMENT OF MINES
OIL AND GAS SECTION

To THE DEPARTMENT OF MINES,
Charleston, W. Va.

~~Ezra A. Edgell~~
COAL OPERATOR OR COAL OWNER

Curtis B. Fleming
NAME OF WELL OPERATOR

~~Smithfield, W. Va.~~
ADDRESS

Fairmont, W. Va. 502 Locust Ave.
COMPLETE ADDRESS

No operation within 12
or 15 miles of this property.
COAL OPERATOR OR COAL OWNER

Nov. 20th 1935
PROPOSED LOCATION

ADDRESS

Church District

COAL OPERATOR OR COAL OWNER

Wetzel County

ADDRESS

Well No. One

Clyde B. Edgell Heirs Farm

GENTLEMEN:

The undersigned well operator is entitled to drill upon the above named farm or tract of land for oil and gas, having fee title thereto, (or as the case may be) under grant or lease dated October 4th, 1935.

made by Ora Edgell, widow and guardian,

Curtis B. Fleming

and recorded on the day

of October, 1935, in the office of the County Clerk for said County in

Book, page.

The enclosed plat was prepared by a competent engineer and shows the proposed location of a well to be drilled for oil and gas by the undersigned well operator on the farm and in the Magisterial District and County above named, determined by survey and courses and distances from two permanent points, or land marks.

The undersigned well operator is informed and believes there are no coal operators operating beds of coal beneath said farm or tract of land on which said well is located, or within 500 feet of the boundaries of the same, who have mapped their workings and filed their maps as required by law, excepting the coal operators or coal owners (if any) above named as addressees.

The above named coal operators or coal owners (if any) are notified that any objections they may desire to make to such proposed location, or which they are required to make by Section 3 of said Act, if the drilling of a well at said proposed location will cause a dangerous condition in or about their respective coal mines, must be received by, or filed with the Department of Mines within ten* days from the receipt of a copy of this notice and accompanying plat by said Department. Said coal operators are further notified that forms for use in making such objections will be furnished to them by the Department of Mines promptly on request and that all such objections must set forth as definitely as is reasonably possible the ground or grounds on which such objections are based and indicate the direction and distance the proposed location should be moved to overcome same.

(The next paragraph is to be completed only in Department's copy.)

Copies of this notice and the enclosed plat were mailed by registered mail, or delivered to the above

Ezra A. Edgell, Smithfield, W. Va.

named coal operators or coal owners at their above shown respective address 21st day of Nov. before, 1935, or on the same day with the mailing or delivery of this copy to the Department of Mines at Charleston, West Virginia.

Very truly yours,

Curtis B. Fleming
WELL OPERATOR

502 Locust Ave.
STREET

Fairmont, W. Va.
CITY OR TOWN

STATE

09/29/2023

The undersigned Company owning the surface and Mapletown vein of coal in connection with the above well location, hereby waives service of the notice, this 21st day of November, 1935.

Maxton Oil and Gas Co.
By Scott C. Lowe Sec. and Treas.

*Section 3. If no such objections be filed, or be found by the department of mines, within said period of ten days from the receipt of said notice and plat by the department of mines, to said proposed location, the department shall forthwith issue to the well operator a drilling permit reciting the filing of such plat, that no objections have been made by the coal operators to the location, or found thereto by the department, and that the same is approved and the well operator authorized to proceed to drill at said location.

NOTICE OF PROPOSED LOCATION OF OIL AND GAS WELL
 (Required by Section 2, Chapter 40, Act 1925)
 WEST VIRGINIA DEPARTMENT OF MINES
 OIL AND GAS SECTION

Form 97

To The Department of Mines,
 Charleston, W. Va.

NAME OF WELL OPERATOR _____
 COAL OPERATOR OR COAL OWNER _____
 ADDRESS _____
 CITY OR TOWN _____
 STATE _____

PROPOSED LOCATION _____
 DISTRICT _____
 COUNTY _____
 Well No. _____
 FARM _____

DEPARTMENT: _____
 The undersigned well operator is entitled to drill upon the above named farm or tract of land for oil and gas having the title hereto, or as the case may be, under grant or lease dated _____ made by _____ and recorded on the _____ day of _____ in the office of the County Clerk for said County in Book _____ page _____.

The enclosed plat was prepared by a competent engineer and shows the proposed location of a well to be drilled for oil and gas by the undersigned well operator on the farm and in the Mineral District and County above named, determined by survey and courses and distances from two permanent points, or land marks.

The undersigned well operator is informed and believes there are no coal operators operating both of coal beneath said farm or tract of land on which said well is located, or within 500 feet of the boundary of the same, who have mapped their workings and filed their maps as required by law, excepting the coal operators or coal owners (if any) above named as aforesaid.

The above named coal operators or coal owners (if any) are notified that any objections they may desire to make to such proposed location, or which they see required to make by Section 2 of said Act, if the drilling of a well at said proposed location will cause a dangerous condition in or about their respective coal mines must be received by, or filed with the Department of Mines within ten days from the receipt of a copy of this notice and accompanying plat by said Department. Said coal operators are further notified that forms for use in making such objections will be furnished to them by the Department of Mines promptly on request and that all such objections must set forth as definitely as is reasonably possible the ground or grounds on which such objections are based and indicate the direction and distance the proposed location should be moved to overcome same.

(The next paragraph is to be completed only in Department's copy.)

Copies of this notice and the enclosed plat were mailed by registered mail or delivered to the above named coal operators or coal owners at their above shown respective addresses _____ on the same day with the mailing or delivery of this copy to the Department of Mines at Charleston, West Virginia.

Very truly yours,

 WELL OPERATOR

 CITY OR TOWN _____
 STATE _____

09/29/2023

A-10

November 22, 1935

Mr. Ezra A. Edgell
Smithfield, West Virginia

Dear Mr. Edgell:

A notice of a proposed location of oil or gas Well No. 1 on the Clyde E. Edgell Heirs, Church District, Wetzel County, has been received from Curtis B. Fleming. A copy of this notice with an attached map should have been mailed you by the well operator.

Any objections you might wish to make to the proposed location that come under our jurisdiction must be filed not later than December 2, 1935.

Very truly yours,

NPR/AS

Chief of Department of Mines

09/29/2023

4-11

December 2, 1935

Mr. Curtis B. Fleming
502 Locust Avenue
Fairmont, W. Va.

Dear Sir:

Permit to drill Well No. 1 on the Clyde
E. Edgell Heirs Farm, Church District, Wetzel County,
is enclosed.

Just as soon as the well is completed, please
fill out the enclosed blanks and return to this office.

Very truly yours,

Chief of Department of Mines.

NPR:g

encl

09/29/2023


B-1

Clyde E. Edgell's Heirs, No. 1.
Location, near Cottontown, Church Dist., Wetzel Co.
Owner, Curtis B. Fleming.
Contractor, D. W. or Arthur Null.
Commenced, Nov. 9th, 1935.
Completed, Dec. 1st, 1935.

Record.

Clay, Gray	Soft	0- 110
Red Rock, Red	"	110- 120
Clay, Gray	"	120-200
Red Rock, Red,	"	200- 215
Shale, Gray,	"	215- 405
Coal, Dark,	"	405- 415
Slate, Dark,	"	415- 575
Lime, White,	hard	575- 600
Slate, dark,	soft	600- 615
Bluff Sand, white,	hard	615- 650
Fairview Coal, black,	soft	650- 655
Sand Bluff, white,	hard	655- 675
Mapletown Lime, white,	hard	675- 800
" Coal, black,	soft	800- 805
Slate, dark,	"	805- 810
Lime, white	hard	810- 825
Slate, "	soft	825- 840
Lime, "	hard	840- 890
Slate, "	soft	890- 900
Pitts. Coal, black,	"	900- 909
Lime, white,	hard	909- 930
XXXXXXXXXXXX		
Slate, dark,	soft	930- 960
Red Rock, red,	"	960- 970
Lime, dark,	hard	970- 980
Red Roc, red,	soft	980- 992
Lime Shells, light,	hard & "	992-1025
Red Rock, red,	soft	1025-1050
Lime, white,	hard	1050-1065
Slate-shell, dark,	soft	1065-1230
Red Rock, red,	"	1230-1240
Sand, white,	hard	1240-1260
Slate, light,	soft	1260-1280
Little Dunkard, light,	hard	1280-1340
Slate, dark,	soft	1340-1365
Big Dunkard, light,	hard	1365-1420
Slate & Shells,	soft	1420-1575
Gas Sand,	hard	1575-1605
Slate, dark,	soft	1605-1650
1st Salt Sand,	hard	1650-1665
Slate, dark,	soft	1665-1715
2nd Salt Sand, white,	hard	1715-1761 Gas 1747-1750
Slate, dark	soft	1761-1820
3rd Salt Sand, dark,	hard	1820-1890
Slate, dark,	soft	1890-1955
Red Rock, red	"	1955-1985
Gritty Lime, light,	hard	1985-2007
Maxton Sand, "	"	2011-2087
Oil		2034
"		2050-2053
"		2080-2084
Break, dark slate,	soft	2087-2089
Total,		2094

wet-108



09/29/2023

Casing Record:
10" csg. 200'
6 5/8" " 1857'

Respectfully submitted,

Curtis B. Fleming,
Owner.
502. Locust Ave. Fairmont, W. Va.

1-27-36

Completed, Dec. 1st, 1938.
 Commenced, Nov. 25th, 1938.
 Geologist, D. W. or Arthur Hall.
 Owner, Curtis B. Fleming.
 Location, near Gottenstown, Church Dist., Wetzel Co.
 Clyde R. Magell's Heirs, No. 1.

Records.

0-110	Soft	Gray, Gray
110-120	"	Red Rock, Red
120-200	"	Gray, Gray
200-215	"	Red Rock, Red
215-405	"	Slate, Gray
405-415	"	Coal, Dark
415-575	"	Slate, Dark
575-600	hard	Lime, White
600-615	soft	Slate, dark
615-650	hard	Bill Band, white
650-655	soft	Triview Coal, black
655-675	hard	Band Bill, white
675-800	hard	Mapletown Lime, white
800-805	soft	Coal, black
805-810	"	"
810-825	hard	Slate, dark
825-840	soft	Lime, white
840-890	hard	"
890-900	soft	"
900-909	"	Pitta, Coal, black
909-930	hard	Lime, white
930-950	soft	Slate, dark
950-970	"	Red Rock, red
970-980	hard	Lime, dark
980-985	soft	Red Rock, red
985-1025	"	Lime Shell, light
1025-1050	soft	Red Rock, red
1050-1065	hard	Lime, white
1065-1230	soft	Slate-shell, dark
1230-1240	"	Red Rock red
1240-1260	hard	Sand, white
1260-1280	soft	Slate, light
1280-1290	hard	Little Dunkard, light
1290-1355	soft	Slate, dark
1355-1420	hard	Big Dunkard, light
1420-1575	soft	Slate & Shells
1575-1605	hard	Gas Sand
1605-1650	soft	Slate, dark
1650-1655	hard	1st Belt Sand
1655-1715	soft	Slate, dark
1715-1761	hard	2nd Belt Sand, white
1761-1820	soft	Slate, dark
1820-1890	hard	3rd Belt Sand, dark
1890-1955	soft	Slate, dark
1955-1955	"	"
1955-2007	hard	Red Rock, red
2007-2087	hard	Gitty Lime, light
2087	"	Nexton Sand
2087-2087	oil	"
2087-2087	"	"
2087-2087	soft	Break, dark slate
2087	Total	

Gaining Record:
 10' sec. 200'
 2 1/2" " 1887'

09/29/2023

Responsibility submitted.

