

NOTICE OF PROPOSED LOCATION OF OIL AND GAS WELL
(REQUIRED BY SECTION 2, CHAPTER 22, CODE 1931)
WEST VIRGINIA DEPARTMENT OF MINES
OIL AND GAS SECTION

To THE DEPARTMENT OF MINES,
Charleston, W. Va.

J. W. Dawson

C. B. Smith

~~COAL OPERATOR OR COAL OWNER~~ OWNER

NAME OF WELL OPERATOR

New Martinsville, Rt # 2

R.D. # 3

ADDRESS

COMPLETE ADDRESS

W. VA.

Parkersburg, W. VA. 193
Sept. 6, 1939

COAL OPERATOR OR COAL OWNER

PROPOSED LOCATION

ADDRESS

Green District

Wetzel County

OWNER OF MINERAL RIGHTS

Well No. 1 ^{39° 35'}
_{80° 45'}

ADDRESS

J. W. Dawson Farm

GENTLEMEN:

The undersigned well operator is entitled to drill upon the above named farm or tract of land for oil and gas, having fee title thereto, (or as the case may be) under grant or lease dated May, 1935

Made by J. W. Dawson et Ux, made by _____, to

C. B. Smith & A. B. Hendershot, and recorded on the 12th day of Sept 1938, in the office of the County Clerk for said County in

Book 33-A, page 15.

The enclosed plat was prepared by a competent engineer and shows the proposed location of a well to be drilled for oil and gas by the undersigned well operator on the farm and in the Magisterial District and County above named, determined by survey and courses and distances from two permanent points, or land marks.

The undersigned well operator is informed and believes there are no coal operators operating beds of coal beneath said farm or tract of land on which said well is located, or within 500 feet of the boundaries of the same, who have mapped their workings and filed their maps as required by law, excepting the coal operators or coal owners (if any) above named as addressees.

The above named coal operators or coal owners (if any) are notified that any objections they may desire to make to such proposed location, or which they are required to make by Section 3 of said Code, if the drilling of a well at said proposed location will cause a dangerous condition in or about their respective coal mines, must be received by, or filed with the Department of Mines within ten* days from the receipt of a copy of this notice and accompanying plat by said Department. Said coal operators are further notified that forms for use in making such objections will be furnished to them by the Department of Mines promptly on request and that all such objections must set forth as definitely as is reasonably possible the ground or grounds on which such objections are based and indicate the direction and distance the proposed location should be moved to overcome same.

(The next paragraph is to be completed only in Department's copy.)

Copies of this notice and the enclosed plat were mailed by registered mail, or delivered to the above named coal operators or coal owners at their above shown respective address _____ day _____ before, or on the same day with the mailing or delivery of this copy to the Department of Mines at Charleston, West Virginia.

Very truly yours,

C. B. Smith
WELL OPERATOR

R. D. # 3

STREET

Parkersburg, W. VA.

CITY OR TOWN

09/22/2023

STATE

Address of Well Operator }



*Section 3 . . . If no such objections be filed, or be found by the department of mines, within said period of ten days from the receipt of said notice and plat by the department of mines, to said proposed location, the department shall forthwith issue to the well operator a drilling permit reciting the filing of such plat, that no objections have been made by the coal operators to the location, or found thereto by the department, and that the same is approved and the well operator authorized to proceed to drill at said location.

NOTICE OF PROPOSED LOCATION OF OIL AND GAS WELL
 WEST VIRGINIA DEPARTMENT OF MINES
 OIL AND GAS SECTION

To The Department of Mines
 Charleston, W. Va.

NAME OF WELL OPERATOR _____ COUNTY _____ DISTRICT _____ PROPOSED LOCATION _____ ADDRESS _____ CITY _____ STATE _____	NAME OF COAL OWNER _____ COUNTY _____ DISTRICT _____ PROPOSED LOCATION _____ ADDRESS _____ CITY _____ STATE _____
---	--

The undersigned well operator is entitled to drill upon the above named tract of land for oil and gas, having the title thereto, (or as the case may be) under grant or lease dated _____, 19____.

The undersigned well operator is entitled to drill upon the above named tract of land for oil and gas, having the title thereto, (or as the case may be) under grant or lease dated _____, 19____.

The enclosed plat was prepared by a competent engineer and shows the proposed location of a well to be drilled for oil and gas by the undersigned well operator on the tract and in the Magisterial District and County above named, determined by survey and contact and distances from two permanent points or land marks.

The undersigned well operator is informed and believes there are no coal operators operating on the tract and land on which said well is located or within 500 feet of the land on which the same, who have mapped their workings and filed their maps as required by law, excepting the coal operators or coal owners (if any) above named as addressees.

The above named coal operators or coal owners (if any) are notified that any objections they may desire to make to such proposed location or which they are required to make by Section 5 of said Code, if the drilling of a well at said proposed location will cause a dangerous condition in or about their respective coal mines, must be received by the Department of Mines within ten days from the receipt of a copy of this notice and upon receiving that by said Department, said coal operators or coal owners (if any) shall be notified that forms for filing in writing such objections will be furnished to them by the Department of Mines promptly on request and that all such objections must be filed as aforesaid as to responsibility. The grounds of grounds on which such objections are based and indicate the character and distance the proposed location should be moved to overcome same.

(The next paragraph is to be completed only in Department's copy.)

Copies of this notice and the enclosed plat were mailed by registered mail, or delivered to the above named coal operators or coal owners at their above shown respective addresses _____ day _____ before _____, 19____, and a copy to the Department of Mines at Charleston, West Virginia.

Very truly yours,

 WELL OPERATOR

 COUNTY

 DISTRICT

 STATE

Address
 of
 Well Operator

09/22/2023

Section 5 of the Code provides that objections be filed or be found by the Department of Mines within said period of ten days from the receipt of said notice and that by the aforesaid notice a warning is given to such persons of record the manner and means for filing such objections to the well operator a drilling permit covering the time of such objections have been made by the coal operators to the location of land therefor by the Department and that the same is approved and the well operator authorized to proceed to drill at said location.

A 10

September 9, 1939

Mr. J. W. Dawson
Route No. 2
New Martinsville, W. Va.

Dear Sir:

A notice of proposed location of Well No. 1, on the J. W. Dawson Farm, Green District, Wetzel County, has been received from C. B. Smith, Parkersburg, West Virginia. A copy of the notice and location plat should have been mailed you by the well operator.

If you have any objections to the proposed location please file same not later than September 19, 1939.

Very truly yours,

Secretary
OIL AND GAS DIVISION

MG/ar

09/22/2023

A-11

September 19, 1939

Mr. C. B. Smith
R. F. D. No. 3
Parkersburg, W. Va.

Dear Sir:

Permit WET-232 to drill Well No. 1 on the
J. W. Dawson Farm, Green District, Wetsel County, is
enclosed.

Duplicate permit shall be posted on the rig.

When the well is completed, please file complete
record on the enclosed forms OG-10.

Very truly yours,

Secretary
OIL AND GAS DIVISION

MC/er
enc-4

Lat39d-35'
Long80d-45'

09/22/2023

3-2

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks
Lime						1320-1325	
Slate						1325-1340	
Lime						1340-1350	
Sand						1350-1365	
Slate & Shells						1365-1395	
and						1395-1460	
Slate						1460-1580	
Sand						1580-1600	
Slate						1600-1620	
Sand						1620-1680	
Slate						1680-1685	
Sand dark						1685-1700	
Sand						1700-1770	
Black Lime						1770-1780	
Sand						1780-1790	
Black Slate						1790-1795	
Black Sandy Slate						1795-1885	
Black Lime						1885-1890	
Slate						1890-1895	
Little Lime						1895-1908	
Pencil Cave						1908-1920	
Big Lime						1920-1986	1925'-5 3/16"
Keener Sand						1986-2010	
Injun Sand						2010-2040	
Black Formation						2040-2079	
Squaw Water						2079-2100	Total Depth

1925'-5 3/16"

Total Depth

09/22/2023

Date Oct 29th, 1939

APPROVED C.B. Smith, Herkese oil Co, Owner

By C.B. Smith atty in fact. (Title)

B-1

STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION

WELL RECORD

WET 232

Dry Hole

Permit No.

Oil or Gas Well (Kind)

Company Her Lee Oil Co.
 Address Parkersburg, W. Va.
 Farm J. W. Dawson Acres 16
 Location (waters) Fluharty Run
 Well No. 1 Elev.
 District Green County Wetzel
 The surface of tract is owned in fee by J.W. Dawson
 Address New Martinsville, W. Va. R #2
 Mineral rights are owned by J. W. Dawson
 Address

Drilling commenced Sept. 20, 1939
 Drilling completed Oct. 28, 1939
 Date shot..... Depth of shot.....

Open Flow /10ths Water in..... Inch
 /10ths Merc. in..... Inch

Volume..... Cu. Ft.
 Rock Pressure..... lbs..... hrs.
 Oil..... bbls., 1st 24 hrs.
 Fresh water..... feet..... feet
 Salt water..... feet..... feet

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			Kind of Packer.....
16			
13			
10	140 ft		Size of.....
8 1/4	1018 ft		
6 3/8	1305 ft		Depth set.....
5 3/16	1925 ft		
3			Perf. top.....
2			Perf. bottom.....
Liners Used.....			Perf. top.....
			Perf. bottom.....

CASING CEMENTED..... SIZE..... No. Ft..... Date.....

COAL WAS ENCOUNTERED AT..... FEET..... INCHES
 FEET..... INCHES..... FEET..... INCHES
 FEET..... INCHES..... FEET..... INCHES

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks
13" Wood Conductor						14 ft	
Yellow Clay						13-60	
Sand				Very little	Water	60-70	
Slate						70-125	140'-10"
Slate & Shells						125-300	
Black Slate						300-310	
Lime						310-320	
Slate	White					320-360	
Red Rock						360-390	
Slate & Shells						390-475	
Lime						475-500	
White Slate						500-550	
Lime						550-565	
XXXXXXXXXX Shells						565-600	
Lime Hard						600-640	
Slate & Shells						640-700	
Sand						700-710	
Slate & Shells						710-755	
Black Slate						755-756	
Lime						756-770	
Black Slate						770-780	
Blue Slate						780-810	
Sand						810-845	
Slate						845-850	
Lime & Sand						850-890	
Red Rock						890-910	
Lime						910-925	
Slate						925-930	
Red Rock						930-935	
Shells						935-965	
Red Rock						965-995	
Slate						995-1080	
Red Rock						1080-1100	1018'-8 1/4"
Blue Slate						1100-1115	09/22/2023
Slate White						1115-1150	
Pink Rock						1150-1170	
Slate & Shells						1170-1260	
Pink Rock						1260-1270	
Blue Slate						1270-1300	
Big Dunkard						1300-1310	1305'-6 5/8"
Blue Slate						1310-1320	



STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION



INSPECTOR'S WELL REPORT

Permit No. *Wpt. 232P.*

Oil or Gas Well (KIND)

Company	Casing and Tubing	Used in Drilling	Left in Well	Packers
<i>Her Lee Oil Co</i>	Size			Kind of Packer
<i>Parkersburg W Va</i>	16			
<i>J W Dawson</i>	13			
Well No. <i>1</i>	10			Size of
District <i>Green</i> County <i>Wetzel</i>	8 1/4			
Drilling commenced	6 5/8			Depth set
Drilling completed	5 3/16			
Date shot	3			Perf. top
Initial Open Flow	2			Perf. bottom
Open Flow after tubing	Liners Used			Perf. top
Volume				Perf. bottom
Rock Pressure	CASING CEMENTED	SIZE	No. FT.	Date
Oil	COAL WAS ENCOUNTERED AT	<i>755</i>	FEET	<i>12</i> INCHES
Fresh water	FEET	INCHES	FEET	INCHES
Salt water	FEET	INCHES	FEET	INCHES

Drillers' Names *Elsy Peck*

Well Abandoned and Plugged, 19

REMARKS: *Bridged at 1038 Rigging to pull 8" have omitted cement for coal at 755 on driller's statement that there was only a show.*
Nov. 10 1939

D. J. Courney
DISTRICT WELL INSPECTOR

09/22/2023

B-9

PROPOSED MANNER OF PLUGGING AND FILLING WELL

(REQUIRED BY RULES AND REGULATIONS)

WEST VIRGINIA DEPARTMENT OF MINES

OIL AND GAS DIVISION

WORK ORDER

Well to be plugged and filled as follows:

WORK ORDER ARRANGED BY THE DEPARTMENT OF MINES:

Total Depth 2100'

Fill with red clay from bottom 2100' - 1945' - 20' below 5-3/16" casing.

Wood Plug 1945' - 1942'

Cement 1942' - 1932' - Sealing hole completely below 5-3/16" Casing.

Pull 1925' - 5-3/16" casing.

Set a permanent bridge at 1730' - 30' below Salt Sands.

1 sack cement on bridge.

Fill with non-porous material from 1730' - 1335' - 30' below 6-5/8" casing.

Wood Plug 1335' - 1332'

Cement 1332' - 1322' - Sealing Salt Sands above.

Pull 1305' - 6-5/8" casing.

Set a permanent bridge at 1038' - 20' below 8 1/4" casing.

1 sack cement on bridge.

Pull 8 1/4" casing (1013')

Fill to 900'

Cement 900' - 890'

Set a permanent bridge 350'

1 sack cement on bridge.

Pull 140' - 10" casing and

Fill with red clay to surface.

Erect Marker such as is required by Rule 18, 1931 Regulations.

NOTE: CEMENT FOR MAKING CEMENT PLUGS BE MIXED WITH WATER ONLY--APPROXIMATELY FIVE GAL WATER TO ONE SACK CEMENT.

To the Department of Mines,
Coal Owner or Operator,
Lease or Property Owner.

Gentlemen:

This "work order" is submitted for your approval and concurrence and unless notified of your disapproval or non-concurrence, the undersigned will proceed with the plugging and filling of said well in the above described manner on the date stated in the notice of intention to plug and abandon the said well on opposite side of this sheet.

Very truly yours,

Well Operator.

No objections have been filed by the coal owner or coal operator, or any available adjacent lease or property owners or interposed by the Department of Mines to the manner herein described for the plugging and filling of the well above mentioned. Therefore, the same is hereby approved this.....day of....., 193.....

DEPARTMENT OF MINES
Oil and Gas Division

09/22/2023

By:

NOTE: This "work order" must be filed in duplicate, one copy for the files of the Department of Mines and the other to be approved or corrected and returned to the well operator as his authority for plugging said well.

NOTICE OF INTENTION TO PLUG AND ABANDON WELL

(REQUIRED BY SECTION 9, ARTICLE 4, CHAPTER 22 OF THE CODE)

WEST VIRGINIA DEPARTMENT OF MINES

OIL AND GAS DIVISION

To THE DEPARTMENT OF MINES,
Charleston, W. Va.

J. W. Dawson
COAL OPERATOR OR COAL OWNER

Rfd # 2 - New Martinsville
ADDRESS

Her Lee Oil Co.
NAME OF WELL OPERATOR

Parkersburg, W. Va.
COMPLETE ADDRESS

Oct. 29 19 *29*

COAL OPERATOR OR COAL OWNER

WELL TO BE ABANDONED

ADDRESS

Green District

LEASE OR PROPERTY OWNER

Wetzel County

ADDRESS

Well No. *1*

J. W. Dawson Farm

Gentlemen:—


The undersigned well operator is about to abandon the above described well and will commence the work of plugging and abandoning said well on the *4th* day of *November*, 19 *39*, (which date shall not be less than five days after the day on which this notice so mailed is received, or in due course should be received by the Department of Mines).

This notice is given you in order that your respective representatives may be present at the plugging and filling of said well. You are further notified that whether you are represented or not represented the undersigned will proceed on that date, or shortly thereafter, to plug and fill said well in the manner required by Section 10, Article 4, Chapter 22 of the Code and given in detail on the reverse side of this notice, in "Work Order."

This notice is being mailed by registered mail to each of you at the above addresses on the above date.

Very truly yours,

C. B. Smith
Well Operator.



NOTE: Upon the abandonment of all wells drilled prior to June 1, 1929, a plat prepared by a competent engineer, showing the district and county in which the tract of land is located, the name and acreage of said tract, the names of the owners of adjacent tracts, and the location of the about to be abandoned well, determined by survey, and the courses and distances of such well from two permanent points or landmarks on said tract, shall be submitted with this notice.

(Over)

net-232-B

09/22/2023

