

STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION

NOTICE OF PROPOSED LOCATION OF OIL AND GAS WELL

To THE DEPARTMENT OF MINES,
Charleston, W. Va.

M. P. Wells
COAL OPERATOR OR COAL OWNER
New Martinsville, W. Va.
ADDRESS

M. P. Wells
COAL OPERATOR OR COAL OWNER
New Martinsville, W. Va.
ADDRESS

M. P. Wells
OWNER OF MINERAL RIGHTS
New Martinsville, W. Va.
ADDRESS

see tracing

S. J. BRENDEL
NAME OF WELL OPERATOR
565 Union Trust Building
Pittsburgh, Pa.
COMPLETE ADDRESS

March 28, 1934
PROPOSED LOCATION

Proctor District

Wetzel County

Well No. 2

M. P. Wells Farm

GENTLEMEN:

The undersigned well operator is entitled to drill upon the above named farm or tract of land for oil and gas, having fee title thereto, (or as the case may be) under grant or lease dated 18th June 20, 1938, made by M. P. Wells and Wife, to S. J. Brendel, and recorded on the 12th day of July 1938, in the office of the County Clerk for said County in Book 32A, page 439.

The enclosed plat was prepared by a competent engineer and shows the proposed location of a well to be drilled for oil and gas by the undersigned well operator on the farm and in the Magisterial District and County above named, determined by survey and courses and distances from two permanent points, or land marks.

The undersigned well operator is informed and believes there are no coal operators operating beds of coal beneath said farm or tract of land on which said well is located, or within 500 feet of the boundaries of the same, who have mapped their workings and filed their maps as required by law, excepting the coal operators or coal owners (if any) above named as addressees.

The above named coal operators or coal owners (if any) are notified that any objections they may desire to make to such proposed location, or which they are required to make by Section 3 of said Code, if the drilling of a well at said proposed location will cause a dangerous condition in or about their respective coal mines, must be received by, or filed with the Department of Mines within ten* days from the receipt of a copy of this notice and accompanying plat by said Department. Said coal operators are further notified that forms for use in making such objections will be furnished to them by the Department of Mines promptly on request and that all such objections must set forth as definitely as is reasonably possible the ground or grounds on which such objections are based and indicate the direction and distance the proposed location should be moved to overcome same.

(The next paragraph is to be completed only in Department's copy.)

Copies of this notice and the enclosed plat were mailed by registered mail, or delivered to the above named coal operators or coal owners at their above shown respective address _____ day _____ before, or on the same day with the mailing or delivery of this copy to the Department of Mines at Charleston, West Virginia.

Very truly yours,

S. J. Brendel

WELL OPERATOR

565 Union Trust Building

STREET

Pittsburgh, Pa.

CITY OR TOWN

STATE

Address of Well Operator }

09/22/2023

*Section 3 If no such objections be filed or be found by the department of mines, within said period of ten days from the receipt of said notice and plat by the department of mines, to said proposed location, the department shall forthwith issue to the well operator a drilling permit reciting the filing of such plat, that no objections have been made by the coal operators to the location, or found thereto by the department, and that the same is approved and the well operator authorized to proceed to drill at said location.

236



STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION

NOTICE OF PROPOSED LOCATION OF OIL AND GAS WELL

To The Department of Mines
Charleston, W. Va.

THE MANUFACTURERS LIGHT AND HEAT COMPANY

800 UNION TRUST BUILDING
PITTSBURGH, PENNSYLVANIA

COAL OPERATOR OR COAL OWNER

ADDRESS

JULY 10, 1933

PROPOSED LOCATION

COAL OPERATOR OR COAL OWNER

ADDRESS

District

County

Well No. Foreign Well F-10823

OWNER OF MINERAL RIGHTS

ADDRESS

Farm M. P. Wells

Government

The undersigned well operator is advised to drill upon the above named farm or tract of land for oil and gas, having for this purpose, for as the case may be, under grant or lease dated

March 27, 1933, made by M. P. Wells and Alice Wells to THE MANUFACTURERS LIGHT AND HEAT COMPANY, and recorded on the 1st day

of May, 1933, in the office of the County Clerk for said County in Book 10-A, page 23

The enclosed plat was prepared by a competent engineer and shows the proposed location of a well to be drilled for oil and gas by the undersigned well operator on the farm and in the Mineral District and County above named, determined by survey and courses and distances from two permanent points on land marked.

The undersigned well operator is informed and believes there are no coal operators operating both a coal mine and land on which said well is located, or within 500 feet of the boundary of the same, who have mapped their workings and filed their maps as required by law, excepting the coal operators (if any) above named as addressees.

The above named coal operators or coal owners (if any) are notified that any objections they may desire to make to such proposed location, of which they are required to make by Section 3 of said Code, if the drilling of a well at said proposed location will cause a dangerous condition in or about their respective coal mines, must be received by or filed with the Department of Mines within ten days from the receipt of a copy of this notice and accompanying plat by said Department. Said coal operators are further notified that failure to so in making such objections will be deemed to be a consent to the proposed location, or on request and that all such objections must set forth as definitely as is reasonably possible the ground or grounds on which such objections are based and indicate the direction and distance the proposed location should be moved to overcome same.


(The next paragraph is to be completed only in Department's copy.)
Copies of this notice and the enclosed plat were mailed by registered mail, or delivered to the above named coal operators or coal owners at their above shown respective addresses _____ day _____ before or on the same day with the mailing or delivery of this copy to the Department of Mines at Charleston, West Virginia.

Very truly yours,

THE MANUFACTURERS LIGHT AND HEAT COMPANY
LAND AGENT

800 UNION TRUST BUILDING
PITTSBURGH, PENNSYLVANIA

Address
of
Well Operator



09/22/2023

If no such objections be filed or so found by the Department of Mines within said period of ten days from the receipt of said notice and plat by the Department of Mines, the Department shall authorize a drilling permit covering the tract of land plat that no objections have been made by the coal operators to the location, or found thereby by the Department, and that the same is approved and the well operator authorized to proceed to drill at said location.

Permit Number 107-230-H

A-10

SAMUEL J. BRENDEL
OIL AND GAS PROPERTIES
UNION TRUST BUILDING
PITTSBURGH, PENNA.

March 14, 1940

Marie E. Griffith, Secretary
Oil & Gas Division
Department of Mines
Charleston, West Virginia


Dear Madam:

Under date of March 16, 1939 your office issued Permit No. WET-221 which granted S. J. Brendel the right to drill a well for oil and gas on the M. P. Wells Farm in Proctor District, Wetzel County, West Virginia. The drilling of the well was postponed and the drilling permit expired by term. We advised your office in our letter of October 12, 1939 that Mr. Brendel proposed drilling the well at a later date.

A new location has now been made on the Tract in question and I am attaching a copy of the plat which was formerly filed with your Department. You will note thereon that the new location has been staked 300' south of north and 300' west of east.


We wish to apply for a drilling permit as required by the laws of West Virginia and would appreciate your favorable consideration in that regard. For your information, we contemplate going forward with the drilling of the well just as soon as the drilling permit is obtainable.

Very truly yours,



C. M. Whitehead

Attachment
CMW:IA



09/22/2023

10/10/23

SAMUEL J. BRENDEN
ATTORNEY AT LAW
1000 BROADWAY
NEW YORK, NY 10018

09/22/2023

A-11
March 16, 1940

Mr. C. M. Whitehead
Care of Samuel J. Brendel
Oil & Gas Properties
Union Trust Building
Pittsburgh, Pennsylvania

Dear Sir:

We are in receipt of your letter of March 14th requesting renewal of permit Wet-221 to drill Well No. 1 on the M. P. Wells Farm, Proctor District, Wetzel County.

The blue print accompanying your letter shows a revised location of this well and we are returning the original tracing to have the revised location properly shown thereon. As the tracings are reproduced, the blue print with the pencil markings is not clear enough for this purpose.

Please show the revised location tied in to two permanent landmarks and return tracing as soon as possible.

Very truly yours,

Secretary
OIL AND GAS DIVISION

MG/am
enc-1

09/22/2023

A-1W

OFFICE OF
J. M. COCHRAN
COUNTY SURVEYOR, WETZEL COUNTY
PORTERS FALLS, W. VA.

March 25th; 1940,

Department of Mines,
Charleston, West Virginia;

Dear Sirs-:

Inclosed herewith you will find drawing and blue print of the M. P. Wells, farm in Proctor District, Wetzel County, on which the S. J. Brindle, Company, contemplates drilling for oil and gas.

It seems that they have decided to drill their No. 2 well first.

On March 20th; 1940, we went upon the premises and checked this location in as shown on the drawing.

I had previously made this survey of the farm and checked in their No. location.

Yours very truly

J. M. Cochran



09/22/2023

B-2

| Formation | Color | Hard or Soft | Top | Bottom | Oil, Gas or Water | Depth Found | Remarks |
|----------------------|-------|--------------|-------|--------|-------------------|-------------|--------------------------|
| Lime | | | 1065' | 1080' | | | |
| Slate | | | 1080' | 1090' | | | |
| Lime | | | 1090' | 1164' | | | |
| Pgh Coal | | | 1164' | 1170' | | | |
| Lime | | | 1170' | 1190' | | | (Steel Line Measurement) |
| Slate | | | 1190' | 1200' | | | |
| Lime | | | 1200' | 1230' | | | |
| Red Rock | | | 1230' | 1240' | | | |
| Lime | | | 1240' | 1260' | | | |
| Sand | | | 1260' | 1275' | | | |
| Slate | Dark | Soft | 1275' | 1300' | | | |
| Gritty Lime | White | Hard | 1300' | 1350' | | | |
| Shale | Gray | Soft | 1350' | 1360' | | | |
| Red Rock | Red | Soft | 1360' | 1400' | | | |
| Slate | Gray | Soft | 1400' | 1430' | | | |
| Lime | White | Hard | 1430' | 1460' | | | |
| Slate | Gray | Hard | 1460' | 1495' | | | |
| L. Dunkard | Gray | Hard | 1495' | 1510' | | | |
| Lime | White | Hard | 1510' | 1540' | | | |
| Slate | Dark | Soft | 1540' | 1625' | | | |
| B. Dunkard | White | Hard | 1625' | 1650' | | | |
| Lime | White | Soft | 1650' | 1680' | | | |
| Sand | White | Soft | 1680' | 1700' | | | |
| Lime | White | Soft | 1700' | 1725' | | | |
| Sand | White | Hard | 1725' | 1740' | | | |
| Slate | Dark | Soft | 1740' | 1760' | | | |
| Sand | White | Soft | 1760' | 1820' | | | |
| Slate | Dark | Soft | 1820' | 1840' | | | |
| Sand | White | Hard | 1840' | 1860' | | | |
| Slate | Dark | Soft | 1860' | 1875' | | | |
| Sand | White | Soft | 1875' | 1935' | | | |
| Lime | Dark | Soft | 1935' | 1950' | | | |
| Slate | White | Hard | 1950' | 1965' | | | |
| Lime - Sand | Dark | Soft | 1965' | 2115' | | | |
| Slate | Gray | Hard | 2115' | 2140' | | | |
| Sand | Dark | Soft | 2140' | 2160' | | | |
| Slate | Dark | Hard | 2160' | 2195' | | | |
| Lime | Dark | Soft | 2195' | 2235' | | | |
| Big Injun Sand | Dark | Hard | 2235' | 2293' | | | |
| Slate | Light | Hard | 2293' | 2568' | | | |
| Slate & Shells | Dark | Soft | 2568' | 2600' | | | |
| Pink Rock | | | 2600' | 2995' | | | |
| Shells, Lime & Slate | | | 2995' | 3000' | | | |
| Sand | | | 3000' | 3129' | | | |
| Slate | | | 3129' | 3153' | | | |
| Gordon Sand | | | 3153' | 3178' | | | |
| Slate | | | 3178' | 3192' | | | |
| Total Depth | | | 3192' | 3198' | | | |
| | | | | 3198' | | | |

1488' - 8 1/4"

2169' - 6 7/8"

Gas at 3129' - 3153' (shows)

Gas -

3186' - 3189'

09/22/2023

Date August 8th, 19.40

APPROVED S. J. BRENDEN, Owner

By E. M. Whithead (Title) Land Dept.

STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION

Littleton

WELL RECORD

Oil or Gas Well (Kind) Gas


Permit No. WET-236

Company S. J. Brendel
Address 565 Union Trust Bldg - Pittsburgh, Pa.
Farm Bachman Heirs Acres 67
Location (waters) _____
Well No. 2 Elev. 1318'
District Proctor County Wetzel
The surface of tract is owned in fee by Beachner Bros.
Address New Martinsville.
Mineral rights are owned by M. P. Wells - New-
Address Martinsville, W.Va.
Drilling commenced May 9, 1940
Drilling completed August 1, 1940
Date shot (Not shot) Depth of shot _____
Open Flow /10ths Water in _____ Inch
_____ /10ths Merc. in _____ Inch
Volume 190,000 Cu. Ft.
Rock Pressure 960 lbs. 40 hrs.
Oil None bbls., 1st 24 hrs.
Fresh water 245 feet 248 feet
Salt water _____ feet _____ feet

| Casing and Tubing Size | Used in Drilling | Left in Well | Packers |
|------------------------|------------------|--------------|----------------|
| 16 | | | Kind of Packer |
| 13 | | | |
| 10 | 320'-11" | All | Size of |
| 8 1/4 | 1487'-8" | All | |
| 6 5/8 | 21168'-7" | All | Depth set |
| 5 3/16 | | | |
| 3 | 3190' | All | Perf. top |
| 2 | | | Perf. bottom |
| Liners Used | | | Perf. top |
| | | | Perf. bottom |

CASING CEMENTED _____ SIZE _____ No. Ft. _____ Date _____
COAL WAS ENCOUNTERED AT 1164 FEET to INCHES
1170 FEET INCHES FEET INCHES
FEET INCHES FEET INCHES

| Formation | Color | Hard or Soft | Top | Bottom | Oil, Gas or Water | Depth Found | Remarks |
|------------------|-------|--------------|-------|--------|-------------------|-------------|-----------------------|
| Shale | | Soft | 14' | 14' | | | |
| Soap Stone | | | 30' | 30' | | | |
| Red Rock | | | 40' | 40' | | | |
| Lime | | | 70' | 70' | | | |
| Slate | | | 100' | 100' | | | |
| Lime | | | 150' | 150' | | | |
| Sand | | | 200' | 200' | | | |
| Red Rock | | | 225' | 225' | | | |
| Slate | | | 240' | 240' | | | |
| Gritty Lime | | | 240' | 250' | Water from | | |
| Red Rock | | | 250' | 260' | 245'-248' | | (13 Bailers per Hour) |
| Lime | | | 260' | 285' | | | |
| Slate | | | 285' | 325' | | | |
| Lime | | | 350' | 375' | | | |
| Red Rock | | | 375' | 400' | | | |
| Shale | | | 400' | 425' | | | |
| Lime | | | 425' | 445' | | | |
| Slate | | | 445' | 460' | | | |
| Red Rock | | | 460' | 485' | | | |
| Slate | | | 485' | 500' | | | |
| Sand | | | 500' | 520' | | | |
| Slate | | | 520' | 540' | | | |
| Lime | | | 540' | 560' | | | |
| Red Rock | | | 560' | 590' | | | |
| Sand | | | 590' | 615' | | | |
| Slate | | | 615' | 635' | | | |
| Lime | | | 635' | 675' | | | |
| Red Rock | | | 675' | 690' | | | |
| Lime & Slate | | | 690' | 745' | | | |
| Red Rock | | | 745' | 755' | | | |
| Lime | | | 755' | 825' | | | |
| Slate & Red Rock | | | 825' | 850' | | | |
| Lime | | | 850' | 875' | | | |
| Slate | | | 875' | 890' | | | |
| Lime | | | 890' | 910' | | | |
| Sand | | | 910' | 920' | | | |
| Slate | | | 920' | 930' | | | |
| Lime | | | 930' | 966' | | | |
| Slate | | | 966' | 975' | | | |
| Lime | | | 975' | 1051' | | | |
| Mapletown Coal | | | 1051' | 1055' | | | |
| Slate | | | 1055' | 1065' | | | |



09/22/2023

Table with 8 columns: Formation, Color, Hard or Soft, Top, Bottom, Oil, Gas or Water, Depth Found, Remarks. The table contains various entries with handwritten notes and a large circular stamp in the center.



09/22/2023

Date August 22, 19 56
APPROVED THE MANUFACTURERS LIGHT AND HEAT CO, Owner
By [Signature] LAND AGENT

B-3



STATE OF WEST VIRGINIA DEPARTMENT OF MINES OIL AND GAS DIVISION

Quadrangle Littleton

Permit No. WET-236-R

WELL RECORD


Oil or Gas Well Gas
(KIND)

Company THE MANUFACTURERS LIGHT AND HEAT COMPANY
 Address 800 Union Trust Building, Pgh., Pa.
 Farm M. P. Wells Acres 60
 Location (waters) _____
 Well No. F-16823 Elev. 1318'
 District Proctor County Wetzel
 The surface of tract is owned in fee by _____
 Address _____
 Mineral rights are owned by _____
 Address _____
 Drilling commenced October 14, 1953
 Drilling completed July 31, 1956
 Date Shot _____ From _____ To _____
 With _____
 Open Flow 0/10ths Water in 3/8 Inch
 _____/10ths Merc. in _____ Inch
 Volume 6.000 Cu. Ft.
 Rock Pressure _____ lbs. _____ hrs.
 Oil _____ bbls., 1st 24 hrs.
 Fresh water _____ feet _____ feet
 Salt water _____ feet _____ feet

| Casing and Tubing | Used in Drilling | Left in Well | Packers |
|-------------------|------------------|--------------|----------------|
| Size | | | Kind of Packer |
| 16 | | | |
| 13 | | | |
| 10 | 347' 11" | 347' 11" | Size of |
| 8 1/4 | | 1397' 3" | |
| 6 5/8 | | | Depth set |
| 5 3/16 | | 2172' 1" | |
| 3 | | | Perf. top |
| 2 | | | Perf. bottom |
| Liners Used | | | Perf. top |
| | | | Perf. bottom |

CASING CEMENTED _____ SIZE _____ No. Ft. _____ Date _____
 COAL WAS ENCOUNTERED AT _____ FEET _____ INCHES
 _____ FEET _____ INCHES _____ FEET _____ INCHES
 _____ FEET _____ INCHES _____ FEET _____ INCHES

| Formation | Color | Hard or Soft | Top | Bottom | Oil, Gas or Water | Depth Found | Remarks |
|--------------------|-------|--------------|------|--------|--|-------------|---------|
| Clg. out to | | | | 2295 | Schlumberger | Measurement | |
| Filled with stone | | | 2295 | 2235 | | | |
| Filled with cement | | | 2235 | 2200 | 10 3/4" Casing set at 345'9" cemented with 200 bag cement. Good return to surface | | |
| TOTAL DEPTH: | | | | 2200 | | | |
| Maxton Sand | | | 2152 | 2200 | 8 5/8" Casing set at 1386'3" cemented with 400 bag cement and 10 bag Gel. No return. | | |
| | | | | | 5 1/2" Casing set at 2155'3" cemented with 400 bag cement. No return. | | |
| | | | | | 15 - bags cement run from the top between 8" and 10" Casing. | | |
| | | | | | 365 - bags of cement run from top between 5 1/2" and 8" casing. | | |



09/22/2023

B-4

STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION

INSPECTOR'S WELL REPORT

Storage Gas


Permit No. WET-236-R

Oil or Gas Well
(KIND)

| | | CASING AND TUBING | USED IN DRILLING | LEFT IN WELL | PACKERS |
|------------------------|-------------------------------------|-------------------------|------------------|--------------|----------------|
| Company | <u>Migsight and Heat Co</u> | | | | |
| Address | <u>Pittsburgh Pa</u> | Size | | | |
| Farm | <u>M. P. Wells</u> | 16 | | | Kind of Packer |
| Well No. | <u>F 16823</u> | 13 | | | |
| District | <u>Proctor</u> County <u>Netzel</u> | 10 | | | Size of |
| Drilling commenced | | 8 1/4 | | | |
| Drilling completed | Total depth <u>2000'</u> | 6 5/8 | | | Depth set |
| Date shot | Depth of shot | 5 3/16 | | | Perf. top |
| Initial open flow | /10ths Water in Inch | 3 | | | Perf. bottom |
| Open flow after tubing | /10ths Merc. in Inch | 2 | | | Perf. top |
| Volume | Cu. Ft. | Liners Used | | | Perf. bottom |
| Rock pressure | lbs. hrs. | | | | |
| Oil | bbls., 1st 24 hrs. | CASING CEMENTED | SIZE | No. FT. | Date |
| Fresh water | feet feet | | | | |
| Salt water | feet feet | COAL WAS ENCOUNTERED AT | FEET | INCHES | |
| | | | FEET | INCHES | FEET INCHES |
| | | | FEET | INCHES | FEET INCHES |

Drillers' Names L. E. Haugh & L. E. Haugh Jr.

Remarks: Reading out at 2000'



9-1-54

DATE

Byron Shuman

DISTRICT WELL INSPECTOR

09/22/2023

STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION
INSPECTOR'S PLUGGING REPORT

Permit No. 236-R

Well No. _____

COMPANY _____ ADDRESS _____

FARM _____ DISTRICT _____ COUNTY _____

Filling Material Used _____

| Liner | | | Packer | | | | |
|-----------------------------|-----------|--------|-----------------------|--|-------------------|------|------|
| Location | | Amount | Location | | Location | | |
| PLUGS USED AND DEPTH PLACED | | | BRIDGES | | CASING AND TUBING | | |
| CEMENT-THICKNESS | WOOD-SIZE | LEAD | CONSTRUCTION-LOCATION | | RECOVERED | SIZE | LOST |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |

Drillers' Names _____

Remarks: _____

_____ I hereby certify I visited the above well on this date.
DATE

DISTRICT WELL INSPECTOR
09/22/2023

B-5

STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION

INSPECTOR'S WELL REPORT


Permit No. 236 R

Oil or Gas Well (KIND) Storage

| Company | CASING AND TUBING | USED IN DRILLING | LEFT IN WELL | PACKERS |
|---|---|------------------|--------------|----------------|
| <u>M.P.R.'s Light & Heat Co</u> | Size | | | |
| <u>Pittsburgh PA</u> | 16 | | | Kind of Packer |
| <u>M. P. Wells</u> | 13 | | | |
| <u>R 16823</u> | 10 | | | Size of |
| District <u>Proctor</u> County <u>Wetzel</u> | 8 1/4 | | | |
| Drilling commenced <u>1953</u> | 6 5/8 | | | Depth set |
| Drilling completed <u>Total depth 2048</u> | 5 3/16 | | | |
| Date shot _____ Depth of shot _____ | 3 | | | Perf. top |
| Initial open flow _____ /10ths Water in _____ Inch | 2 | | | Perf. bottom |
| Open flow after tubing _____ /10ths Merc. in _____ Inch | Liners Used | | | Perf. top |
| Volume _____ Cu. Ft. | | | | Perf. bottom |
| Rock pressure _____ lbs. _____ hrs. | CASING CEMENTED _____ SIZE _____ No. FT. _____ Date | | | |
| Oil _____ bbls., 1st 24 hrs. | COAL WAS ENCOUNTERED AT _____ FEET _____ INCHES | | | |
| Fresh water _____ feet _____ feet | _____ FEET _____ INCHES _____ FEET _____ INCHES | | | |
| Salt water _____ feet _____ feet | _____ FEET _____ INCHES _____ FEET _____ INCHES | | | |

Drillers' Names E. Whipkey and Henry Caldwell

Remarks: Drilling by Tools.



8 24 55
DATE

[Signature]
DISTRICT WELL INSPECTOR

09/22/2023

STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION

INSPECTOR'S PLUGGING REPORT

Permit No. _____ Well No. _____

COMPANY _____ ADDRESS _____

FARM _____ DISTRICT _____ COUNTY _____

Filling Material Used _____

Liner _____ Location _____ Amount _____ Packer _____ Location _____

| PLUGS USED AND DEPTH PLACED | | | BRIDGES | CASING AND TUBING | | |
|-----------------------------|-----------|------|-----------------------|-------------------|------|------|
| CEMENT-THICKNESS | WOOD-SIZE | LEAD | CONSTRUCTION-LOCATION | RECOVERED | SIZE | LOST |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Drillers' Names _____

Remarks: _____

_____ I hereby certify I visited the above well on this date.
DATE

DISTRICT WELL INSPECTOR

09/22/2023

2
B-9

PROPOSED MANNER OF PLUGGING AND FILLING WELL

(REQUIRED BY RULES AND REGULATIONS)

**WEST VIRGINIA DEPARTMENT OF MINES
OIL AND GAS DIVISION**

WORK ORDER

Well to be plugged and filled as follows:

Fill with mud and clay from 3198' back to 3129'
Place suitable wooden plug and cement - 10'
Fill with mud and clay - cement bridge at 2429'
Remove 6-5/8" casing at 2116'
Fill with mud and clay to 1480' - remove 8-1/4" casing
Place a plug at casing seat
Fill with mud and clay to 1214' - cement 1164'
Fill with mud and clay to 1050' - cement coal
Fill with mud and clay to 320' - place wooden plug and cement
Fill to the top with mud and clay
Erect concrete marker

WORK ORDER INTERPOSED BY THE DEPARTMENT OF MINES:

Total Depth 3198'
Fill with red clay from 3198' - 3109' - 20' above top Gas show
Wood Plug 3109' - 3106'
Neat Cement 3106' - 3096' - Sealing off all gas.
Continue filling with red clay from 3096' - 2245' - 10' below top of Big Lime.
Wood Plug 2245' - 2242'
Neat cement 2242' - 2232' - Sealing hole completely below 6-5/8" casing.
Pull 2169' - 6-5/8" casing.

Continue as original Work Order to 1200' - 30' below Pittsburgh Coal.

Cement 1200' - 1144' - 20' above Pittsburgh Coal.
Red Clay 1144' - 1085' - 30' below Mapletown Coal.
Cement 1085' - 1031' - 20' above Mapletown Coal.
Fill with red clay 1031' - 341' - 20' below 10" casing.
Wood Plug 341' - 338'
Cement 338' - 328' - Sealing hole below largest casing.
Red Clay 328' - to surface.
Erect marker such as is required by Rule 18, 1931 Regulations.


NOTE: CEMENT FOR MAKING CEMENT PLUGS BE MIXED WITH WATER ONLY--APPROXIMATELY FIVE GAL WATER TO ONE SACK CEMENT. ALLOW CEMENT TO SET BEFORE CONTINUING FILLING.

To the Department of Mines
Coal Owner or Operator,
Lease or Property Owner.

Gentlemen:

This "work order" is submitted for your approval and concurrence and unless notified of your disapproval or non-concurrence, the undersigned will proceed with the plugging and filling of said well in the above described manner on the date stated in the notice of intention to plug and abandon the said well on opposite side of this sheet.

Very truly yours,



Well Operator.

No objections have been filed by the coal owner or coal operator, or any available adjacent lease or property owners or interposed by the Department of Mines to the manner herein described for the plugging and filling of the well above mentioned. Therefore, the same is hereby approved this.....8th.....day

of.....February....., 19.41.....

DEPARTMENT OF MINES 09/22/2023
Oil and Gas Division

By:.....

NOTE: This "work order" shall be filed in triplicate, one copy for the files of the Department of Mines; one to be approved or corrected and returned to the well operator as his authority for plugging said well; and one for the well inspector.

STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION

NOTICE OF INTENTION TO PLUG AND ABANDON WELL

(REQUIRED BY SECTION 9, ARTICLE 4, CHAPTER 22 OF THE CODE)

To THE DEPARTMENT OF MINES,
Charleston, W. Va.

M. P. Wells

COAL OPERATOR OR COAL OWNER

New Martinsville, W. Va.

ADDRESS

COAL OPERATOR OR COAL OWNER

ADDRESS

M. P. Wells

LEASE OR PROPERTY OWNER

New Martinsville, West Va.

ADDRESS

S. J. Brendel

NAME OF WELL OPERATOR

565 Union Trust Bldg
Pittsburgh, Penna.

COMPLETE ADDRESS

February 12th 19 41

WELL TO BE ABANDONED

Proctor District

Wetzel County

Well No. 2

Bachman Heirs Farm


Gentlemen:—

The undersigned well operator is about to abandon the above described well and will commence the work of plugging and abandoning said well on the 13th day of February, 19 41, (which date shall not be less than five days after the day on which this notice so mailed is received, or in due course should be received by the Department of Mines.)

This notice is given you in order that your respective representatives may be present at the plugging and filling of said well. You are further notified that whether you are represented or not represented the undersigned will proceed on that date, or shortly thereafter, to plug and fill said well in the manner required by Section 10, Article 4, Chapter 22 of the Code and given in detail on the reverse side of this notice, in "Work Order."

This notice is being mailed by registered mail to each of you at the above addresses on the above date.

Very truly yours,



S. J. Brendel
Well Operator.

NOTE: Upon the abandonment of all wells drilled prior to June 1, 1929, a plat prepared by a competent engineer, showing the district and county in which the tract of land is located, the name and acreage of same, the names of the owners and adjacent tracts, and the location of the about to be abandoned well, as determined by survey, and the courses and distances of such well from two permanent points or landmarks on said tract, shall be submitted with this notice.

(Over)

WET-236-P

PERMIT NUMBER

wet-236-P

0982/2023

STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, ONE COPY MAILED TO THE DEPARTMENT, ONE COPY TO BE RETAINED BY THE WELL OPERATOR AND THE THIRD COPY (AND EXTRA COPIES IF REQUIRED) SHOULD BE MAILED TO EACH COAL OPERATOR AT THEIR RESPECTIVE ADDRESSES.

| | |
|--|--|
| <p><u>M. P. Wells</u> COAL OPERATOR OR OWNER <u>New Martinsville, West Va.</u> ADDRESS <u>Same</u></p> | <p><u>S. J. Brendel</u> NAME OF WELL OPERATOR <u>565 Union Trust Bldg</u> <u>Pittsburgh Penna</u> COMPLETE ADDRESS <u>February 12th</u> 194<u>1</u> WELL AND LOCATION <u>Procter</u> District <u>Wetzel</u> County</p> |
| <p>COAL OPERATOR OR OWNER ADDRESS <u>Same</u></p> | <p>Well No. <u>2</u></p> |
| <p>LEASE OR PROPERTY OWNER ADDRESS</p> | <p><u>Bachman Heirs</u> Farm</p> |


STATE INSPECTOR SUPERVISING PLUGGING Not present

AFFIDAVIT

STATE OF WEST VIRGINIA, }
County of WETZEL } SS:

A. G. Isiminger and W. M. Ernest
being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by A. G. Isiminger (S. J. Brendel) well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 12th day of February, 1941, and that the well was plugged and filled in the following manner:

| SAND OR ZONE RECORD | FILLING MATERIAL | | | PLUGS USED | CASING | |
|---------------------------------------|------------------------------------|---------|------------|---------------------------------------|--------|------------|
| | FORMATION | CONTENT | FROM | | TO | CSG PULLED |
| Total Depth - 3198' | Red Clay | 3198' | 3109' | (20' above top Gas Show) | | |
| | | 3109' | 3106' | Wood Plug | | |
| | Neat Cement | 3106' | 3096' | (Sealing off gas) | | |
| | Red Clay | 3096' | 2245' | (Being 10' below top Big Lime) | | |
| | | 2245' | 2242' | Wood Plug | | |
| | Neat Cement | 2242' | 2232' | (Completely sealing hole below 6-5/8" | | |
| | Red Clay | 2232' | 1480' | (Wood Plug at Casing Seat) - 8-1/4" | | |
| | Red Clay | 1480' | 1200' | (30' below Pgh. Coal) | | |
| | Cement | 1200' | 1144' | (20' above Pgh. Coal) | | |
| | Red Clay | 1144' | 1085' | (30' below Mapletown Coal) | | |
| | Cement | 1085' | 1031' | (20' above Mapletown Coal) | | |
| | Red Clay | 1031' | 341' | (20' below 10" casing) | | |
| | | 341' | 338' | Wood Plug | | |
| | Cement | 338' | 328' | (Sealing hole below 10") | | |
| | Red Clay | 328' | to Surface | | | |
| COAL SEAMS | DESCRIPTION OF MONUMENT | | | | | |
| (NAME) <u>Cemented as above noted</u> | <u>Concrete marker as required</u> | | | | | |
| (NAME) | <u>by 1931 Regulations</u> | | | | | |
| (NAME) | | | | | | |
| (NAME) | | | | | | |



and that the work of plugging and filling said well was completed on the 22nd day of February, 1941.

And further deponents saith not.

A. G. Isiminger 09/22/2023
W. M. Ernest

Sworn to and subscribed before me this 19th day of February, 1942.

J. P. [Signature]
Notary Public.

My commission expires:
December 1st 1945

Permit No. WET-236-P

64
April 7, 1940

Mr. S. J. Brendel
565 Union Trust Building
Pittsburgh, Pennsylvania

Dear Sir:

Permit WET-236 to drill Well No. 2 on the
M. F. Wells Farm, Proctor District, Wetzel County, is
enclosed.

Duplicate permit shall be posted on the rig.

When the well is completed, please file complete
record on the enclosed forms OC-10.

Very truly yours,


Secretary
OIL AND GAS DIVISION

MC/am
enc-4

09/22/2023

SAMUEL J. BRENDEL
OIL AND GAS PROPERTIES
UNION TRUST BUILDING
PITTSBURGH, PENNA.

February 4, 1941



Marie E. Griffith, Secretary
Oil & Gas Division
Bureau of Mines
Charleston, West Virginia

Dear Madam:


Under date of April 7, 1940 your Department issued Drilling Permit No. WET-236 to S. J. Brendel covering Well No. 2 located on the M. P. Wells farm in Proctor District, Wetzel County, West Virginia. The well in question was drilled and your Department was furnished a copy of the well location. The well produced some gas from the Gordon sand formation, but the volume has since reduced to the point where the operation of the well is no longer profitable.

Complying with the regulations of your Department, application if herein made for necessary plugging permit so that we may proceed with the work at an early date. Your approval of this request will be greatly appreciated.

Very truly yours,


C. M. Whitehead

CMW: IA



Company L. J. Brendel Co.
 Address Pittsburgh Pa.
 Farm M. P. Wells
 Tract One Acres 67 Lease No. _____
 Well (Farm) No. One Serial No. _____
 Elevation (Spirit Level) 1266, 1318 Ft.
 Quadrangle Littleton
 County Netel District Proctor
 Engineer J. M. Cochran
 Engineer's Registration No. Co. Surveyor
 File No. _____ Drawing No. _____
 Date Feb. 20, 1939 Scale 1-inch = 20 Fds.

STATE OF WEST VIRGINIA
 DEPARTMENT OF MINES
 OIL AND GAS DIVISION
 CHARLESTON

WELL LOCATION MAP
 FILE NO. WET-221
WET-230 02/22/2023
 WELL #2

+ Denotes location of well on United States Topographic Maps, scale 1 to 62,500, latitude and longitude lines being represented by border lines as shown.
 - Denotes one inch spaces on border line of original tracing.

