

STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION

NOTICE OF PROPOSED LOCATION OF OIL AND GAS WELL

To THE DEPARTMENT OF MINES,
Charleston, W. Va. *cc. to*

J. Littleton Dawson
COAL OPERATOR OR COAL OWNER
Uniontown Pa
ADDRESS

S. J. BRENDEL
NAME OF WELL OPERATOR

565 UNION TRUST BLDG., PITTSBURGH, PA.
COMPLETE ADDRESS

DECEMBER 8, 1941

PROPOSED LOCATION

PROCTOR District

WETZEL County

Well No. *39° 45'*
80' 40' ONE (1)

THURMAN L. GODDARD Farm

GENTLEMEN:

The undersigned well operator is entitled to drill upon the above named farm or tract of land for oil and gas, having fee title thereto, (or as the case may be) under grant or lease dated FEB. 13, 1941 Assignment, made by W. M. EARNEST & A. G. ISMINGER, to S. J. BRENDEL, 565 UNION TRUST BLDG., PITTSBURGH, PA., and recorded on the 16TH day of JULY, 1941, in the office of the County Clerk for said County in Book 35A, page 260.

The enclosed plat was prepared by a competent engineer and shows the proposed location of a well to be drilled for oil and gas by the undersigned well operator on the farm and in the Magisterial District and County above named, determined by survey and courses and distances from two permanent points, or land marks.

The undersigned well operator is informed and believes there are no coal operators operating beds of coal beneath said farm or tract of land on which said well is located, or within 500 feet of the boundaries of the same, who have mapped their workings and filed their maps as required by law, excepting the coal operators or coal owners (if any) above named as addressees.

The above named coal operators or coal owners (if any) are notified that any objections they may desire to make to such proposed location, or which they are required to make by Section 3 of said Code, if the drilling of a well at said proposed location will cause a dangerous condition in or about their respective coal mines, must be received by, or filed with the Department of Mines within ten* days from the receipt of a copy of this notice and accompanying plat by said Department. Said coal operators are further notified promptly on request and that all such objections must set forth as definitely as is reasonably possible the ground or grounds on which such objections are based and indicate the direction and distance the proposed location should be moved to overcome same.

(The next paragraph is to be completed only in Department's copy.)

Copies of this notice and the enclosed plat were mailed by registered mail, or delivered to the above named coal operators or coal owners at their above shown respective address _____ day before, or on the same day with the mailing or delivery of this copy to the Department of Mines at Charleston, West Virginia.

Very truly yours,


S. J. Brendel
WELL OPERATOR

565 UNION TRUST BUILDING
STREET

PITTSBURGH
CITY OR TOWN

PENNSYLVANIA
STATE

10/13/2023



Address of Well Operator }

*Section 3 If no such objections be filed or be found by the department of mines, within said period of ten days from the receipt of said notice and plat by the department of mines, to said proposed location, the department shall forthwith issue to the well operator a drilling permit reciting the filing of such plat, that no objections have been made by the coal operators to the location, or found thereto by the department, and that the same is approved and the well operator authorized to proceed to drill at said location.

211

STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION

NOTICE OF PROPOSED LOCATION OF OIL AND GAS WELL

To The Department of Mines
Charleston, W. Va.

NAME OF WELL OPERATOR	COAL OPERATOR OR COAL OWNER
COMPLEX ADDRESS	ADDRESS
PROPOSED LOCATION	COAL OPERATOR OR COAL OWNER
DISTRICT	ADDRESS
COUNTY	OWNER OF MINERAL RIGHTS
Well No.	ADDRESS
FARM	

GENTLEMEN:

The undersigned well operator is entitled to drill upon the above named farm or tract of land for oil and gas, having fee title thereto, (or as the case may be) under grant or lease dated _____, to _____, made by _____, and recorded on the _____ day of _____, 19____, in the office of the County Clerk for said County in _____, page _____, Book _____.

The enclosed plat was prepared by a competent engineer and shows the proposed location of a well to be drilled for oil and gas by the undersigned well operator on the farm and in the Magisterial District and County above named, determined by survey and courses and distances from two permanent points or land marks.


The undersigned well operator is informed and believes there are no coal operators operating beds of coal beneath said farm or tract of land on which said well is located, or within 500 feet of the boundary of the same, who have mapped their workings and filed their maps as required by law, excepting the coal operators or coal owners (if any) above named as addressees.

The above named coal operators or coal owners (if any) are notified that any objections they may desire to make to such proposed location, or which they are required to make by Section 3 of said Code, if the drilling of a well at said proposed location will cause a dangerous condition in or about their respective coal mines, must be received by, or filed with the Department of Mines within ten days from the receipt of a copy of this notice and accompanying plat by said Department. Said coal operators are further notified that forms for use in making such objections will be furnished to them by the Department of Mines promptly on request and that all such objections must set forth as definitely as is reasonably possible the ground or grounds on which such objections are based and indicate the direction and distance the proposed location should be moved to overcome same.

(The next paragraph is to be completed only in Department's copy.)

Copies of this notice and the enclosed plat were mailed by registered mail, or delivered to the above named coal operators or coal owners at their above shown respective addresses _____ day before, or on the same day with the mailing or delivery of this copy to the Department of Mines at Charleston, West Virginia.

Very truly yours,



WELL OPERATOR

ADDRESS

CITY OR TOWN

STATE

10/13/2023

Section 3 If no such objections be filed or be found by the department of mines, within said period of ten days from the receipt of said notice and plat by the department of mines, to said proposed location, the department shall forthwith issue to the well operator a drilling permit reciting the time of such plat that no objections have been made by the coal operators to the location, or found there by the department, and that the same is approved and the well operator authorized to proceed to drill at said location.

PERMIT NUMBER

A-10

December 20, 1941

Mr. S. J. Brendel
565 Union Trust Building
Pittsburgh, Pennsylvania

Dear Sir:

Permit WET-271 to drill Well No. 1 on the
Thurman L. Coddard Farm, Proctor District, Wetzel County,
is enclosed.

Duplicate permit shall be posted on the rig.

When the well is completed, please file com-
plete record on the enclosed forms OG-10.

Very truly yours,

Secretary
OIL AND GAS DIVISION

MG/am
enc-4

CC: Inspector D. G. Courtney

10/13/2023

A-11

SAMUEL J. BRENDEL
OIL AND GAS PROPERTIES
UNION TRUST BUILDING
PITTSBURGH, PENNA.

February 9, 1942

File

Miss Marie Griffith
Bureau of Mines
Charleston, West Virginia

Dear Miss Griffith:

In compliance with the requirements of your office as regards oil and gas wells, there is enclosed herewith a log of the gas well recently drilled by S. J. Brendel on the Thurman Goddard tract situated in Proctor District, Wetzel County, West Virginia.

This well was drilled under Permit No. WET-271 issued by your department.

Very truly yours,



C. M. WHITEHEAD

CMW:mw
Encl.

10/13/2023

B-2

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks
Red Rock			1330	1350			
Lime			1350	1380			
Slate			1380	1425			
Lime Shells			1425	1435			
Slate			1435	1455			
Sand			1455	1480			
Slate			1480	1520			
Big Drunkard Sand			1520	1550			
Slate			1550	1610			
Slate			1650	1745	Gas Sand	1610-1650	
Sand			1745	1770			
Slate			1770	1775			
Sand			1775	1810			
Slate			1810	1850			
Sand Soft White			1850	1900			
Slate			1900	1985			
3rd Salt Sand			1985	2035			
Slate & Shells			2035	2120			
Blue Monday Sand			2120	2140			
Big Lime			2140	2180			
Big Injun Sand			2180	2440			
Slate			2440	2500			
Lime Shells			2500	2525			
Slate			2525	2560			
Lime Shells			2560	2600			
Slate			2600	2635			
Lime Shells			2635	2650			
Slate			2650	2690			
Lime Shells			2690	2725			
Slate Soft Black			2725	2775			
Lime			2775	2785			
Slate			2785	2825			
30-Foot Shell			2825	2865			
Slate			2865	2900			
Pink Rock			2900	2925			
Lime & Slate Shells			2925	3008			
50-Foot Shell			3008	3019			
Slate			3019	3049			
Sand Gordon			3049	3067			
Slate			3067	3090	Gas	3061-3065	357,000
Total Depth			3090				
Filled Bank to			3077				

Gas blew down to 94,000 before well was shot. 10 minutes after show - 873,000 cu. ft.
 SHUT IN - 798,000 cu. ft. Rock pressure - 1 hour, 600# - 36 hours, 1000#
 Steel Line measurement run at 3019' and 3099'

Drillers - Wm. Ernest, Ross Ernest & A. G. Isminger
 Tool Dressers - A. G. Gettings, John Morris, Lawrence Quigley

10/13/2023

Date..... February 9th, 1942.

APPROVED..... S. J. BRENDEL, Owner

By..... *[Signature]*,
 (Title) Land Dept

STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION

WELL RECORD

Permit No. WET-271

Oil or Gas Well Gas
(KIND)

Company S. J. Brendel
 Address 565 Union Trust Bldg., Pittsburgh, Pa.
 Farm Thurman Goddard Acres 59
 Location (waters) _____
 Well No. 1 Elev. _____
 District Proctor County Wetzel
 The surface of tract is owned in fee by Thurman Goddard,
et al Address Bebee, W. Va.
 Mineral rights are owned by Same
 Address Same
 Drilling commenced December 15, 1941
 Drilling completed February 4, 1942
 Date shot February 4, 1942 Depth of shot 3059'-3067'
 (Shot with 20 quarts)
 Open Flow /10ths Water in _____ Inch
 _____ /10ths Merc. in _____ Inch
 Volume 357,000 Natural (798,000 Shut In) Cu. Ft.
 Rock Pressure 1,000 lbs. 36 hrs.
 Oil _____ bbls., 1st 24 hrs.
 Fresh water _____ feet _____ feet
 Salt water _____ feet _____ feet

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			
16			Kind of Packer
13			<u>Anchor</u>
10	<u>234'</u>		Size of <u>5-3/16" X</u>
8 1/4	<u>1377'</u>	<u>1377'</u>	<u>6-5/8</u>
6 3/8	<u>2180'</u>		Depth set
5 3/16	<u>2961'</u>	<u>2961'</u>	<u>2961'</u>
3			Perf. top
2			Perf. bottom
Liners Used			Perf. top
			Perf. bottom

CASING CEMENTED _____ SIZE _____ No. Ft. _____ Date _____
 _____ None _____
 COAL WAS ENCOUNTERED AT _____ (See Log) FEET _____ INCHES
 _____ FEET _____ INCHES _____ FEET _____ INCHES
 _____ FEET _____ INCHES _____ FEET _____ INCHES

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks
Shale			-0-	14			
Grit			14	50			
Red Rock			50	60			
Shale			60	90			
Lime Gritty			90	110			
Slate Dark			110	160			
Red Rock			160	190			
Lime			190	210			
Slate			210	225			
Lime Gritty			225	240			
Red Rock			240	360			
Lime			360	380			
Slate			380	400			
Lime Gritty			400	415			
Coal Blossom			415	420			
Lime			420	435			
Red Rock			435	460			
Lime Broken			460	950			
Mepleton Coal			950	955			
Lime			955	970			
Sand			970	1000			
Lime			1000	1040			
Slate			1040	1050			
Pittsburgh Coal			1050	1057			
(Steel Line Measurement)							
Slate			1057	1065			
Lime			1065	1075			
Slate			1075	1090			
Red Rock			1090	1100			
Lime			1100	1120			
Red Rock			1120	1125			
Lime			1125	1135			
Slate Dark			1135	1150			
Lime			1150	1175			
Sand			1175	1185			
Slate			1185	1200			
Lime Shells			1200	1230			
Red Rock			1230	1245			
Lime			1245	1250			
Slate White			1250	1285			
Lime			1285	1300			
Slate			1300	1330			

10/13/2023

