

FILE NO. _____
 DRAWING NO. _____
 SCALE 1" = 1000'
 MINIMUM DEGREE OF ACCURACY 1 IN 200
 PROVEN SOURCE OF ELEVATION RD. FORKS
 831'

I THE UNDERSIGNED, HEREBY CERTIFY THAT THIS PLAT IS CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF AND SHOWS ALL THE INFORMATION REQUIRED BY LAW AND THE REGULATIONS ISSUED AND PRESCRIBED BY THE DEPARTMENT OF MINES.
 (SIGNED) David L. Mitchell
 R.P.E. _____ L.L.S. 873

PLACE SEAL HERE

WEST VIRGINIA
 DIVISION OF ENVIRONMENTAL PROTECTION
 OFFICE OF OIL AND GAS
 #10 McJUNKIN ROAD
 NITRO, WEST VIRGINIA 25143-2506



DATE 1/31/90, 19____
 OPERATOR'S WELL NO. 1669
 API WELL NO. 47-103-00836-P
 STATE COUNTY PERMIT

WELL TYPE: OIL ___ GAS X LIQUID INJECTION ___ WASTE DISPOSAL ___
 (IF "GAS,") PRODUCTION X STORAGE ___ DEEP ___ SHALLOW ___
 LOCATION: ELEVATION 1121 WATER SHED NORTH FORK OF RICHWOOD RUN
 DISTRICT GRANT COUNTY WETZEL
 QUADRANGLE BIG RUN, WV./LITTLETON SE 12 3!
 SURFACE OWNER COASTAL LUMBER CO. ACREAGE 1627.6
 OIL & GAS ROYALTY OWNER MILLS WETZEL LAND CO. LEASE ACREAGE 659
 LEASE NO. 2891
 PROPOSED WORK: DRILL ___ CONVERT ___ DRILL DEEPER ___ REDRILL ___ FRACTURE OR STIMULATE ___ PLUG OFF OLD FORMATION ___ PERFORATE NEW FORMATION ___ OTHER PHYSICAL CHANGE IN WELL (SPECIFY) _____

Plugging of Pre 1929 well drilled in 1900

was: 103 72263

PLUG AND ABANDON X CLEAN OUT AND REPLUG ___
 TARGET FORMATION BIG INJUN ESTIMATED DEPTH 2918' (T.D.)
 WELL OPERATOR EQUITRANS, INC. DESIGNATED AGENT BILL HOSTUTLER
 ADDRESS 4955 STEUBENVILLE PIKE ADDRESS P.O. BOX 1550
PITTSBURGH, PA. 15205 CLARKSBURG, WV. 26301

JUN 19 1997

DRILLER'S RECORD

Previously Requested, but NOT
AVAILABLE

DATE: _____

<u>103</u> COUNTY	<u>836</u> PERMIT
----------------------	----------------------

STATE OF WEST VIRGINIA
DIVISION OF ENVIRONMENTAL PROTECTION
SECTION OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: COASTAL LUMBER COMPANY Operator Well No.: MILLS 1669

LOCATION: Elevation: 1,121.00 Quadrangle: BIG RUN
 District: CENTER County: WETZEL
 Latitude: 11710 Feet South of 39 Deg. 35 Min. 0 Sec
 Longitude 3370 Feet West of 80 Deg. 35 Min. 0 Sec

Well Type: OIL _____ GAS X

Company: EQUITRANS, L. P. Coal Operator CONSOLIDATION COAL CO
420 BOULEVARD OF THE ALLIES or Owner P O BOX 103
PITTSBURGH PA 15275 WILMINGTON DE 19899

Agent: WILLIAM HOSTITLER Coal Operator _____
 or Owner _____

Permit Issued: 06/17/97

RECEIVED
 Environmental Protection
 DIVISION OF
 OCT 27 1997

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of WETZEL ss:

KYLE D PERKINS and ROGER L BARR being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well, and RANDAL MICK Oil and Gas Inspector representing the Director, say that said work was commenced on the _____ day of _____, 19____, and that the well was plugged and filled in the following manner:


TYPE	FROM	TO	PIPE REMOVED	LEFT
Gel	2918	2850	5 1/2 2270	0
Cement	2850	2650	6 5/8 0	652
Cement	2350	2250	8 1/4 590	773
Cement	2100	2000	10 0	356
Cement	1450	1350		
Cement	890	790	Note: perforated	8" @ 855,810
Cement	620	520	perforated 10"	@ 365,330
Cement	390	320		
Cement	180	120		
Cement	60	surface		

Description of monument: 1 joint 8" csg extending 30" above surface
and that the work of plugging and filling said well was completed on the 24th day of October, 1997.

And further deponents saith not.

Sworn and subscribe before me this 24th day of October, 1997
 My commission expires: June 7, 2000

Kyle D Perkins
Roger L Barr
[Signature]
 Notary Public



Oil and Gas Inspector: _____