

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Morrison, Billy & Rosa Operator Well No.: WV 605287 (Knisely 5287)

LOCATION: Elevation: 1262' Quadrangle: Big Run
District: Grant County: Wetzel
Latitude: _____ Feet South of _____ Deg. _____ Min. _____ Sec.
Longitude: _____ Feet West of _____ Deg. _____ Min. _____ Sec.

RECEIVED
Office of Oil & Gas

OCT 22 2013

Well Type: OIL _____ GAS X

Company EQT Production Company Coal Operator Consolidation Coal Company
1710 Pennsylvania Avenue or Owner 1000 Conso Energy DR
Charleston, WV 25302 Canonsburg, Pa. 15317
Agent John Damato Coal Operator ATTN: Don Puglio
Permit Issued Date 7-24-2012 or Owner WPP LLC
5260 Irwin Rd, Huntington, WV 25705 ATTN: George Angus

WV Department of
Environmental Protection

AFFIDAVIT

STATE OF ~~WEST VIRGINIA~~ KY
County of Floyd ss:

Charles Moore and Rodney Osborne being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 13th day of August, 2013, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
See Attachment A			1107' of 5"	1588' of 5"
			30' of 6 5/8"	2250' of 6 5/8"
				1823' of 8 1/4"
				588' of 10"
				Perfd 3 holes each @ 1050', 1000', 900', 797', 700', 700', 650'
				515', 200', 150', 100', 50.5 holes each @ 950', 720' 10 holes each
				1888', 1735', 1630', 1520', 1475', 1422', 655', and 415'

Description of monument: 4" casing w/ plug date and API # 36" above ground and that the work of plugging and filling said well was completed on the 30th day of August, 2013.


And further deponents saith not.

Charles Moore
Rodney Osborne

Sworn and subscribe before me this 4th day of Sept, 2013

My commission expires: 9-26-14

Michelle Handshoe
Notary Public



Affidavit reviewed by the Office of Oil and Gas: _____

Title: Inspector 10/25/2013

**Attachment A
8-30-13
47-103-00871
Knisely 605287**

<u>Type</u>	<u>From</u>	<u>To</u>
6% gel	2695'	Surface
Class A Cement	2690'	2640'
Class A Cement	2331'	2186'
Class A Cement	1890'	1595'
Class A Cement	1512'	1404'
Class A Cement	1102'	881'
Class A Cement	790'	518'
Class A Cement	210'	Surface