


Latitude



Longitude

Topo Location

7.5' Loc. _____ 15' Loc. _____
 _____ (calc.) _____

#239 MTW Co Rept 1909

Company South Penn

Farm Rachael Wright #6

15' Quad _____
(sec.)

7.5' Quad Pine Grove

District Green

WELL LOCATION PLAT

County 103 Permit 70497

now 103 - 908

STATE OF WEST VIRGINIA
DIVISION OF ENVIRONMENTAL PROTECTION
SECTION OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: HAUGHT, SANTFORD JOE Operator Well No.: R.WRIGHT #6

LOCATION: Elevation: 856.00 Quadrangle: PINE GROVE
District: GREEN County: WETZEL
Latitude: 9450 Feet South of 39 Deg. 32 Min. 30 Sec.
Longitude 8000 Feet West of 80 Deg. 40 Min. 0 Sec.

Well Type: OIL X GAS _____

Company: Pennzoil Products Company Coal Operator NA
P. O. Box 5519 or Owner _____
Vienna, WV 26105-5519 _____

Agent: P. S. Ondrusek Coal Operator _____
or Owner _____

Permit Issued: 04/16/96

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Wood ss:

R. A. Green and Leroy Snodgrass being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well, and Mike Underwood Oil and Gas Inspector representing the Director, say that said work was commenced on the 27th day of September, 1996, and that the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Tried to clean out to T.D.; hole problems and junk in			hole; obtained verbal permission	
to plug from 2563'. Perforated liner from	2563'	2280'	w/8 holes & set following plugs:	
40 sks. cement	2563'	2280'	5x5 1/2" liner 200'	375'
20 sks. cement	2150'	2050'	5-3/16" csq. 2105'	0'
30 sks. cement	1200'	1100'	6-5/8" csq. 320'	1740'
35 sks. cement	670'	570'		
40 sks. cement	320'	220'		
40 sks. cement	200'	100'		
50 sks. cement	50'	Surface		

Ripped 7" @ 640', 620', 600', 580', 340', 320' ripped free.


Description of monument: 7" pipe

and that the work of plugging and filling said well was completed on the 25th day of October, 1996

And further deponents saith not.

Sworn and subscribe before me this 10/3/2000 day of DECEMBER, 1996

R. A. Green
Leroy Snodgrass
Dirk F. Anderson
Notary Public



Oil and Gas Inspector: