

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL & GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm Name: W. O. Efav

Location: Elevation: 1261' Operator Well No.: 2
 District: Center Quadrangle: Littleton 7.5'
 Latitude: _____ Feet South of: _____ County: Wetzel
 Longitude: _____ Feet West of: _____ Deg. _____ Min. _____ Sec.
 Deg. _____ Min. _____ Sec.

Well Type: Oil Gas _____ WTW _____

Company: HG Energy, LLC Coal Operator or Owner: Murray Coal
5260 Dupont Road 46226 National Road
Parkersburg, WV 26101 St. Clairsville, OH 43950
 Agent: Diane White Coal Operator or Owner: NA

Permit Issued: 11/24/14

AFFIDAVIT

State of West Virginia, County of Wood ss:

Timmy Morris and Ken Dotson being first duly sworn according to law, depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 29th day of December, 20 14 and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Cement	3040'	2910'	5-3/16" 1604'	824'
Cement	2475'	2150'	6-5/8" 175'	1901'
Cement	2050'	1950'		
Cement	1500'	1300'		
Cement	1050'	830'		
Cement	350'	0'		
Perforated 5-3/16" casing 1950'-2050' (1 shot/10'), 1400'-1500' (1 shot/10'), 1050'-850' (1 shot/10'), 1008'-1018' (1 shot/1') & 904'-914' (1 shot/1')				
Ripped 7" casing @ 350', 330', 310', 290', 270' & 250'				
Parted 7" @ 175'				
6% gel between cement plugs				

Received
Office of Oil & Gas
FEB 05 2015

Description of monument: 7" x 20' and that the work of plugging and filling said well was completed on the 20th day of January, 20 15

And further deponents saith not.

Timmy A. Morris
Ken Dotson

Sworn and subscribed before me this 29th day of January, 20 15
My commission expires: 4/26/2020


Notary Public

[Signature]

Affidavit reviewed by the
Office of Oil and Gas:

[Signature]

Title: Oil & Gas Inspector



02/20/2015