

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: I.D. Morgan Operator Well No.: 7255

LOCATION: Elevation: 1109' Quadrangle: Big Run W.VA  
District: Grant County: Wetzel  
Latitude: \_\_\_\_\_ Feet South of 39 Deg. 30 Min. 23.87 Sec.  
Longitude: \_\_\_\_\_ Feet West of -80 Deg. 32 Min. 03.13 Sec.

Well Type: OIL X GAS \_\_\_\_\_

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.  
1 Bridge Street or Owner 1 Bridge Street  
Monongah, WV 26554 Monongah, WV 26554  
Agent David Roddy Coal Operator \_\_\_\_\_  
Permit Issued Date 01/10/2023 or Owner \_\_\_\_\_

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 16th day of February, 2023, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye and Gas Block	1115'	702'	7" Casing - 463' Removed	Unknown - Multiple perforations placed in remaining casing
Expandable Cement	702'	Surface	16" Conductor - 0'	20'


Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented and that the work of plugging and filling said well was completed on the 12th day of March, 2023.

And further deponents saith not. Matthew A. Yearsley  
Kevin S. Wright

Sworn and subscribe before me this 24 day of April, 2023

My commission expires: June 8, 2027

Christopher Andrew Willis  
Notary Public



Affidavit reviewed by the Office of Oil and Gas: \_\_\_\_\_ Title: \_\_\_\_\_



AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
WEST VIRGINIA LAND RESOURCES INC  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
MAGNOLIA LAND PARTNERS LLC.  
Lease or Property Owner  
104 S 20<sup>TH</sup> ST STE A PHILADELPHIA, PA 19103  
Address

WEST VIRGINIA LAND RESOURCES INC  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address  
BIG RUN W.VA  
Well Location  
GRANT  
District  
WETZEL  
County  
7255  
Well No.  
I.D. MORGAN  
Farm

STATE INSPECTOR SUPERVISING PLUGGING \_\_\_\_\_

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 16<sup>th</sup> day of February, 2023 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
	Cleaned out existing 7" casing from the surface to 33'. Removed 23' of 7" casing from the surface to 23'. Milled 7" casing from 23' to 33'. Cleaned a 12 1/4" hole from the surface to top of 7" casing at 205'. Removed 251' of 7" casing from 205' to 456'. Cleaned a 12 1/4" hole from 205' to top of 7" casing at 456'. Cleaned out 7" casing from 456' to 1115'. Cut 7" casing at 1110.8' and 802.2'. Removed 212' of 7" casing from 456' to 668'. Attempts to remove additional 7" casing from 668' by pulling 150% of the string weight were unsuccessful. Left an unknown amount of 7" casing in the hole from 668' to an unknown depth. Perforated remaining 7" casing with 6 shots at each of the following depths; 1060.8', 1010.8', 960.8', 920.8', 915.8', 910.8', 908.8', 906.8', 904.8', 902.2', 897.2', 892.2' and 852.2'. Left 20' of 16" conductor pipe in the hole from the surface to 20'.  <u>Cemented the hole from 1115' to the surface as follows:</u> From 1115' to 702' with 80 sacks of Thixotropic Cement with Green Dye and a Gas Blocker additive. Tagged top of Thixotropic Cement plug at 702'. Cemented the hole from 702' to the surface with 440 sacks of Expandable Cement. Cement did circulate at the surface. A total of 520 sacks of cement were used to fill the hole from 1115' to the surface.	7" Casing  16" Conductor	463'  0'	Unknown  20'
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	<u>902.2' – 910.8'</u>	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 12<sup>th</sup> day of March, 2023

And further deponents saith not.

*Matthew A. Yearsley*

Matthew A. Yearsley

*Kevin S. Wright*


Kevin S. Wright

Sworn to and subscribed before me this 24 day of April, 2023

*Christopher Andrew Willis*  
Notary Public

My commission expires:

June 8, 2027



Permit No. 47-103-01034

Well No. 7255

Latitude: 39° 30' 23.87"N

Longitude: -80° 32' 03.13"W