

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: I.D. Morgan Operator Well No.: 7323

LOCATION: Elevation: 952.25 Quadrangle: Big Run W.VA  
District: Grant County: Wetzel  
Latitude: \_\_\_\_\_ Feet South of 39 Deg. 30 Min. 28.60 Sec.  
Longitude: \_\_\_\_\_ Feet West of -80 Deg. 30 Min. 56.86 Sec.

Well Type: OIL X GAS \_\_\_\_\_

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.  
1 Bridge Street or Owner 1 Bridge Street  
Monongah, WV 26554 Monongah, WV 26554  
Agent David Roddy Coal Operator \_\_\_\_\_  
Permit Issued Date 09/28/2021 or Owner \_\_\_\_\_

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 22nd day of February, 2022, and the well was plugged and filled in the following manner:


TYPE	FROM	TO	PIPE REMOVED	LEFT
Expandable Cement	2869	971	2838' - 5/8" Sucker Rods	0'
Thixotropic Cement w/ Green Dye	971'	549'	2869' - 2 3/8" Tubing	0'
Expandable Cement	549'	Surface	999' - 5 1/2" Casing	1491'
			0' - 7" Casing (Multiple Perforations)	Unknown
			0' - 16" Conductor	20'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented and that the work of plugging and filling said well was completed on the 23rd day of March, 2022.

And further deponents saith not. Matthew A. Yearsley

Kevin S. Wright

Sworn and subscribe before me this 24th day of Apr, 2022



My commission expires: 09/15/22

John J. Sullivan  
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Kenneth Greynolds Title: \_\_\_\_\_  
Digitally signed by: Kenneth Greynolds  
DN: CN = Kenneth Greynolds email = Kenneth.L.Greynolds@wv.gov C = AD O = IWDEP OU = Oil and Gas  
Date: 2022.05.02 09:29:34 -0400

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES, INC.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
WEST VIRGINIA LAND RESOURCES, INC.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
WALTER K. & CHRISTINA L. EINSMINGER  
Lease or Property Owner  
8 CRESTVIEW CT BLOOMINGDALE, OH 43910  
Address

WEST VIRGINIA LAND RESOURCES, INC.  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address  
BIG RUN W.VA  
Well Location  
GRANT  
District  
WETZEL  
County  
7323  
Well No.  
I.D. MORGAN  
Farm

STATE INSPECTOR SUPERVISING PLUGGING Kenneth Greynolds


AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:  
MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 22<sup>nd</sup> day of February, 2022 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
Removed 2838' of 5/8" sucker rods from the surface to 2838'. Removed 2869' of 2 3/8" tubing from the surface to 2869'. Cleaned out existing 5 1/2" casing from the surface to 2869'. Removed 999' of 5 1/2" casing from the surface to 999'. Attempted to pull remaining 5 1/2" casing by pulling 150% of the string weight but all attempts were unsuccessful. Left 1491' of 5 1/2" casing in the hole from the 999' to 2490'. Cleaned a 6 1/4" hole through the existing 7" casing from the surface to 999'. Cleaned a 6 1/4" hole through the Pittsburgh Coal Seam (749.8' - 756.3'). Attempted to pull existing 7" casing from the surface by pulling 150% of the string weight but all attempts were unsuccessful. Left an unknown amount of 7" casing in the hole from the surface to an unknown depth. Cemented the bottom hole from 2869' to 971' with 175 sacks of Expandable Cement. Tagged the top of the bottom hole plug at 971'. Perforated the remaining 7" casing with 6 shots at each of the following depths: 956', 906', 856', 806', 766', 761', 756', 754', 752', 750', 745', 740', 700' and 650'. <b>Cemented the hole from 971' back to surface as follows:</b> From 971' to 549' with 90 sacks of Thixotropic Cement with Green Dye. Cemented the hole from the top of the Thixotropic cement plug at 549' to the surface with 140 sacks of Expandable Cement. Cement did circulate at the surface. A total 405 sacks of cement were used to fill the hole from 2869' to the surface.	5/8" Sucker Rods 2 3/8" Tubing 5 1/2" Casing 7" Casing 16" Conductor	2838' 2869' 999' 0' 0'	0' 0' 1491' Unknown 20'	
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	<u>749.8' - 756.3'</u>	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 23<sup>rd</sup> day of March, 2022

And further deponents saith not.



Sworn to and subscribed before me this 29<sup>th</sup> day of Apr 2022

My commission expires: 02/15/24

Matthew A. Yearsley  
Matthew A. Yearsley

Kevin S. Wright  
Kevin S. Wright

[Signature]  
Notary Public

Permit No. 47-103-01041  
Well No. 7323  
Latitude: 39° 30' 28.60"N  
Longitude: -80° 30' 56.86"W

02/23/2024