

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: I.D. Morgan Operator Well No.: 7283

LOCATION: Elevation: 1220' Quadrangle: Big Run W.VA  
District: Grant County: Wetzel  
Latitude: \_\_\_\_\_ Feet South of 39 Deg. 30 Min. 19.43 Sec.  
Longitude: \_\_\_\_\_ Feet West of -80 Deg. 30 Min. 59.35 Sec.

Well Type: OIL X GAS \_\_\_\_\_

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.  
1 Bridge Street or Owner 1 Bridge Street  
Monongah, WV 26554 Monongah, WV 26554  
Agent David Roddy Coal Operator \_\_\_\_\_  
Permit Issued Date 07/14/2023 or Owner \_\_\_\_\_

AFFIDAVIT


STATE OF WEST VIRGINIA,  
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 19th day of July, 2023, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Expandable Cement w/ Gas Blocker	3160'	1263'	5/8" Sucker Rods - 3140'	0'
Thixotropic Cement w/ Green Dye	1263'	841'	2 3/8" Tubing - 3145'	
Expandable Cement	841'	Surface	5 1/2" Casing - 1379'	1403 (Multiple perforations placed in 5 1/2" Csg.)
			7" Casing - 1057.5'	Unknown (Multiple cuts placed in 7" Csg.)

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented and that the work of plugging and filling said well was completed on the 18th day of August, 2023.

And further deponents saith not. Matthew A. Yearsley  
Kevin S. Wright



Sworn and subscribe before me this 14th day of September, 2023

My commission expires: June 8, 2027 Christopher Willis  
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Stephen Mccoy Digitally signed by Stephen Mccoy Date: 2023.09.20 07:49:48 -04'00' Title: \_\_\_\_\_

RECEIVED  
Office of Oil and Gas  
SEP 26 2023  
WV Department of  
Environmental Protection  
10/20/2023

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address

WEST VIRGINIA LAND RESOURCES INC  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address

NICHOLAS E. & DEBORAH ENSMINGER  
Lease or Property Owner  
43 KIMBERLY CIRCLE FAIRMONT, WV 26554  
Address

WEST VIRGINIA LAND RESOURCES INC  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address

BIG RUN W.VA  
Well Location  
GRANT  
District  
WETZEL  
County  
7283  
Well No.  
I.D. MORGAN  
Farm

Digitally signed by Stephen Mccoy  
Mccoy  
Date: 2023.09.20 07:50:59  
-04'00'

Stephen Mccoy

STATE INSPECTOR SUPERVISING PLUGGING

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 19<sup>th</sup> day of July, 2023 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Removed 3140' of 5/8" sucker rods. Removed all 3145' of 2 3/8" tubing. Removed 1379' of 5 1/2" casing. Left 1403' of 5 1/2" casing in the hole from 1379' to 2782'. Perforated remaining 5 1/2" casing with 6 shots at each of the following depths: 2682', 2582', 2482', 2382', 2282', 2182', 2082', 1982', 1882', 1782', 1682', 1582' and 1482'. Cemented the bottom hole from 3160' to 1263' with 240 sacks of Expandable Cement with a Gas Blocker additive. Cut existing 7" casing at 1247.5'. Removed 1057.5' of casing from the surface to 1057.5'. A diligent effort was made to remove the remaining 7" casing to 1247.5' by pulling 150% of the string weight but all efforts were unsuccessful. Left and unknown amount of 7" casing in the hole from 1057.5' to an unknown depth. Cut the remaining 7" casing at 1197.5', 1147.5', and 1097.5'. Cleaned a 12 1/4" hole from the surface to 382'. Cleaned a 9 7/8" hole from 382' to the top of the remaining 7" casing at 1157.5'. Cleaned a 6 1/4" hole from 1157.5' to top of bottom hole plug at 1263'. Cleaned a 9 7/8" hole through the Pittsburgh Coal Seam (1041.0' - 1047.5'). Left 19' of 20" conductor pipe in the hole from the surface to 19'. CONTINUED ON PAGE 2	5/8" Sucker Rods	3140'	0'	
	2 3/8" Tubing	3145'	0'	
	5 1/2" Casing	1379'	1403'	
	7" Casing	1057.5'	Unknown	
	20" Conductor	0'	19'	
Coal Seams	Description of Monument			
<u>Pittsburgh</u>	<u>1041.0' - 1047.5'</u>	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 18<sup>th</sup> day of August, 2023

And further deponents saith not.

Matthew A. Yearsley  
Matthew A. Yearsley


Kevin S. Wright  
Kevin S. Wright

Sworn to and subscribed before me this 14<sup>th</sup> day of September, 2023

[Signature]  
Notary Public

My commission expires:

June 8, 2027



Permit No. 47-103-01043  
Well No. 7283  
Latitude: 39° 30' 19.43"N  
Longitude: -80° 30' 59.35"W

RECEIVED  
Office of Oil and Gas

SEP 26 2023

WV Department of  
Environmental Protection  
10/20/2023