

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Fairfield - Peterson Operator Well No.: 7235

LOCATION: Elevation: 1156.05 Quadrangle: Folsom, WV  
District: Grant County: Wetzel  
Latitude: 39.512458 Feet South of 39 Deg. 30 Min. 40.84 Sec.  
Longitude: -80.545413 Feet West of -80 Deg. 32 Min. 43.48 Sec.

Well Type: OIL X GAS \_\_\_\_\_

Company Consolidation Coal Co. Coal Operator Consolidation Coal Co.  
1 Bridge Street or Owner 1 Bridge Street  
Monongah, WV 26554 Monongah, WV 26554  
Agent David Roddy Coal Operator \_\_\_\_\_  
Permit Issued Date 10/13/2020 or Owner \_\_\_\_\_

AFFIDAVIT


STATE OF WEST VIRGINIA,  
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 21st day of October, 2020, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic Cement w/ Green Dye	1220'	791'		
Expandable Cement	791'	Surface		
5 1/2" Casing	228'	Unknown	228'	Unknown
7" Casing	18'	Unknown	0'	Unknown
8 5/8" Casing	Unknown	Unknown	0'	Unknown
13 3/8" Conductor	Surface	20'	0'	Unknown

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented. and that the work of plugging and filling said well was completed on the 12th day of November, 2020.

And further deponents saith not. Matthew A. Yearsley  
Kevin S. Wright



Sworn and subscribe before me this 19th day of NOV, 2020

My commission expires: 09/15/22  
[Signature]  
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Derek M. Haught Title: Oil & Gas Inspector

03/12/2021

# Plugging Report for MSHA

Well Number: 7235

Mine: Harrison County Mine

Surface

Permit Number: 47-103-01069

Date Clean Out Started: 10/21/2020

Date Well Bore Plugged: 11/12/2020

Pittsburgh Coal Seam: 991 ft. To 998 ft.

Plugs:	From	To	Type of Cement
	1220'	791'	Thixotropic Cement w/ Green Dye
	791'	Surface	Expandable Cement

**Casing Remaining in Well Bore**

**Thix Top: 791'**

	Top	Bottom	Left	Pulled
Sucker Rods				
2 3/8" Tubing				
5 1/2" Casing	228'	Unknown	Unknown	228'
7" Casing	18'	Unknown	Unknown	0'
7" fiberglass				
8 5/8" Casing	Unknown	Unknown	Unknown	0
10 3/4" Casing				
13 3/8" Cond.	Surface	20'	20'	0'

Expandable Cement

Thixotropic Cement w/ Green Dye

Thixotropic Cement w/ Green Dye

Top of 13 3/8" Conductor at Surface

Bottom of 13 3/8" Conductor at 20'

5 1/2" casing cut at 438'

5 1/2" casing cut at 657'

5 1/2" casing cut at 760'

5 1/2", 7" and 8 5/8" cut at 891'

5 1/2", 7" perforated at 941'

5 1/2", 7" perforated at 981'

5 1/2", 7" perforated at 986'

991' - 998'

5 1/2", 7" and 8 5/8" cut at 991', 993', 995.5' and 998'

5 1/2", 7" perforated at 1003'

5 1/2", 7" perforated at 1003'

5 1/2", 7" perforated at 1048'

5 1/2", 7" perforated at 1098'

5 1/2", 7" perforated at 1148'

5 1/2", 7" and 8 5/8" cut at 1198'

5 1/2" casing cut at 1212'

**Pittsburgh Coal**

**Cement:**

Expandable	<u>105</u>	sacks
Thixotropic	<u>50</u>	sacks
Econofill		sacks
Mud Flush	<u>1000</u>	gal
Other		
Est. Top Thix		ft
Did Cement Circ.	<u>Yes</u>	

**Comments:**

Caving: Extreme **Moderate** Normal

Lost Circulation: Extreme **Moderate** Normal

Difficulty in Removing Casing: **Extreme** Moderate Normal Does Not Apply

Debris in Well Bore: Wood **Steel** Other: \_\_\_\_\_

Surface Elevation (Surveyed)	<u>1156'</u>
Bottom of Coal Structure (Map)	<u>158'</u>
Difference	<u>998'</u>

**Thix Bottom: 1220'**

**Total Depth: 1220'**

03/12/2021

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
CONSOLIDATION COAL CO.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
COASTAL FOREST RESOURCES COMPANY  
Lease or Property Owner  
P.O. BOX 709 BUCKHANNON, WV 26201  
Address

CONSOLIDATION COAL CO.  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address  
FOLSOM, WV  
Well Location  
GRANT  
District  
WETZEL  
County  
7235  
Well No.  
FAIRFIELD - PETERSON  
Farm

STATE INSPECTOR SUPERVISING PLUGGING Derek M. Haught

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:  
MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 21<sup>st</sup> day of October, 2020 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Drilled cement out of existing 5 1/2" casing with 4 3/4" bit from the surface to 1220'. Cut 5 1/2" casing at 1212', 760', 657' and 438'. Removed 228' of 5 1/2" casing from the surface to 228'. Left an unknown amount of 5 1/2" casing in the hole from 228' to an unknown depth. Attempted to pull remaining 5 1/2" casing by pulling 150% of the string weight but all attempts were unsuccessful. Left an unknown amount of 7" casing in the hole from 18' to an unknown depth. The previous well record indicated that 8 5/8" casing was left in the hole but no 8 5/8" casing was visible at the surface. Cut remaining 5 1/2", 7" and 8 5/8" casing at the following depths with a multiple string cutter: 1198', 998', 995.5', 993', 991' and 891'. Perforated remaining 5 1/2", 7" and 8 5/8" casings with 4 shots at each of the following depths: 1148', 1098', 1048', 1008', 1003', 986', 981' and 941'. Cleaned a 4 3/4" hole through the Pittsburgh Coal Seam (991' - 998'). Left 20' of 13 3/8" conductor in the hole from the surface to 20'.		5 1/2" Casing	228'	Unknown
		7" Casing	0'	Unknown
		8 5/8" Casing	0'	Unknown
		13 3/8" Conductor	0'	20'
<b>Cemented the hole from 1220' to surface as follows:</b> From 1220' to 791' with 50 sacks of Thixotropic Cement with Green Dye. From 791' to surface with 105 sacks of Expandable Cement. Cement did circulate at surface.				
<b>Coal Seams</b>	<b>Description of Monument</b>			
<u>Pittsburgh</u>	<u>991' - 998'</u>	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 12<sup>th</sup> day of November, 2020


And further deponents saith not.

Matthew A. Yearsley

Matthew A. Yearsley

Kevin S. Wright

Kevin S. Wright



Sworn to and subscribed before me this 12<sup>th</sup> day of Dec, 2020

03/12/2021

[Signature]  
Notary Public

My commission expires: 09/15/22

Permit No. 47-103-01069  
Well No. 7235  
Latitude: 39° 30' 40.84"N  
Longitude: -80° 32' 43.48"W