

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: B.W. Peterson Operator Well No.: 7184

LOCATION: Elevation: 1308.08' Quadrangle: Folsom W.VA  
District: Grant County: Wetzel  
Latitude: \_\_\_\_\_ Feet South of 39 Deg. 29 Min. 31.62 Sec.  
Longitude: \_\_\_\_\_ Feet West of -80 Deg. 31 Min. 14.85 Sec.

Well Type: OIL X GAS \_\_\_\_\_

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.  
1 Bridge Street or Owner 1 Bridge Street  
Monongah, WV 26554 Monongah, WV 26554

Agent David Roddy Coal Operator \_\_\_\_\_  
Permit Issued Date 05/12/2021 or Owner \_\_\_\_\_

AFFIDAVIT


STATE OF WEST VIRGINIA,  
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 6th day of May, 2021, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye and Gas Block	1436'	1006'		
Expandable Cement	1006'	Surface		
7" Casing	396'	Unknown	0'	Unknown
16" Conductor	Surface	20'	0'	20'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented. and that the work of plugging and filling said well was completed on the 15th day of May, 2021.

And further deponents saith not. Matthew A. Yearsley  
Kevin S. Wright



Sworn and subscribe before me this 29th day of June, 2021

My commission expires: 09/15/22  
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Bryan Harris Title: Inspector 08/13/2021

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES, INC.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
WEST VIRGINIA LAND RESOURCES, INC.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
COASTAL FOREST RESOURCES COMPANY  
Lease or Property Owner  
P.O. BOX 709 BUCKHANNON, WV 26201  
Address

WEST VIRGINIA LAND RESOURCES, INC.  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address  
FOLSOM, W.VA  
Well Location  
GRANT  
District  
WETZEL  
County  
7184  
Well No.  
B.W. PETERSON  
Farm

STATE INSPECTOR SUPERVISING PLUGGING Bryan Harris 7/6/21  
AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:  
MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 6<sup>th</sup> day of May, 2021 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned the hole with a 13 3/4" bit from the surface to 201'. Tagged top of existing 10 3/4" casing at 201'. Removed all (61') 10 3/4" casing from the hole from 201' to 262'. Cleaned the hole with a 12 1/4" bit from 262' to 396'. Tagged top of existing 7" casing at 396'. Reduced the hole to 6 1/4" at 396'. Cleaned the hole with a 6 1/4" bit from 396' to 1436. Cleaned a 6 1/4" hole through the Pittsburgh Coal Seam (1163.5' - 1169.5'). Attempted to pull existing 7" casing from 396' by pulling 150% of the string weight but all attempts were unsuccessful. Left 7" casing in the hole from 396' to an unknown depth. Cut remaining 7" casing at 1369.50', 1319.50', 1269.50', 1219.50', 1179.50', 1174.50', 1169.50', 1167.50', 1165.50', 1163.50', 1158.50', 1153.50', 1113.50' and 1063.50'. Left 20' of 16" conductor in the hole from 20' to surface.	7" Casing	0'	Unknown	
	<b>Cemented the hole from 1436' to surface as follows:</b> From 1436' to 1006' with 100 sacks of Thixotropic Cement with Green Dye and a gas blocker additive. Tagged top of Thixotropic plug at 1006'. Cemented to hole from 1006' to surface with 370 sacks of Expandable Cement. Cement did circulate at surface. A total of 470 sacks of cement were used to fill the hole from 1436' to surface.	16" Conductor	0'	20'
<b>Coal Seams</b>	<b>Description of Monument</b>			
<u>Pittsburgh</u>	1163.5' - 1169.5'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 15<sup>th</sup> day of June, 2021

And further deponents saith not.


*Matthew A. Yearsley*

Matthew A. Yearsley

*Kevin S. Wright*

Kevin S. Wright

08/13/2021



Sworn to and subscribed before me this 29<sup>th</sup> day of June, 2021

*[Signature]*  
Notary Public

My commission expires: 09/15/22

Permit No. 47-103-01074  
Well No. 7184  
Latitude: 39° 29' 31.62"N  
Longitude: -80° 31' 14.85"W