

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Shay Heirs Operator Well No.: SHAY HEIRS #10

LOCATION: Elevation: 1341.5' Quadrangle: Hundred 7.5'  
District: Church County: Wetzel  
Latitude: 4,389,034 Feet South of \_\_\_\_\_ Deg. \_\_\_\_\_ Min. \_\_\_\_\_ Sec.  
Longitude: 549,229 Feet West of \_\_\_\_\_ Deg. \_\_\_\_\_ Min. \_\_\_\_\_ Sec.

Well Type: OIL \_\_\_\_\_ GAS X

Company West Virginia Land Resources Inc Coal Operator West Virginia Land Resources Inc.  
1 Bridge Street or Owner 1 Bridge Street  
Monongah, WV 26554 Monongah, WV 26554  
Coal Operator \_\_\_\_\_  
Agent David Roddy or Owner \_\_\_\_\_  
Permit Issued Date 07/10/23

AFFIDAVIT


STATE OF WEST VIRGINIA,  
County of Wetzel ss:

Tim Simmons and Chaz Simmons being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 31st day of July, 2023, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
555 sks of Class L cmt	2240'	surface	2160' of 2 - 3/8" tbg	0 of 2 - 3/8" tbg
Cement did circulate to surface			927' of 5 - 1/2" csg	973' of 5 - 1/2" csg
			Made a diligent effort to remove 5 1/2" Pipe by pulling 150% string weight. All attempts were unsuccessful.	
			Perforated pipe with 6 shots each @ 1350, 1300, 1250, 1200, 1160, 1155, 1150, 1145, 1143, 1138, 1133, 1093, 1043	
			Pittsburgh Coal was 1143'-1150'	

Description of monument: 7" casing w/ API # welded on. Monument is 5' above ground and that the work of plugging and filling said well was completed on the 11th day of August, 2023.

And further deponents saith not. Chris Veazey



Sworn and subscribe before me this 2nd day of November, 2023

My commission expires: Sept. 18, 2027  
Sandra L. Messer  
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Stephen Mccoy Digitally signed by Stephen Mccoy Date: 2023.12.18 09:24:28 -05'00'

Title: \_\_\_\_\_ 12/22/2023