

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: J.L. Stevens Operator Well No.: 7513

LOCATION: Elevation: 918.4' Quadrangle: Big Run W.VA
District: Grant County: Wetzel
Latitude: 39.5166 Feet South of 39 Deg. 31 Min. 00.0019 Sec.
Longitude: -80.5054 Feet West of -80 Deg. 30 Min. 19.53 Sec.

Well Type: OIL GAS

Company West Virginia Land Resources INC. Coal Operator West Virginia Land Resources INC.
1 Bridge Street or Owner _____
Monongah, WV 26554 _____
Agent David Roddy Coal Operator _____
Permit Issued Date 03/04/2024 or Owner _____

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Wetzel ss:

Mathew A. Yearsley and Delbert Moore being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 12th day of April, 2024, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye	974'	571'	5 1/2" Casing 974'	Unknown
Expanding	571'	Surface	7" Casing 974'	Unkown
			8 5/8" Casing 973'	Unknown
			16" Conductor Casing 0'	20'

Description of monument: 77" of 7" casing with company name, well #, API #, and date completed and that the work of plugging and filling said well was completed on the 29th day of April, 2024.


And further deponents saith not. Matthew A. Yearsley

Delbert Moore

Sworn and subscribe before me this 21st day of May, 2024

My commission expires: June 8, 2024

Christopher Willis
Notary Public



Affidavit reviewed by the Office of Oil and Gas: _____ Title: _____

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATED, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
WEST VIRGINIA LAND RESOURCES INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
DOUGLAS JOE SMITH
Lease or Property Owner
Smithfield, WV 26437
Address

WEST VIRGINIA LAND RESOURCES INC.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
Big Run W. VA
Well Location
GRANT
District
WETZEL
County
7513
Well No.
J.L STEVENS
Farm

STATE INSPECTOR SUPERVISING PLUGGING Steve McCoy

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Wetzel ss:

MATTHEW A. YEARSLEY and Delbert Moore being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources INC. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 12th day of April, 2024 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Removed 974' of 5 1/2" casing from surface to 974'. Removed 974' of 7" casing from surface to 974'. Removed 973' of 8 5/8" casing from surface to 973'. Cleaned a 12 1/4" hole from surface to 317'. Reduced hole to 9 7/8" and cleaned a 9 7/8" hole from 317' to 973'. Cleaned a 9 7/8" hole through the Pittsburgh Coal Seam (965'-971.5') Left 20' of 16" conductor casing in the hole from 20' to surface. <u>Cemented Hole from 974' to surface as follows:</u> Cemented bottom hole from 974' to 571' with 235 sacks of Thixotropic cement with green dye and gas blocker additive. Cemented from 571' to surface with 430 sacks of Expanding cement. Cement did circulate at surface. A total of 665 sacks of cement were used to fill the hole from 974' to surface.	5 1/2" Casing	974'	Unknown	
	7" Casing	974'	Unknown	
	8 5/8" Casing	973'	Unknown	
	16" Conductor Casing	0'	20'	
Coal Seams	Description of Monument			
<u>Pittsburgh</u>	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.			

... and that the work of plugging and filling said well was completed on the 29th day of April, 2024

And further deponents saith not.


Matthew A. Yearsley
Matthew A. Yearsley

Delbert L. Moore
Delbert Moore

Sworn to and subscribed before me this 21st day of May 2024

My commission expires:

June 8, 2027



[Signature]
Notary Public

Permit No. 47-103-01437
Well No. 7513
Latitude: 39° 31' 00.0019"N
Longitude: -80° 30' 19.53"W