

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

WEST VIRGINIA LAND RESOURCES INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

WEST VIRGINIA LAND RESOURCES INC.
Lease or Property Owner
1 BRIDGE STREET MONONGAH, WV
Address

WEST VIRGINIA LAND RESOURCES INC.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
Big Run, WV 7.5'
Well Location
Wetzel County
District
Grant
County
7294
Well No.
I.D. Morgan
Farm

Digitally signed by Stephen McCoey
Date: 2023.02.24 08:46:08 -05'00'

STATE INSPECTOR SUPERVISING PLUGGING

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Wetzel :

Bruce Chisler and Garrett Hickman being first duty sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 18th day of August 2022 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
3Formation		7"	0	n/a
Drilled from surface to 653 ft with 12-1/4" bit. Milled with 12" mill from 653 ft to 674 ft, clean out with 6-1/4" bit to 1170 ft. Trip in 7" sphere and pulled 150% casing string weight – would not come. Made cuts at 1106, 1056, 1006, 956, 916, 911, 906, 904, 902, 900, 898, 894, 889, 848 and 798 ft. Appalachian perforated pipe at 876, 885 and 895 ft. Cement from 1106 to 698' with 90 sacks Thix. Cement from 698' to surface with 575 sacks expandable cement.				
Coal Seams		Description of Monument		
Pittsburgh	898' to 906'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 5th day of October, 2022

And further deponents saith not.

Bruce Chisler
Bruce Chisler

Garrett Hickman
Garrett Hickman

Sworn to and subscribed before me this


3

day of

Feb 2023

Paul A. Baker
Notary Public

My commission expires:



Permit No. **47-103-01579**
Well No. **7294**
Latitude: **39.510017 N**
Longitude: **-80.530197 W**

12/01/2023