

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Tall Timber Inc. Operator Well No.: 6327

LOCATION: Elevation: 1318.45 Quadrangle: Wallace, WV 7.5'
District: Grant County: Wetzel
Latitude: _____ Feet South of 39 Deg. 29 Min. 07.53 Sec.
Longitude: _____ Feet West of -80 Deg. 29 Min. 17.71 Sec.

Well Type: OIL GAS _____

Company Consolidation Coal Co. Coal Operator Consolidation Coal Co.
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Coal Operator _____
Agent David Roddy or Owner _____
Permit Issued Date 04/21/21

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 7th day of April, 2021, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye and Gas Block	1440'	1022'		
Expandable Cement	1022'	Surface		
8 5/8" Casing	716'	Unknown	0'	Unknown
16" Conductor	Surface	20'	0'	20'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented. and that the work of plugging and filling said well was completed on the 21st day of April, 2021.

And further deponents saith not. Matthew A. Yearsley
Kevin S. Wright



Sworn and subscribe before me this 3rd day of May, 2021

My commission expires: 09/15/22
[Signature]
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Bryan Harris Title: Inspector 06/18/2021

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
TALL TIMBER INC.
Lease or Property Owner
446 MANNINGTON RD. SMITHFIELD, WV 26437
Address


CONSOLIDATION COAL CO.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
WALLACE, WV 7.5'
Well Location
GRANT
District
WETZEL
County
6327
Well No.
TALL TIMBER INC.
Farm

STATE INSPECTOR SUPERVISING PLUGGING Bryan Harris 5/4/21
AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:
MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 7th day of April, 2021 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned the hole with a 12 1/4" bit from the surface to 299'. Reduced the hole to 9 7/8" at 299'. Cleaned the hole with a 9 7/8" bit from 299' to the top of the existing 8 5/8" casing at 716'. Reduced the hole to 7 7/8" at 716'. Cleaned the hole with a 7 7/8" bit from 716' to 1440'. Attempted to remove existing 8 5/8" casing by pulling 150% of the string weight but all attempts to remove 8 5/8" casing were unsuccessful. Left an unknown amount of 8 5/8" casing in the hole from 716' to an unknown depth. Cut remaining 8 5/8" casing at the following depths; 1428', 1378', 1328', 1278', 1238', 1233', 1229', 1227', 1225', 1223', 1221', 1216', 1211', 1172', 1122'. Cleaned a 7 7/8" hole through the Pittsburgh Coal Seam (1222' - 1228'). Left 20' of 16" conductor pipe in the hole from the surface to 20'.		8 5/8" Casing	0'	Unknown
		16" Conductor	0'	20'
Cemented the hole from 1440' to surface as follows: From 1440' to 1022' with 125 sacks of Thixotropic Cement with Green Dye and gas blocker additive. Tagged top of Thixotropic plug at 1022'. From 1022' to surface with 465 sacks of Expandable Cement. Cement did circulate at surface. A total of 590 sacks of cement were used to fill the hole from 1440' to surface.				
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	<u>1222' to 1228'</u>	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 21st day of April, 2021
And further deponents saith not.



Matthew A. Yearsley
Matthew A. Yearsley
Kevin S. Wright
Kevin S. Wright

Sworn to and subscribed before me this 3rd day of May, 2021

[Signature]
Notary Public
06/18/2021

My commission expires: 09/15/22

Permit No. 47-103-01835
Well No. 6327
Latitude: 39° 29' 07.53"N
Longitude: -80° 29' 17.71"W