

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL & GAS

RECEIVED
Office of Oil and Gas

SEP 12 2016

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses. **WV Department of Environmental Protection**

Farm Name: WV Public Lands Operator Well No.: F.L. Hoge 12
Location: Elevation: 1007' Quadrangle: Centerpoint 7.5'
District: Green County: Wetzel
Latitude: 8,600 Feet South of: 39 Deg. 30 Min. 30 Sec.
Longitude: 5,275 Feet West of: 80 Deg. 40 Min. Sec.

Well Type: Oil X Gas WIW

Company: HG Energy, LLC Coal Operator
5260 Dupont Road or Owner
Parkersburg, WV 26101
Agent: Diane White Coal Operator
or Owner

Permit Issued: 8/3/15

AFFIDAVIT

State of West Virginia, County of Wood ss:

Jared Stemple and Ken Dotson being first duly sworn according to law, depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 7th day of July, 20 16 and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Class A Cement	2900'	2800'	4 1/2" 1056'	2027'
Class A Cement	2250'	2150'	8 5/8"	253'
Class A Cement	1100'	900'		
Class A Cement	575'	475'		
Class A Cement	300'	0'		
CIB plug set @ 2898', T.O.C. on backside of 4 1/2" casing @ 1538'. Free-point @ 1056'. 6% gel between all plugs.				
6% gel between all cement plugs				

Received
Office of Oil & Gas
Aug 03 2016

Description of monument: 7" Cemented Pipe and that the work of plugging and filling said well was completed on the 12th day of July, 20 16

And further deponents saith not.


[Signature]
Ken Dotson

Sworn and subscribed before me this 29th day of July, 20 16
My commission expires: July 11, 2022

Notary Public Diane White

Affidavit reviewed by the Office of Oil and Gas: Derek M. Haught

Title: Oil & Gas Inspector



09/16/2016