

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Hart Operator Well No.: 518477

LOCATION: Elevation: 871 Quadrangle: Center Point
District: Grant County: Wetzel
Latitude: 4720 Feet South of 39 Deg. 30 Min. _____ Sec.
Longitude: 1770 Feet West of 80 Deg. 37 Min. 30 Sec.

Well Type: OIL _____ GAS x _____

Company EQT Production Company Coal Operator _____
2400 Ansys Drive - Suite 200 or Owner _____
Canonsburg, PA 15317 _____
Agent Jason Ranson Coal Operator _____
Permit Issued Date April 25, 2019 or Owner _____

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of Roane ss:

Johnny Payne and Doug Garrett being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 9th day of May, 2019, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Class A Cmt. - 44 sks	6830	6430	2-3/8" lbg. - 6,820'	5-1/2" CIBP @ 6830
Gel Spacer	6430	5186	5-1/2" csg. - 2,190'	6-1/2" CIBP @ 2064
Class A Cmt. - 37 sks	5186	4850		Perf.'d w/ (2) shots ea. @ 5,100, 5,050, 5,000, 4,950
Gel Spacer	4850	3984		4,900, 3,950, 3,900, 3,850, 3,800, & 3,750
Class A Cmt. - 37 sks	3984	3650		
Gel Spacer	3650	2356		
Class A Cmt. - 61 sks	2356	2056	Continued on back	

Description of monument: Above ground plate welded on 5-1/2" w/ API #, Well Name, & Plug Date and that the work of plugging and filling said well was completed on the 19th day of June, 2019.

And further deponents saith not. [Signatures]



Sworn and subscribe before me this 3rd day of July, 2019
My commission expires: December 14, 2022 David N. Brannon
Notary Public

WV Department of Environmental Protection

Affidavit reviewed by the Office of Oil and Gas: Derek M. Haught Title: Oil & Gas Inspector

TYPE	FROM	TO
Gel Spacer	2064	2056
Class A Cmt. - 86 sks	2064	1764
Gel Spacer	1764	1006
Class A Cmt. - 86 sks	1006	660
Gel Spacer	660	400
Class A Cmt. - 118 sks	400	surface

RECEIVED
Office of Oil and Gas

JUL 16 2019

WV Department of
Environmental Protection