

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: LEASURE (DELBERT&RUTH) Operator Well No.: 519055 LEASURE 2H

LOCATION: Elevation: 934' Quadrangle: PORTERS FALLS 7.5'
District: GREEN County: WETZEL
Latitude: 39.605616 Feet South of _____ Deg. _____ Min. _____ Sec.
Longitude: -80.781925 Feet West of _____ Deg. _____ Min. _____ Sec.

Well Type: OIL _____ GAS X

Company EQT Production Co. Coal Operator HARRISON COUNTY COAL RESOURCES
625 LIBERTY AVE. SUITE 1700 or Owner 46226 NATIONAL RD. ST.CLAIRSVILLE OH
PITTSBURGH PA 15222
Agent JOSEPH C MALLOW Coal Operator DELBERT LEASURE
Permit Issued Date 04-28-2022 or Owner 6941 MOUNTAINEER HWY NEW MARTINSVILLE WV

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of WETZEL ss:

PATRICK CARNAHAN and JAMES PURSLEY being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 07 day of JULY, 2022, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
CLASS A CMT 50 SKS	6465	5975	3,450' 4 1/2" CASING	
6% GEL	5975	3480	6,532' 2 3/8" TUBING	40' OF 16" CONDUCTOR CASING
CLASS A CMT 91 SKS	3480	3290		919' OF 11 3/4" CASING
6% GEL	3290	2530	4 1/2" CUT@ 3450	2,332' OF 9 5/8" CASING
CLASS A CMT 699 SKS	2530	SURFACE	WINDOWS CUT 1,146, 530',306',190'	3,239' OF 4 1/2" CASING
CIBP		6465		

Description of monument: 2' X 2' PLATE ON 4 1/2" CASING 5' ABOVE GROUND and that the work of plugging and filling said well was completed on the 26TH day of SEPTEMBER, 2022.


And further deponents saith not.

[Handwritten signatures]

Sworn and subscribe before me this 27 day of SEPT, 2022

My commission expires: 8-30-2024

Stephen Mccoy
Notary Public
Digitally signed by Stephen Mccoy
Date: 2023.01.13 13:27:19 -05'00'



Affidavit reviewed by the Office of Oil and Gas:

Title: WV Oil and Gas Inspector