

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL & GAS

RECEIVED  
Office of Oil and Gas  
AUG 4 2017  
WV Department of  
Environmental Protection

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm Name: Hoge E.M. Operator Well No.: 4  
 Location: Elevation: 1061' Quadrangle: Centerpoint 7.5'  
 District: Green County: Wetzel  
 Latitude: 4,371,137 (NAD 83) Feet South of: \_\_\_\_\_ Deg. \_\_\_\_\_ Min. \_\_\_\_\_ Sec. \_\_\_\_\_  
 Longitude: 525,368 (NAD 83) Feet West of: \_\_\_\_\_ Deg. \_\_\_\_\_ Min. \_\_\_\_\_ Sec. \_\_\_\_\_

Well Type: Oil X Gas \_\_\_\_\_ WIW \_\_\_\_\_

Company: HG Energy, LLC Coal Operator or Owner \_\_\_\_\_  
5260 Dupont Road \_\_\_\_\_  
Parkersburg, WV 26101 \_\_\_\_\_

Agent: Diane White Coal Operator or Owner \_\_\_\_\_

Permit Issued: 6/27/16

AFFIDAVIT


State of West Virginia, County of Wood ss:

Jared Stemple and Jim Lamp being first duly sworn according to law, depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 7th day of October, 20 16 and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
			2 3/8" 2100'	800'
Class A Cement	2120'	1767'	5 3/16"	170'
Class A Cement	1100'	1000'	5 1/2"	500'
Class A Cement	860'	760'	6 5/8"	2240'
Class A Cement	425'	325'	10"	265'
Class A Cement	200'	0'		
Perforated 6 5/8" casing 2100' - 2000', 1100' - 1000', 860' - 760', 425' - 325', 200' - 100' (one shot every 10')				
6% gel between all cement plugs				

Description of monument: 7" Cemented Pipe and that the work of plugging and filling said well was completed on the 26th day of October, 20 16

And further deponents saith not.

  
\_\_\_\_\_  
James D. Lamp

Sworn and subscribed before me this 30th day of October, 20 16

My commission expires: July 11, 2022

Notary Public Diane White

Affidavit reviewed by the Office of Oil and Gas: Derek M. Haught

Title: Oil & Gas Inspector

