

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Weekley, Larry & Donna Operator Well No.: Weekley #7H

LOCATION: Elevation: 727' Quadrangle: Porters Falls  
District: Green County: Wetzel  
Latitude: 12,160 Feet South of 39 Deg. 37 Min. 30 Sec.  
Longitude: 8,010 Feet West of 80 Deg. 45 Min. 00 Sec.

Well Type: OIL \_\_\_\_\_ GAS

Company Stone Energy Corporation Coal Operator No Coal Operator  
6000 Hampton Center, Suite B or Owner \_\_\_\_\_  
Morgantown, WV 26505  
Agent Tim McGregor Coal Operator Larry I. and Donna S. Weekley  
Permit Issued Date 4-4-2012 or Owner RR 2, Box 175A  
New Martinsville, WV 26155

RECEIVED  
Office of Oil & Gas  
JUN 06 2012

AFFIDAVIT

WV Department of  
Environmental Protection

STATE OF WEST VIRGINIA,  
County of Monongalia ss:

Chad Shoffner and W. Lee Hornsby being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 15th day of March, 2012, and the well was plugged and filled in the following manner:


TYPE	FROM	TO	PIPE REMOVED	LEFT
Treated Water	12,339' MD / 6,455' TVD	6,526' MD / 6,334' TVD	None	20" Conductor @ 45' GTS
Cement	6,526' MD / 6,334' TVD	5,174' MD / 5,169' TVD	None	13-3/8" @ 696' CTS
Cement	4,012' MD / 4,010' TVD	3,812' MD / 3,810' MD	None	9-5/8" @ 2,172' CTS
Cement	2,738' MD / TVD	2,108' MD / TVD	None	5-1/2" @ 12,339' MD / 6,455' TVD CTS
Cement	1,654' MD / TVD	1,451' MD / TVD		
Cement (RFC)	796' MD / TVD	Surface		
6% Gel	Between All Of The	Cement Plugs		

Description of monument: Metal Cap below plow depth with API. Off site sign w/API & Azi. and that the work of plugging and filling said well was completed on the 16th day of March, 2012.

And further deponents saith not.

Chad Shoffner  
W. Lee Hornsby

Sworn and subscribe before me this 7<sup>th</sup> day of June, 2012



My commission expires: May 18, 2021

Danielle L. Snoderly  
Notary Public  
Managers

Affidavit reviewed by the Office of Oil and Gas:

Title:

06/08/2012