

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL COMPANY  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
CONSOLIDATION COAL COMPANY  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
CONSOLIDATION COAL COMPANY  
Lease or Property Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address

CONSOLIDATION COAL CO.  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address  
WALLACE 7.5'  
Well Location  
GRANT  
District  
WETZEL  
County  
7112  
Well No.  
CONSOLIDATION COAL COMPA  
Farm

STATE INSPECTOR SUPERVISING PLUGGING

*James Unholzer*  
AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:

ROGER MOORE and STEPHAN MOATS being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 30<sup>th</sup> day of July, 2014 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleansed 12 1/4" hole from Surface to 516'. Reduced hole to 9 7/8". Cleansed 9 7/8" hole from 516' to 1281'. Tagged top of 8 5/8" casing at 1281'. Cleansed 9 7/8" hole through the Pittsburgh Coal seam from 1241' to 1248'. Reduced hole to 7 7/8". Cleansed 7 7/8" hole from 1281' to 2288'. Reduced hole to 6 1/4". Cleansed 6 1/4" hole from 2288' to 2291'. Removed 179' of 8 5/8" casing from 1281' to 1460'. Left 274' of 8 5/8" casing in the hole from 1460' to 1734'.		16" Conductor	0'	20'
		8 5/8" Casing	179'	274'
<b>Received Office of Oil &amp; Gas OCT 07 2014</b>				
<b>Cemented hole from 2291' back to surface as follows:</b>				
From 2291' to 1432' with 175 sacks of Expandable Cement. From 1432' to 1123' with 160 sacks of Thixotropic Cement with green dye. From 1123' back to the Surface with 545 sacks of Expandable Cement. Cement did circulate at the surface. Left 20' of 16" conductor casing in the hole from the surface to 20'.				
Coal Seams	Description of Monument			
Pittsburgh	(1241' - 1248')	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 22<sup>nd</sup> day of August, 2014


And further deponents saith not.

*Roger Moore*  
Roger Moore  
*Stephan E Moats*  
Stephan Moats

Sworn to and subscribed before me this 29 day of September 2014

*Kara Beth Ford*  
Notary Public

My commission expires: 11/4/23



Permit No. 47-103-03018-P  
Well No. 7112

10/10/2014