

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Consolidation Coal Company Operator Well No.: 7132

RECEIVED  
Office of Oil and Gas

LOCATION: Elevation: 1334.04' Quadrangle: Folsom, WV 7.5"  
District: Grant County: Wetzel  
Latitude: \_\_\_\_\_ Feet South of 39 Deg. 28 Min. 46.70 Sec.  
Longitude: \_\_\_\_\_ Feet West of 80 Deg. 31 Min. 22.27 Sec.

MAY 15 2018

WV Department of  
Environmental Protection

Well Type: OIL \_\_\_\_\_ GAS X

Company Consolidation Coal Co Coal Operator 1 Bridge St  
or Owner Monongah, WV 26554  
Agent David Roddy Coal Operator \_\_\_\_\_  
or Owner \_\_\_\_\_  
Permit Issued Date 03/08/18

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of Wetzel ss:

Delbert E. Moore and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 3rd day of April, 2018, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Expandable	1550'	1398'		
Thixotropic	1398'	1088'		
Expandable	1088'	Surface		
8 5/8"	1311'	1580'	320'	249'
18" Conductor	Surface	20'	0'	20'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented. and that the work of plugging and filling said well was completed on the 23rd day of April, 2018.


And further deponents saith not.

Delbert E. Moore  
Kevin S. Wright

Sworn and subscribe before me this 10th day of May, 2018

My commission expires: 06/17/2021

Richard O'Dell  
Notary Public



Affidavit reviewed by the Office of Oil and Gas: Derek M. Haught Title: Oil & Gas Inspector

# Plugging Report for MSHA

Well Number: 7132 Mine: Marion County Mine

Permit Number: 47-103-03227

Date Clean Out Started: 4/3/2018

Date Well Bore Plugged: 4/23/2018

Pittsburgh Coal Seam: 1189 ft. To 1195.50 ft.

Plugs:	From	To	Type of Cement
	1550'	1396'	Expandable Cement
	1396'	1089'	Thixotropic Cement with green dye
	1089'	Surface	Expandable Cement

**Casing Remaining in Well Bore**

	Top	Bottom	Left	Pulled
Sucker Rods				
2 3/8" tubing				
4 1/2" casing				
7" casing				
8 5/8" casing	1311'	1560'	249'	320'
10 3/4" casing				
16" casing	Surface	20'	20'	0'
Other				

**Cement:**

Expandable 520 sacks

Thixotropic 145 sacks

Econofill \_\_\_\_\_ sacks

Mud Flush 1000 gal

Other \_\_\_\_\_

Est. Top Thix 1089' ft

Did Cement Circ. Yes

**Comments:**

Caving: Extreme Moderate Normal

Lost Circulation: Extreme Moderate Normal

Difficulty in Removing Casing: Extreme Moderate Normal Does Not Apply

Debris in Well Bore: Wood Steel Other: \_\_\_\_\_

Surface

Top of 16" Conductor Casing at Surface  
Bottom of 16" Conductor Casing at 20'

Expandable Cement

RECEIVED  
Office of Oil and Gas  
MAY 15 2018  
WV Department of  
Environmental Protection

Thix Top: 1089'

Pittsburgh Coal

1189' to 1195.5'

Top of 8 5/8" casing at 1311'

Cut 8 5/8" casing at 1346'

Thix Bottom: 1396'

Cut 8 5/8" casing at 1396'

Cut 8 5/8" casing at 1416'

Expandable Cement

Surface Elevation (Surveyed) 1335

Bottom of Coal Structure (Map) 151

Difference 1184

Total Depth: 1560'

Bottom of 8 5/8" casing at 1560'

Supplemental

FORM WR-38  
(Affidavit of Plugging)

WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OIL AND GAS WELLS DIVISION

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address

CONSOLIDATION COAL CO.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address

MICHAEL W. & ANGIE LEE COEN  
Lease or Property Owner  
RT. 1 BOX 48 FOLSOM, WV 26348  
Address

CONSOLIDATION COAL CO.  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address

FOLSOM, WV 7.5'  
Well Location

GRANT  
District

WETZEL  
County

7132  
Well No.

GENINE ROBINSON  
Farm

RECEIVED  
Office of Oil and Gas  
MAY 15 2018  
WV Department of  
Environmental Protection

STATE INSPECTOR SUPERVISING PLUGGING Derek W. Haught

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:

DELBERT E. MOORE and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 3rd day of April, 2018 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned 12 1/4" hole from the surface to 355'. Reduced hole to 9 7/8" at 355'. Cleaned 8 7/8" hole from 355' to the top of the 8 5/8" casing at 991'. Reduced hole to 7 7/8" at 991'. Cleaned 7 7/8" hole through 8 5/8" casing from 991' to 1560'. Tagged cement plug at 1560'. Pulled 320' of 8 5/8" casing from 991' to 1311'. Cut remaining 8 5/8" casing at the following depths: 1416', 1396', and 1346'. Continued to clean 9 7/8" hole from 991' to 1311'. Cleaned 9 7/8" hole through the Pittsburgh Coal Seam (1189' - 1195.5').		8 5/8"	320'	249'
<u>Cemented hole from top of bottom hole plug at 1560' back to the surface as follows:</u> From 1560' to 1396' with 40 sacks of Expandable cement. From 1396' to 1089' with 145 sacks of Thixotropic cement with green dye. From 1089' to the surface with 480 sacks of Expandable cement. Cement did circulate at the surface. Left 20' of 16" conductor at the surface from the surface to 20'.		16" Conductor	0'	20'
<b>Coal Seams</b>		<b>Description of Monument</b>		
<u>Pittsburgh</u>	<u>(1189' - 1195.5')</u>	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 25th day of April, 2018

And further deponents saith not.


Delbert E. Moore  
Delbert E. Moore

Kevin S. Wright  
Kevin S. Wright

Sworn to and subscribed before me this 10<sup>th</sup> day of May, 2018

Richard O Dell  
Notary Public

My commission expires: October



Permit No. 47-103-03227-P  
Well No. 7132  
Latitude: 39° 28' 46.70"N  
Longitude: 80° 31' 22.27"W