

west virginia department of environmental protection

Office of Oil and Gas 601 57th Street, S.E. Charleston, WV 25304 (304) 926-0450 fax: (304) 926-0452

Austin Caperton, Cabinet Secretary www.dep.wv.gov

Thursday, October 25, 2018
PERMIT MODIFICATION APPROVAL
Horizontal 6A / New Drill

EQT PRODUCTION COMPANY 625 LIBERTY AVE., SUITE 1700

PITTSBURGH, PA 15222

Re:

Permit Modification Approval for BIG 245 H17

47-103-03236-00-00

Modified Conductor to 26"

EQT PRODUCTION COMPANY

The Office of Oil and Gas has reviewed the attached permit modification for the above referenced permit. The attached modification has been approved and well work may begin. Please be reminded that the oil and gas inspector is to be notified twenty-four (24) hours before permitted well work is commenced.

If there are any questions, please feel free to contact me at (304) 926-0450.

James A. Martin

Chief

Operator's Well Number: BIG 245 H17

Farm Name: ET BLUE GRASS, LLC

U.S. WELL NUMBER: 47-103-03236-00-00

Horizontal 6A New Drill

Date Modification Issued: October 25, 2018

Promoting a healthy environment.

WW-6B (04/15)

API NO. 47- 103	.03236 Me 1)	
OPERATOR V	WELL NO. BIG245H17	_
Well Pad Na	me: BiG245	

STATE OF WEST VIRGINIA DEPARTMENT OF ENVIRONMENTAL PROTECTION, OFFICE OF OIL AND GAS WELL WORK PERMIT APPLICATION

1) Well Operator: EQT Production Company 306686 Wetzel	Grant	Big Run
Operator ID County	District	Quadrangle
2) Operator's Well Number: BIG245H17 Well Pad Name: BIG2	245	
3) Farm Name/Surface Owner: E.T. Bluegrass Public Road Access: Rt	. 19/2	
4) Elevation, current ground: 1480 Elevation, proposed post-construction	tion: 1430	
5) Well Type (a) Gas X Oil Underground Stora	age	
(b)If Gas Shallow X Deep Horizontal X		Michael Communication of the C
6) Existing Pad: Yes or No No	DMH 8/	15/18
7) Proposed Target Formation(s), Depth(s), Anticipated Thickness and Expected Marcellus, 7531, 51, 2620 PSI	Pressure(s):	
8) Proposed Total Vertical Depth: 7531		
9) Formation at Total Vertical Depth: Marcellus		
10) Proposed Total Measured Depth: 18990		
11) Proposed Horizontal Leg Length: 8332		
12) Approximate Fresh Water Strata Depths: 229, 507, 662, 752, 1011		
 13) Method to Determine Fresh Water Depths: From offset wells 14) Approximate Saltwater Depths: None 		
15) Approximate Coal Seam Depths: 925, 1024, 1132		RECEIVED Office of Oil and Ga
16) Approximate Depth to Possible Void (coal mine, karst, other): None	·	OCT - 9 2018
17) Does Proposed well location contain coal seams directly overlying or adjacent to an active mine? Yes No.	o <u>x</u>	WV Department of Environmental Protect
(a) If Yes, provide Mine Info: Name:		
Depth:	-	
Seam: Owner:	*******	

API NO. 47- 103	_ 03236	men	
OPERATOR W	ELL NO.	BIG245H17	
Well Pad Nar	ne: BIG24	5	_

18)

CASING AND TUBING PROGRAM

TYPE	Size (in)	New or Used	Grade	Weight per ft. (lb/ft)	FOOTAGE: For Drilling (ft)	INTERVALS: Left in Well (ft)	CEMENT: Fill-up (Cu. Ft.)/CTS
Conductor	26	New	A-500	85.6	40	40	49 ft^3 / CTS
Fresh Water	13 3/8	New	J-55	54.5	1179	1179	1086 ft^3 / CTS
Coal							
Intermediate	9 5/8	New	A-500	40	2925	2855	1108 ft^3 / CTS
Production	5 1/2	New	P-110	20	18990	18990	500' above top producing zone
Tubing	2 3/8		J-55	4.7		May not be run, if run set 40° above top perf or 80° inclination	
Liners							

DMH 8/15/18

ТҮРЕ	Size (in)	Wellbore Diameter (in)	Wall Thickness (in)	Burst Pressure (psi)	Anticipated Max. Internal Pressure (psi)	Cement Type	<u>Cement</u> <u>Yield</u> (cu. ft./k)
Conductor	26	30	.312	1378	17	Class A	1.18
Fresh Water	13 3/8	17 1/2	.38	2700	2160	See Variance	1.19
Coal							
Intermediate	9 5/8	12 3/8	.395	3950	3160	Class H	1.07
Production	5 1/2	8 1/2	.361	12640	10112	Class H	1.123/2.098
Tubing	2 3/8	NA	.19	7700			
Liners							

PACKERS

Kind:		RECEIVED Office of Oil and Gas
Sizes:		UCT - 9 2018
Depths Set:		WV Department of Environmental Protection

WW-6B
(10/14)

API NO. 47-103 - 03236 WWY

OPERATOR WELL NO. BIG245H17

Well Pad Name: BIG245

19) Describe proposed well work, including the drilling and plugging back of any pilot hole:

Drill and complete a new horizontal well in the Marcellus Formation. Drill the vertical to an approximate depth of 5477'. Kick off and drill curve. Drill the lateral in the Marcellus. Cement casing.

DMH 8/15/18

20) Describe fracturing/stimulating methods in detail, including anticipated max pressure and max rate:

Hydraulic fracturing is completed in accordance with state regulations using water recycled from previously fractured wells and obtained from freshwater sources. This water is mixed with sand and a small percentage (less than 0.3%) of chemicals (including 15% Hydrochloric acid, gelling agent, gel breaker, friction reducer, biocide, and scale inhibitor), referred to in the industry as a "slickwater" completion. Maximum anticipated internal casing pressure is expected to be approximately 10000 psi, maximum anticipated treating rates are expected to average approximately 100 bpm. Stage lengths vary from 150 to 300 feet. Average approximately 350,000 barrels of water per stage. Sand sizes vary from 100 mesh to 20/40 mesh. Average approximately 400,000 pounds of sand per stage.

- 21) Total Area to be disturbed, including roads, stockpile area, pits, etc., (acres): +/- 40.35
- 22) Area to be disturbed for well pad only, less access road (acres): +/- 34.59
- 23) Describe centralizer placement for each casing string:
- Surface: Bow spring centralizers One at the shoe and one spaced every 500'.
- Intermediate: Bow spring centralizers— One cent at the shoe and one spaced every 500'.
- Production: One solid body cent spaced every joint from production casing shoe to KOP

RECEIVED
Office of Oil and Gas

24) Describe all cement additives associated with each cement type:

OCT - 9 2018

Lead (Class H Cement): 0.2% CD-20 (dispersant makes cement easier to mix). .15% SuperFL-300 (fluid loss/lengthens thickening time). .15% SEC-10 (fluid loss) 50.50 POZ (extender)
Tail (Class H Cement): 0.2% Super CR-1 (Relarder). Lengthens thickening time. .3% Super FL-200 (fluid loss). 2% SEC-10 (Fluid loss). 2% SuperFL-350 (fluid loss). Reduces amount of water lost to formation. 60 % Colcuim Carbonate. Acid solubility.

lost to

25) Proposed borehole conditioning procedures:

Surface: Circulate hole clean while rotating & reciprocating the drill string until cuttings diminish at surface. Intermediate: Circulate hole clean while rotating & reciprocating the drill string until cuttings diminish at surface.

Production: Pump marker sweep with nut plug to determine actual hole washout. Calculate a gauge holes bottoms up volume. Perform a cleanup cycle by pumping 3-5 bottoms up or until the shakers are clean. Check volume of cuttings coming across the shakers every 15 minutes.

*Note: Attach additional sheets as needed.

BIG245H17 Well **EQT Production**

Big Run Quad Wetzel County, WV

Note: Diagram is not to scale

ENERTIA# 516520 35 381

Azimuth	3	
ical Section	83	

	Top Base				Casing and Cementing			'Deepest Fresh Water:	1,011'
Formations	TVD TVD				Type	Conductor	Surface	Intermediate	Production
Conductor	40				Hole Size, In.	30	17 1/2	12 3/8	8 1/2
		-111	111-		Casing Size, OD In.	26	13 3/8	9 5/8	5 1/2
		111	111		Casing Wall Thickness, In.	0.312	0.380	0.395	0.361
Base Red Rock	967	111	111		Depth, MD	40'	1,179'	2,855'	18,990'
Base Fresh Water	1011	111	111		Weight	85.6#	54.5#	40#	20#
Surface Casing	1179	4			Grade	A-500	J-55	A-500	P-110
		- 11	11		New or Used	New	New	New	New
Maxton	2305 - 2346	- 11	11		Burst (psi)	1378	2,700	3,950	12,640
Big Lime	2359 - 2429	- 11	11		Cement Class	A	A / Type 1	Н	Н
Big Injun	2429 - 2596		11		Cement Yield	1.18	1.19	1.07	1.123/2.098
Intermediate Casing	2855	4	N		Top of Cement (Planned)	Surface	Surface	Surface	500' above top Producing Zone
					Method	Displacement	Displacement	Displacement	Displacement
		- 1	1		Est. Volume (cu ft)	49	1,086	1,108	2,883
Gordon Forth Sand Bayard	3163 - 3202 3221 - 3265 3124 - 3499	1			Possible Additives	N/A	Calcium Chloride	Calcium Chloride, Fluid Loss, Defoamer, Dispersant, POZ, Bonding Agent, Extender, Retarder,	Calcium Carbonate, Fluid Loss, Extender, Dispersent, Viscosifier, Defoamer, POZ, Bonding Agent, Retarder, Anti-Settling/Suspension
Speechley	3891 - 4113	- 1	KOP@	5,477°				Flake/LCM	Agent
Riley	4684 - 4916	- 1							-
Benson	5380 - 5528	- 1	1						
Alexander	5842 - 6158	- 1	1						
Sonyea	7063 - 7140	- 1	1						
Middlesex	7140 - 7324	- 1							
Genesee	7324 - 7362	1	1						
Geneseo	7362 - 7388	1	1						
Tully	7388 - 7410		11						
Hamilton	7410 - 7509		11						
Marcellus	7509 - 7560		11						4
Production Casing Onondaga	18990 MD 7560	052,177,272		and the same of th			en e		

Land curve @ 7,531' TVD 10,658' MD

Est. TD @


7,531' TVD 18,990' MD


Proposed Well Work:


Drill and complete a new horizontal well in the Marcellus formation.

Drill the vertical to an approximate depth of 5477'.

8,332' Lateral









Laura Adkins WVDEP Office of Oil and Gas 601 57Th Street SE Charleston WV 25304-2345

Re: Modification of wells BIG245H8 (47-103-03234), BIG245H16 (47-103-03235), and BIG245 (47-103-03236)

Dear Ms. Adkins

Attached are the modifications for the above API numbers. The conductor casing size has been changed for the conductor only.

If you have any questions, please do not hesitate to contact me at (304) 848-0035.

Sincerely,

Rebecca Wanstreet Landman I – Permitting WV

becca Wanshoet

Enc.

Office of Oil and Gas

HU - 9 2018

Environment of