

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Brame Higgins Operator Well No.: 6344

LOCATION: Elevation: 997' Quadrangle: Wallace, W.VA  
District: Grant County: Wetzel  
Latitude: \_\_\_\_\_ Feet South of 39 Deg. 29 Min. 44.90 Sec.  
Longitude: \_\_\_\_\_ Feet West of -80 Deg. 29 Min. 38.91 Sec.

Well Type: OIL X GAS \_\_\_\_\_

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.  
1 Bridge Street or Owner 1 Bridge Street  
Monongah, WV 26554 Monongah, WV 26554  
Agent David Roddy Coal Operator \_\_\_\_\_  
Permit Issued Date 01/12/2023 or Owner \_\_\_\_\_

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 24th day of February, 2023, and the well was plugged and filled in the following manner:


TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye and Gas Block	1112'	693'	8 5/8" Casing - 0'	Unknown - Multiple cuts placed in remaining casing
Expandable Cement	693'	Surface	10 3/4" Casing - 0'	20'
			16" Conductor - 0'	18'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented and that the work of plugging and filling said well was completed on the 27th day of March, 2023.

And further deponents saith not. Matthew A. Yearsley  
Kevin S. Wright

Sworn and subscribe before me this 5 day of April, 2023

My commission expires: June 8, 2027 Christopher Andrew Willis  
Notary Public





AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

**WEST VIRGINIA LAND RESOURCES INC**  
Coal Operator or Owner  
**1 BRIDGE STREET MONONGAH, WV 26554**  
Address  
**WEST VIRGINIA LAND RESOURCES INC**  
Coal Operator or Owner  
**1 BRIDGE STREET MONONGAH, WV 26554**  
Address  
**ROBERT P. & RANDALL B. NICHOLS**  
Lease or Property Owner  
**6753 N RIDGE RD. MADISON, OH 44057**  
Address

**WEST VIRGINIA LAND RESOURCES INC**  
Name of Well Operator  
**1 BRIDGE STREET MONONGAH, WV 26554**  
Complete Address  
**WALLACE W.VA**  
Well Location  
**GRANT**  
District  
**WETZEL**  
County  
**6344**  
Well No.  
**BRAME HIGGINS**  
Farm

STATE INSPECTOR SUPERVISING PLUGGING \_\_\_\_\_

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:

**MATTHEW A. YEARSLEY** and **KEVIN S. WRIGHT** being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 24<sup>th</sup> day of February, 2023 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
	Cleaned a 12 1/4" hole from the surface to top of existing 10 3/4" casing at 379'. Cleaned a 9 7/8" hole from 379' to top of existing 8 5/8" casing at 519'. Cleaned a 7 7/8" hole from 519' to 1112'. Cleaned a 7 7/8" hole through the Pittsburgh Coal Seam (893.1' – 899.6'). A diligent effort was made to remove the existing 8 5/8" casing from 519' to 1099.6' by pulling 150% of the string weight but all efforts were unsuccessful. Left an unknown amount of 8 5/8" casing in the hole from the 519' to an unknown depth. Cut the remaining 8 5/8" casing at the following depths: 1099.6', 1049.6', 999.6', 949.6', 909.6', 904.6', 899.6', 898', 896.4', 894.8', 893.1', 888.1', 883.1', 843.1' and 793.1'. Left 20' of 10 3/4" casing in the hole from the 379' to 399'. Left 18' of 16" conductor pipe in the hole from the surface to 18'.	8 5/8" Casing	0'	Unknown
		10 3/4" Casing	0'	20'
		16" Conductor	0'	18'
<b>Coal Seams</b>		<b>Description of Monument</b>		
<b>Pittsburgh</b>	<b>893.1' – 899.6'</b>	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 27<sup>th</sup> day of March, 2023

And further deponents saith not.

*Matthew A. Yearsley*  
Matthew A. Yearsley


*Kevin S. Wright*  
Kevin S. Wright

Sworn to and subscribed before me this 5 day of April, 2023

*Christopher Andrew Willis*  
Notary Public

My commission expires:

June 8, 2027



Permit No. 47-103-03264  
Well No. 6344  
Latitude: 39° 29' 44.90"N  
Longitude: -80° 29' 38.91"W