

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: H. L. Smith Operator Well No.: 7207

LOCATION: Elevation: 999.36' Quadrangle: Folsom WV 7.5'
District: Grant County: Wetzel
Latitude: 39.495763 Feet South of 39 Deg. 29 Min. 44.7468 Sec.
Longitude: -80.538757 Feet West of -80 Deg. 32 Min. 19.5252 Sec.

Well Type: OIL X GAS _____

Company Consolidation Coal Co. Coal Operator Consolidation Coal Co.
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Agent David Roddy Coal Operator _____
Permit Issued Date 09/24/2019 or Owner _____

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 19th day of August, 2020, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
6% Gel	1436'	1021'		
Thixotropic Cement w/ Green Dye	1021'	569'		
Expandable Cement	569'	Surface		
7" Casing	1021	Unknown	624'	Unknown
16" Conductor Pipe	Surface	20'	0'	20'


Description of monument: 77' of 7" casing with company name, well #, API #, and date cemented. and that the work of plugging and filling said well was completed on the 3rd day of September, 2020.

And further deponents saith not. Matthew A. Yearsley

Kevin S. Wright

Sworn and subscribe before me this 21st day of Sep, 2020

My commission expires: 09/15/22
[Signature]
Notary Public



Affidavit reviewed by the Office of Oil and Gas: Derek M. Haught Title: Oil & Gas Inspector

Plugging Report for MSHA

Well Number: 7207

Mine: Harrison County Mine

Surface

Permit Number: 47-103-03331

Date Clean Out Started: 8/19/2020

Date Well Bore Plugged: 9/3/2020

Pittsburgh Coal Seam: 814 ft. To 821 ft.

Plugs:

From	To	Type of Cement
1436'	1021'	6% Gel
1021'	569'	Thixotropic w/ Green Dye
569'	Surface	Expandable Cement

Casing Remaining in Well Bore

Thix Top: 569'

	Top	Bottom	Left	Pulled
Sucker Rods				
2 3/8" tubing				
4 1/2" casing				
7" casing	1021'	Unknown	Unknown	624'
7" fiberglass				
8 5/8" casing				
10 3/4" casing				
16" Conductor	Surface	20'	20"	0'

Expandable Cement

Top of 16" Conductor at Surface
Bottom of 16" Conductor at 20'

Thixotropic Cement w/ Green Dye

814'-821'

Pittsburgh Coal

Thixotropic Cement w/ Green Dye

Thix Bottom: 1021'

Top of 7" Casing at 1021'

6%Gel Plug

Total Depth: 1436'

Bottom of 7" casing unknown

Cement:

Expandable	<u>435</u>	sacks
Thixotropic	<u>235</u>	sacks
Econofill		sacks
Mud Flush	<u>1000</u>	gal
Other		
Est. Top Thix		ft
Did Cement Circ.	<u>Yes</u>	

Comments:

Caving: Extreme Moderate **Normal**

Lost Circulation: Extreme Moderate **Normal**

Difficulty in Removing Casing: **Extreme** Moderate Normal

Debris in Well Bore: **Wood** **Steel** Other: _____

Surface Elevation (Surveyed)	<u>999.36'</u>
Bottom of Coal Structure (Map)	<u>178.36</u>
Difference	<u>821</u>

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
COASTAL FORREST RESOURCES COMPANY
Lease or Property Owner
P.O. BOX 709 BUCKHANNON, WV 26201
Address

CONSOLIDATION COAL CO.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
FOLSOM, WV 7.5'
Well Location
GRANT
District
WETZEL
County
7207
Well No.
H.L. SMITH
Farm

STATE INSPECTOR SUPERVISING PLUGGING Derek M. Haught

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 19th day of August, 2020 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned hole with a 12 1/4" bit from the surface to 357'. Reduced hole to 9 7/8" at 357'. Cleaned hole with a 9 7/8" bit from 357' to the top of the 7" casing at 397'. Reduced hole to 6 1/4" at 397'. Cleaned hole with a 6 1/4" bit from 397' to 1436'. Tagged plug at 1436'. Removed 624' of 7" casing from 397' to 1021'. Left an unknown amount of 7" casing in the hole from 1021' to an unknown depth. Attempts to re-enter 7" casing at 1021' were unsuccessful. Left a 6% gel plug from 1436' to 1021'. Cleaned a 9 7/8" hole through the Pittsburgh Coal Seam from 814' to 821'.		7" Casing 16" Conductor	624' 20'	Unknown 20'
<u>Cemented the hole from 1021' to surface as follows:</u> From 1021' to 569' with 235 sacks of Thixotropic Cement with Green Dye. Tagged the cement plug at 569'. From 569' to surface with 435 sacks of Expandable Cement. Cement did circulate at surface. A total of 670 sacks of cement were used to cement the hole from 1021' to surface. Left 20' of 16" conductor in the hole from 20' to surface.				
Coal Seams	Description of Monument			
<u>Pittsburgh</u>	814' - 821' 77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.			

... and that the work of plugging and filling said well was completed on the 3rd day of September, 2020

And further deponents saith not.



Matthew A. Yearsley

Matthew A. Yearsley

Kevin S. Wright

Kevin S. Wright

Sworn to and subscribed before me this 23rd day of sep, 2020

[Signature]
Notary Public

My commission expires: 09/15/22

Permit No. 47-103-03331
Well No. 7207
Latitude: 39° 29' 44.7468"N
Longitude: -80° 32' 19.5252"W