

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: B.W. Peterson Operator Well No.: 7274

LOCATION: Elevation: 1120.89' Quadrangle: Folsom, WV 7.5'
District: Grant County: Wetzel
Latitude: 39.499649 Feet South of 39 Deg. 29 Min. 58.73 Sec.
Longitude: -80.525809 Feet West of -80 Deg. 31 Min. 32.91 Sec.

Well Type: OIL GAS

Company Consolidation Coal Co. Coal Operator Consolidation Coal Co.
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Agent David Roddy Coal Operator _____
Permit Issued Date 02/14/2020 or Owner _____

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 2nd day of October, 2020, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thkotropic w/ Green Dye and Gas Block	1244'	702'		
Expandable Cement	702'	Surface		
16" Conductor Pipe	Surface	41'	0'	41'

Description of monument: 77' of 7" casing with company name, well #, API #, and date cemented. and that the work of plugging and filling said well was completed on the 27th day of October, 2020.

And further deponents saith not. Matthew A. Yearsley
Kevin S. Wright



Sworn and subscribe before me this 19th day of NOV, 2020

My commission expires: 09/15/22 [Signature]
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Derek M. Haught Title: Oil & Gas Inspector

05/12/2021

Plugging Report for MSHA

Well Number: 7274

Mine: Harrison County Mine

Surface

Permit Number: 47-103-03340

Date Clean Out Started: 10/2/2020

Date Well Bore Plugged: 10/27/2020

Pittsburgh Coal Seam: 902 ft. To 909 ft.

Plugs:

From	To	Type of Cement
<u>1244'</u>	<u>702'</u>	<u>Thixotropic Cement w/ Green Dye and Gas Block</u>
<u>702'</u>	<u>Surface</u>	<u>Expandable Cement</u>

Top of 16" Conductor at Surface

Bottom of 16" Conductor at 41'

Expandable Cement

Casing Remaining in Well Bore

Thix Top: 702'

	Top	Bottom	Left	Pulled
Sucker Rods				
2 3/8" tubing				
4 1/2" casing				
7" casing				
7" fiberglass				
8 5/8" casing				
10 3/4" casing				
16" Conductor	Surface	41'	41'	0'

Thixotropic Cement w/ Green Dye

902' - 909'

Pittsburgh Coal

Cement:

Expandable	<u>425</u>	sacks
Thixotropic	<u>230</u>	sacks
Econofill		sacks
Mud Flush	<u>1000</u>	gal
Other		
Est. Top Thix		ft
Did Cement Circ.	<u>Yes</u>	

Comments:

Caving: Extreme Moderate Normal
 Lost Circulation: Extreme Moderate Normal
 Difficulty in Removing Casing: Extreme Moderate Normal Does Not Apply
 Debris in Well Bore: Wood Steel Other: _____

Thixotropic Cement w/ Green Dye

Surface Elevation (Surveyed)	<u>1121'</u>
Bottom of Coal Structure (Map)	<u>212'</u>
Difference	<u>909'</u>

Thix Bottom: 1244'

Total Depth: 1244'

03/12/2021

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
COASTAL FOREST RESOURCES COMPANY
Lease or Property Owner
P.O. BOX 709 BUCKHANNON, WV 26201
Address

CONSOLIDATION COAL CO.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
FOLSOM, WV 7.5'
Well Location
GRANT
District
WETZEL
County
7274
Well No.
B.W. PETERSON
Farm

STATE INSPECTOR SUPERVISING PLUGGING Derek M. Haught

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 2nd day of October, 2020 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
	Cleaned a 12 1/4" hole from the surface to 344'. Reduced hole to 9 7/8" at 344'. Cleaned a 9 7/8" hole from 344' to 1072'. Reduced hole to 7 7/8" at 1072'. Cleaned a 7 7/8" hole from 1072' to 1074'. Reduced hole to 6 1/4" at 1074'. Cleaned a 6 1/4" hole from 1074' to 1244'. Cleaned a 9 7/8" hole through the Pittsburgh Coal Seam (902' - 909'). Left 41' of 16" conductor pipe in the hole from 41' to surface. <u>Cemented the hole from 1244' to surface as follows:</u> From 1244' to 702' with 230 sacks of Thixotropic Cement with Green Dye and a gas blocker additive. Tagged the cement plug at 702'. From 702' to surface with 425 sacks of Expandable Cement. Cement did circulate at surface. A total of 655 sacks of cement were used to fill the hole from 1244' to surface.	16" Conductor	0'	41'
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	902' - 909'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 27th day of October, 2020


And further deponents saith not.

Matthew A. Yearsley

Matthew A. Yearsley

Kevin S. Wright

Kevin S. Wright



Sworn to and subscribed before me this 17th day of NOV, 2020

[Signature] 03/12/2021
Notary Public

My commission expires: 09/15/20

Permit No. 47-103-03340
Well No. 7274
Latitude: 39° 29' 58.73"N
Longitude: -80° 31' 32.91"W