

west virginia department of environmental protection

Office of Oil and Gas
601 57th Street, S.E.
Charleston, WV 25304
(304) 926-0450
fax: (304) 926-0452

Austin Caperton, Cabinet Secretary
www.dep.wv.gov

Thursday, November 19, 2020
PERMIT MODIFICATION APPROVAL
Horizontal 6A / New Drill

SWN PRODUCTION COMPANY, LLC
POST OFFICE BOX 12359

SPRING, TX 773914954


Re: Permit Modification Approval for CONSTANCE TAYLOR WTZ 1H
47-103-03352-00-00

Modified Cement Yield

SWN PRODUCTION COMPANY, LLC

The Office of Oil and Gas has reviewed the attached permit modification for the above referenced permit. The attached modification has been approved and well work may begin. Please be reminded that the oil and gas inspector is to be notified twenty-four (24) hours before permitted well work is commenced.

If there are any questions, please feel free to contact me at (304) 926- 0450.



James A. Martin
Chief

Operator's Well Number: CONSTANCE TAYLOR WTZ 1H
Farm Name: CONSTANCE A TAYLOR
U.S. WELL NUMBER: 47-103-03352-00-00
Horizontal 6A New Drill
Date Modification Issued: November 19, 2020

Promoting a healthy environment.

WW-6B
(04/15)

API NO. 47-103 - 03352MOD
OPERATOR WELL NO. Constance Taylor Wtz 1H
Well Pad Name: Constance Taylor Wtz

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION, OFFICE OF OIL AND GAS
WELL WORK PERMIT APPLICATION

1) Well Operator: SWN Production Co., LLC 494512924 103-Wetzel 7-Proctor 681-Wileyville
Operator ID County District Quadrangle

2) Operator's Well Number: Constance Taylor Wtz 1H Well Pad Name: Constance Taylor Wtz

3) Farm Name/Surface Owner: Constance A. Taylor Public Road Access: Brock Ridge Road

4) Elevation, current ground: 1430' Elevation, proposed post-construction: 1430'

5) Well Type (a) Gas Oil _____ Underground Storage _____

Other _____

(b) If Gas Shallow Deep _____

Horizontal _____

6) Existing Pad: Yes or No Yes *DMAH 10/27/20*

7) Proposed Target Formation(s), Depth(s), Anticipated Thickness and Expected Pressure(s):
Target Formation- Marcellus, Up-Dip well to the North, Target Top TVD- 7402', Target Base TVD- 7445', Anticipated Thickness- 43', Associated Pressure- 4839

8) Proposed Total Vertical Depth: 7432' *RECEIVED*

Office of Oil and Gas

9) Formation at Total Vertical Depth: Marcellus

NOV 04 2020

10) Proposed Total Measured Depth: 22540'

WV Department of Environmental Protection

11) Proposed Horizontal Leg Length: 14601.49'

12) Approximate Fresh Water Strata Depths: 365'

13) Method to Determine Fresh Water Depths: Logs on Pad

14) Approximate Saltwater Depths: 1467' Salinity Profile Analysis

15) Approximate Coal Seam Depths: 1382'

16) Approximate Depth to Possible Void (coal mine, karst, other): None that we are aware of.

17) Does Proposed well location contain coal seams directly overlying or adjacent to an active mine? Yes _____ No

(a) If Yes, provide Mine Info: Name: _____

Depth: _____

Seam: _____

Owner: _____

WW-6B
(04/15)

API NO. 47-103 - 03352 Moyn
OPERATOR WELL NO. Constance Taylor Wtz 1H
Well Pad Name: Constance Taylor Wtz

18) CASING AND TUBING PROGRAM

TYPE	Size (in)	New or Used	Grade	Weight per ft. (lb/ft)	FOOTAGE: For Drilling (ft)	INTERVALS: Left in Well (ft)	CEMENT: Fill-up (Cu. Ft.)/CTS
Conductor	20"	New	J-55	94#	126'	126'	CTS
Fresh Water	13 3/8"	New	J-55	54.4#	470'	470'	362 sx/CTS
Coal	See	Interm	Casing				
Intermediate	9 5/8"	New	J-55	36#	2900'	2900'	826 sx/CTS
Production	5 1/2"	New	P-110 HP	20#	22540'	22540'	Tail 3838cu/100' Inside Intermediate
Tubing							
Liners							

RECEIVED
Office of Oil and Gas
NOV 04 2020

DWH 10/27/20 W Department of Environmental Protection

TYPE	Size (in)	Wellbore Diameter (in)	Wall Thickness (in)	Burst Pressure (psi)	Anticipated Max. Internal Pressure (psi)	Cement Type	Cement Yield (cu. ft./k)
Conductor	20"	30"	0.25	2120	81	Class A	1.20/30% Excess
Fresh Water	13 3/8"	17.5"	0.380	2730	633	Class A	1.20/30% Excess
Coal	See	Interm	Casing				
Intermediate	9 5/8"	12 1/4"	0.352	3520	1768	Class A	1.19/40% Excess
Production	5 1/2"	8 3/4"-8 1/2"	0.361	14360	10500	Class A	1.19/5% Excess
Tubing							
Liners							

PACKERS

Kind:				
Sizes:				
Depths Set:				



Check # 1053304

10/27/2020
\$5,000.00

103-03352 MOD

SWN Production Company, LLC
1300 Fort Pierpont Dr, Ste 201
Morgantown, WV 26508
Tel: 304 884 1610
Fax: 304 471 2497
www.swn.com

November 2, 2020

Ms. Laura Adkins
Office of Oil & Gas
601 57th Street
Charleston, WV 25304

RECEIVED
Office of Oil and Gas

NOV 04 2020

WV Department of
Environmental Protection

RE: Proposed **Expedited Modification**: Constance Taylor WTZ 1H

Dear Ms. Adkins

Enclosed please find a modification for the above captioned well. We made changes to the cement yield on page two of the 6B per the DEP inspector's request. This well is situated on the Taylor's property, in Proctor District, Wetzel County, West Virginia. Enclosed documents:

-Updated 6B

If you have any questions or desire additional information, please me at 304-884-1613

Thank you.

Sincerely,

Brittany Woody
Senior Regulatory Analyst
Southwestern Energy Production Company, LLC

The Right People doing the Right Things,
wisely investing the cash flow from our
underlying Assets, will create Value+[®]