

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: L. F. Cain Operator Well No.: 7179

LOCATION: Elevation: 1048.49 Quadrangle: Folsom W.VA  
District: Grant County: Wetzel  
Latitude: \_\_\_\_\_ Feet South of 39 Deg. 29 Min. 22.19 Sec.  
Longitude: \_\_\_\_\_ Feet West of -80 Deg. 31 Min. 15.46 Sec.

Well Type: OIL X GAS \_\_\_\_\_

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.  
1 Bridge Street or Owner 1 Bridge Street  
Monongah, WV 26554 Monongah, WV 26554  
Agent David Roddy Coal Operator \_\_\_\_\_  
Permit Issued Date 01/22/2021 or Owner \_\_\_\_\_

AFFIDAVIT


STATE OF WEST VIRGINIA,  
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 2nd day of April, 2021, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye and Gas Block	1100'	693'		
Expandable Cement	693'	Surface		
8 5/8" Casing	406'	Unknown	0'	Unknown
16" Conductor	Surface	18'	0'	18'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented. and that the work of plugging and filling said well was completed on the 3rd day of May, 2021.

And further deponents saith not. Matthew A. Yearsley  
Kevin S. Wright



Sworn and subscribe before me this 11th day of May, 2021

My commission expires: 09/15/22 Thomas J. Sullivan  
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Bryan Harris Title: Inspector 06/11/2021

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES, INC.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
WEST VIRGINIA LAND RESOURCES, INC.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
EVERETT HAUGHT  
Lease or Property Owner  
28569 SHORTLINE HWY. FOLSOM, WV 26348  
Address

WEST VIRGINIA LAND RESOURCES, INC.  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address  
FOLSOM W.VA  
Well Location  
GRANT  
District  
WETZEL  
County  
7179  
Well No.  
L. F. CAIN  
Farm


STATE INSPECTOR SUPERVISING PLUGGING Bryan Harris  
AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:  
MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 2<sup>nd</sup> day of April, 2021 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
Cleaned the hole with a 12 1/4" bit from the surface to 249'. Reduced the hole to 9 7/8" at 249'. Cleaned the hole with a 9 7/8" bit from 249' to the top of existing 8 5/8" casing at 406'. Reduced the hole to 7 7/8" at 406'. Cleaned out 8 5/8" casing with a 7 7/8" bit from 406' to 1100'. Attempted to remove 8 5/8" casing by pulling 150% of the string weight. All attempts to remove the 8 5/8" casing were unsuccessful. Left an unknown amount of 8 5/8" casing in the hole from 406' to unknown depth. The remaining 8 5/8" casing was cut at 1093', 1043', 993', 943', 903', 898', 893', 890', 888', 886', 881', 876', 836', 786', and 687'. Left 8 5/8" casing through the Pittsburgh Coal Seam (886' - 893'). Left 18' of 16" conductor pipe in the hole from the surface to 18'.	8 5/8" Casing 16" Conductor	0' 0'	Unknown 18'	
<b><u>Cemented the hole from 1100' to surface as follows:</u></b>				
From 1100' to 693' with 125 sacks of Thixotropic Cement with Green Dye and a gas blocker additive. Tagged top of Thixotropic plug at 693'. From 693' to surface with 370 sacks of Expandable Cement. Cement did circulate at surface. A total of 495 sacks of cement were used to cement the hole from 1100' to surface.				
<b>Coal Seams</b>		<b>Description of Monument</b>		
<u>Pittsburgh</u>	886' - 893'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 3<sup>rd</sup> day of May, 2021

And further deponents saith not.



Matthew A. Yearsley  
Matthew A. Yearsley  
Kevin S. Wright  
Kevin S. Wright

Sworn to and subscribed before me this 11<sup>th</sup> day of May, 2021

[Signature] 06/11/2021  
Notary Public

My commission expires: 09/15/22

Permit No. 47-103-03366  
Well No. 7179  
Latitude: 39° 29' 22.19"N  
Longitude: -80° 31' 15.46"W