

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Genine Robinson Operator Well No.: 7183

LOCATION: Elevation: 1338.98 Quadrangle: Folsom W.VA  
District: Grant County: Wetzel  
Latitude: \_\_\_\_\_ Feet South of 39 Deg. 29 Min. 18.50 Sec.  
Longitude: \_\_\_\_\_ Feet West of -80 Deg. 30 Min. 57.90 Sec.

Well Type: OIL \_\_\_\_\_ GAS X

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.  
1 Bridge Street or Owner 1 Bridge Street  
Monongah, WV 26554 Monongah, WV 26554  
Agent David Roddy Coal Operator \_\_\_\_\_  
Permit Issued Date 03/15/2021 or Owner \_\_\_\_\_


AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 15th day of April, 2021, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic W/ Green Dye and Gas Block	1381'	976'		
Expandable Cement	976	Surface		
8 5/8" Casing	1381'	Unknown	410'	Unknown
16" Conductor	Surface	20'	0'	20'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented. and that the work of plugging and filling said well was completed on the 5th day of May, 2021.



Matthew A. Yearsley  
Kevin S. Wright

Sworn and subscribe before me this 17th day of May, 2021

My commission expires: 09/15/22

[Signature]  
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Bryan Harris Title: Inspector

08/13/2021

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES, INC.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
WEST VIRGINIA LAND RESOURCES, INC.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
ROBERT P. & RANDALL B. NICHOLS  
Lease or Property Owner  
6753 N RIDGE RD. MADISON, OH 44057  
Address

WEST VIRGINIA LAND RESOURCES, INC.  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address  
FOLSOM, W.VA  
Well Location  
GRANT  
District  
WETZEL  
County  
7183  
Well No.  
GENINE ROBINSON  
Farm

STATE INSPECTOR SUPERVISING PLUGGING Bryan Harris 5/18/21  
AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:  
MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 15<sup>th</sup> day of April, 2021 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned a 12 1/4" hole from the surface to 530'. Reduced the hole to 9 7/8" at 530'. Cleaned a 9 7/8" hole from 530' to 971'. Tagged top of existing 8 5/8" casing at 971'. Reduced the hole to 7 7/8" at 971'. Cleaned a 7 7/8" hole from 971" to 1381'. Removed 410' of 8 5/8" casing from 971' to 1381'. Left an unknown amount of 8 5/8" casing in the hole from 1381' to an unknown depth. Cleaned a 9 7/8" hole through the Pittsburgh Coal Seam (1174.7' - 1180.9'). Left 20' of 16" conductor pipe in the hole from the surface to 20'.		8 5/8" Casing	410'	Unknown
		16" Conductor	0'	20'
<b>Cemented the hole from 1381' to surface as follows:</b>				
From 1381' to 976' with 290 sacks of Thixotropic Cement with Green Dye and a gas blocker additive. Tagged top of Thixotropic plug at 976'. From 976' to surface with 635 sacks of Expandable Cement. Cement did circulate at surface. A total of 925 sacks of cement were used to fill the hole from 1381' to surface.				
<b>Coal Seams</b>		<b>Description of Monument</b>		
<u>Pittsburgh</u>	1174.7' - 1180.9'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 5<sup>th</sup> day of May, 2021


And further deponents saith not.

*Matthew A. Yearsley*

Matthew A. Yearsley

*Kevin S. Wright*

Kevin S. Wright



Sworn to and subscribed before me this 17<sup>th</sup> day of May, 2021

*[Signature]* 08/13/2021  
Notary Public

My commission expires: 02/15/22

Permit No. 47-103-03373  
Well No. 7183  
Latitude: 39° 29' 18.50"N  
Longitude: -80° 30' 57.90"W