

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: H.L. Smith Operator Well No.: 7384

LOCATION: Elevation: 1354.15' Quadrangle: Folsom W.VA
District: Grant County: Wetzel
Latitude: _____ Feet South of 39 Deg. 29 Min. 52.41 Sec.
Longitude: _____ Feet West of -80 Deg. 32 Min. 22.53 Sec.

Well Type: OIL _____ GAS X

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Agent David Roddy Coal Operator _____
Permit Issued Date 05/13/21 or Owner _____

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 28th day of April, 2021, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye and Gas Block	1370'	1060'		
16" Conuctor	Surface	20'	0'	20'
7" Casing (Degas)	Surface	1055'	(Installed 855' solid - 200' slotted)	1055'
14" Drisco	Surface	20'	0'	20'
Gelled (Easy Seal)	855'	Surface	Grout baskets at 855'	

Description of monument: 77' of 7" casing with company name, well #, API #, and date cemented. and that the work of plugging and filling said well was completed on the 4th day of June, 2021.

And further deponents saith not. Matthew A. Yearsley
Kevin S. Wright



Sworn and subscribe before me this 20th day of July, 2021

My commission expires: 09/15/22 [Signature]
Notary Public

Affidavit reviewed by the Office of Oil and Gas: [Signature] Title: Inspector **08/13/2021**

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
COASTAL FOREST RESOURCES COMPANY
Lease or Property Owner
P.O. BOX 709 BUCKHANNON, WV 26201
Address

WEST VIRGINIA LAND RESOURCES, INC.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
FOLSOM, W.VA
Well Location
GRANT
District
WETZEL
County
7384
Well No.
H.L. Smith
Farm


STATE INSPECTOR SUPERVISING PLUGGING *Bryan Harris*
AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:
MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 28th day of April, 2021 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned the hole with a 12 1/4" bit from the surface to 955'. Reduced the hole to 9 7/8" at 955'. Cleaned the hole with a 9 7/8" bit from 955' to 1221'. Removed various pieces of junk metal out of the hole from 955' to 1221'. Reduced the hole to 7 7/8" at 1221'. Cleaned the hole with a 7 7/8" bit from 1221' to 1370'. Cleaned a 7 7/8" hole through the Pittsburgh Coal Seam (1160' - 1166'). Left 20' of 16 conductor in the hole from the surface to 20'.		7" Casing (Degas)	0'	1055'
		14" Drisco (Degas)	0'	20'
		16" Conductor	0'	20'
<u>Cemented the hole from 1370' to surface as follows:</u> From 1370' to 1060' with 285 sacks of Thixotropic Cement with Green Dye and a gas blocker additive. Tagged top of Thixotropic plug at 1060'.				
The un-cemented portion of the wellbore was converted into a coal degasification hole. Installed 1055' of 7" casing (855' solid and 200' slotted) into the wellbore. Gelled annulus of 7" casing with 88 sacks of Easy Seal from 855' to surface. Gel did circulate at the surface. A 20' joint of 14" drisco was installed from the surface to 20' and cemented with 6 sacks of redi-mix cement.				
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	1160' - 1166'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 4th day of June, 2021

And further deponents saith not.



Matthew A. Yearsley
Matthew A. Yearsley
Kevin S. Wright
Kevin S. Wright

Sworn to and subscribed before me this 20th day of July, 2021

08/13/2021

[Signature]
Notary Public

My commission expires: 09/15/22

Permit No. 47-103-03382
Well No. 7384
Latitude: 39° 29' 52.41"N
Longitude: -80° 32' 22.53"W