

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: O.P McINTYRE Operator Well No.: 7383

LOCATION: Elevation: 1318.41' Quadrangle: Wallace, W.VA
District: Grant County: Wetzel
Latitude: _____ Feet South of 39 Deg. 29 Min. 15.31 Sec.
Longitude: _____ Feet West of -80. Deg. 29 Min. 56.12 Sec.

Well Type: OIL X GAS _____

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Agent David Roddy Coal Operator _____
Permit Issued Date 05/13/2021 or Owner _____

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Monongalia ss:


Mark Wislon and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 13th day of May, 2021, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye and Gas Block	1562'	1081'		
Expandable Cement	1081'	Surface		
8 5/8" Casing	1419'	Unknown	0'	Unknown
16" Conductor	Surface	16'	0'	Unknown

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented. and that the work of plugging and filling said well was completed on the 24th day of May, 2021.

And further deponents saith not. _____

Kevin S. Wright



Sworn and subscribe before me this 7th day of June, 2021

My commission expires: 09/15/22

[Signature]
Notary Public

Affidavit reviewed by the Office of Oil and Gas:

Bryan Harris

Title: Inspector

06/25/2021

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
COASTAL FOREST RESOURCES CO.
Lease or Property Owner
P.O. BOX 709 BUCKHANNON, WV 26201
Address

WEST VIRGINIA LAND RESOURCES, INC.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
WALLACE, W.VA
Well Location
GRANT
District
WETZEL
County
7363
Well No.
O.P. MCINTYRE
Farm

STATE INSPECTOR SUPERVISING PLUGGING Bryan Harris 6/8/21


AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:
MARK WILSON and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 13th day of May, 2021 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned a 12 1/4" hole from the surface to 428'. Reduced the hole to 9 7/8" at 428'. Cleaned a 9 7/8" hole from 428' to 1419'. Tagged top of existing 8 5/8" casing at 1419'. Reduced the hole to 7 7/8" at 1419'. Cleaned a 7 7/8" hole from 1419" to 1562'. Attempted to remove 8 5/8" casing from 1419' by pulling 150% of the string weight. All attempts to remove 8 5/8" casing were unsuccessful. Left an unknown amount of 8 5/8" casing in the hole from 1419' to an unknown depth. Cut remaining 8 5/8" casing 1488'. 8 5/8" was previously ripped from 1440' to 1426'. Cleaned a 9 7/8" hole through the Pittsburgh Coal Seam (1281' - 1288'). Left 16' of 16" conductor pipe in the hole from the surface to 16'.		8 5/8" Casing 16" Conductor	0' 0'	Unknown 16'
Cemented the hole from 1562' to surface as follows: From 1562' to 1081' with 240 sacks of Thixotropic Cement with Green Dye and a gas blocker additive. Tagged top of Thixotropic plug at 1081'. From 1081' to surface with 610 sacks of Expandable Cement. Cement did circulate at surface. A total of 850 sacks of cement were used to fill the hole from 1562' to surface.				
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	<u>1281' - 1288'</u>	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 24th day of May, 2021

And further deponents saith not.



Mark Wilson

Mark Wilson

Kevin S. Wright

Kevin S. Wright

Sworn to and subscribed before me this 7th day of June, 2021

[Signature] 06/25/2021
Notary Public

My commission expires: 09/15/22

Permit No. 47-103-03386
Well No. 7363
Latitude: 39° 29' 15.31"N
Longitude: -80° 30' 56.12"W