

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: B.W. Peterson Operator Well No.: 7232

LOCATION: Elevation: 1131' Quadrangle: Big Run W.VA
District: Grant County: Wetzel
Latitude: _____ Feet South of 39 Deg. 30 Min. 10.57 Sec.
Longitude: _____ Feet West of -80 Deg. 32 Min. 24.88 Sec.

Well Type: OIL GAS _____

Company West Virginia Land Resources Inc Coal Operator West Virginia Land Resources Inc
46226 National Road or Owner 1 Bridge Street
St. Clairsville, OH 43950 St. Clairsville, OH 43950
Coal Operator _____
Agent David Roddy or Owner _____
Permit Issued Date 04/29/2021

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 17th day of June, 2021, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye and Gas Block	1118'	701'		
Expandable Cement	701'	Surface		
7" Casing	936'	1078'	0'	142'
16" Conductor	Surface	20'	0'	20'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented. and that the work of plugging and filling said well was completed on the 7th day of July, 2021.

And further deponents saith not. Matthew A. Yearsley
Kevin S. Wright



Sworn and subscribe before me this 2nd day of Aug, 2021

My commission expires: 09/15/22
Thomas J. Sullivan
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Bryan Harris Title: Inspector

09/20/2024

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC
Coal Operator or Owner
1 BRIDGE STREET ST. CLAIRSVILLE OH 43950
Address
WEST VIRGINIA LAND RESOURCES INC
Coal Operator or Owner
1 BRIDGE STREET ST. CLAIRSVILLE OH 43950
Address
COASTAL FOREST RESOURCES COMPANY
Lease or Property Owner
P.O. BOX 709 BUCKHANNON, WV 26201
Address

WEST VIRGINIA LAND RESOURCES INC
Name of Well Operator
46226 NATIONAL ROAD ST. CLAIRSVILLE OH 43950
Complete Address
BIG RUN WV
Well Location
GRANT
District
WETZEL
County
7232
Well No.
B.W. PETERSON
Farm

STATE INSPECTOR SUPERVISING PLUGGING Bryan Harris 8/4/21
AFFIDAVIT


STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 17th day of June, 2021 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned the hole with 12 1/4" bit from the surface to 455'. Reduced the hole to 9 7/8" at 455'. Cleaned the hole with a 9 7/8" bit from 455' to 936'. Tagged top of existing 7" casing at 936'. Reduced the hole to 6 1/4" at 936'. Cleaned the hole with a 6 1/4" bit from 936' to 1118'. Left 142' of 7" casing in the hole from 936' to 1078'. Cleaned a 9 7/8" hole through the Pittsburgh Coal Seam (901.2' - 907.9'). Left 20' of 16" conductor in the hole from the surface to 20'.		7" Casing	0	142'
		16" Conductor	0	20'
<u>Cemented the hole from 1118' back to surface as follows.</u> From 1118' to 705' with 170 sacks of Thixotropic Cement with Green Dye and a Gas Blocker additive. Tagged top of Thixotropic plug at 705'. From 705' to surface with 395 sacks of Expandable Cement. Cement did circulate at the surface. A total of 565 sacks of cement were used to fill the hole from 1118' to surface.				
Coal Seams		Description of Monument		
<u>Sewickley</u>	804' - 806'	77" of 7" casing w/ company name, well number,		
<u>Pittsburgh</u>	901.2' - 907.9'	permit number and date cemented stated on 7"		
		casing. Well marker will be attached to cement		
		plug at ground level.		

... and that the work of plugging and filling said well was completed on the 7th day of July, 2021

And further deponents saith not.



Sworn to and subscribed before me this 25th day of Aug, 2021

Matthew A. Yearsley

Matthew A. Yearsley

Kevin S. Wright

Kevin S. Wright

Thomas J. Sullivan 09/20/2024
Notary Public

My commission expires: 09/15/22

Permit No. 47-103-03390
Well No. 7232
Latitude: 39° 30' 10.57"N
Longitude: -80° 32' 24.88"W