

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: B. W. Peterson Operator Well No.: 7203B

LOCATION: Elevation: 1437.97' Quadrangle: Folsom, W.VA  
District: Grant County: Wetzel  
Latitude: \_\_\_\_\_ Feet South of 39 Deg. 29 Min. 48.32 Sec.  
Longitude: \_\_\_\_\_ Feet West of -80 Deg. 31 Min. 45.66 Sec.

Well Type: OIL \_\_\_\_\_ GAS X

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.  
1 Bridge Street or Owner 1 Bridge Street  
Monongah, WV 26554 Monongah, WV 26554

Agent David Roddy Coal Operator \_\_\_\_\_  
Permit Issued Date 04/21/2021 or Owner \_\_\_\_\_

AFFIDAVIT


STATE OF WEST VIRGINIA,  
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 17th day of September, 2021, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye and Gas Block	1470'	1055'		
Expandable Cement	1055'	Surface		
8 5/8" Casing	1418'	Unknown	0'	Unknown
16" Conductor Casing	Surface	20'	0'	20'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented and that the work of plugging and filling said well was completed on the 1st day of October, 2021.

And further deponents saith not. Matthew A. Yearsley  
Kevin S. Wright



Sworn and subscribe before me this 11<sup>th</sup> day of Oct, 2021

My commission expires: 09/15/22  
[Signature]  
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Bryan Harris Title: Inspector

09/20/2024

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES, INC.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
WEST VIRGINIA LAND RESOURCES, INC.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
COASTAL FOREST RESOURCES  
Lease or Property Owner  
P.O BOX 709 BUCKHANNON, WV 26201  
Address

WEST VIRGINIA LAND RESOURCES, INC.  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address  
FOLSOM, W.VA  
Well Location  
GRANT  
District  
WETZEL  
County  
7203B  
Well No.  
B.W. PETERSON  
Farm

STATE INSPECTOR SUPERVISING PLUGGING Bryan Harris Inspector 10/12/21

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 17<sup>th</sup> day of September, 2021 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned a 12 ¼ hole from the surface to 487'. Reduced the hole to 9 7/8" at 487'. Cleaned a 9 7/8 hole from 487' to the top of the existing 8 5/8" casing at 1418' top of 8 5/8". Reduced the hole to 7 7/8" at 1418'. Cleaned a 7 7/8 hole from 1418' to 1470'. Cut the existing 8 5/8" casing at 1459'. A diligent effort was made to remove the 8 5/8" casing from 1418' to 1459' by pulling 150% of the string weight. All attempts to remove the 8 5/8" casing were unsuccessful. Left unknown amount of 8 5/8" casing in hole from 1418' to unknown depth. Cleaned 9 7/8 hole through Pittsburgh Coal Seam (1253.1' to 1259.1'). Left 20' of 16" conductor in the hole from the surface to 20'.		8 5/8" Casing 16" Conductor	0' 0'	Unknown 20'
<b>Cemented the hole from 1470' to the surface as follows:</b> From 1470' to 1055' with 260 sacks of Thixotropic with Green Dye and a gas blocker additive. Tagged top of Thixotropic cement plug at 1055'. Cemented the hole from 1055' to surface with 720 sacks of Expandable Cement. Cement did circulate at the surface. A total of 980' sacks of cement were used to fill the hole from 1470' to the surface.				
<b>Coal Seams</b>		<b>Description of Monument</b>		
<u>Pittsburgh</u>	1253.1' – 1259.1'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 1<sup>st</sup> day of October, 2021

And further deponents saith not.

Matthew A. Yearsley

Matthew A. Yearsley

Kevin S. Wright


Kevin S. Wright

Sworn to and subscribed before me this 11<sup>th</sup> day of Oct, 2021

[Signature] 09/20/2024

Notary Public

My commission expires: 09/15/22



Permit No. 47-103-03392  
Well No. 7203B  
Latitude: 39° 29' 48.32"N  
Longitude: -80° 31' 45.66"W