

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: I.D. Morgan Operator Well No.: 7250

LOCATION: Elevation: 988.70' Quadrangle: Big Run W.VA  
District: Grant County: Wetzel  
Latitude: \_\_\_\_\_ Feet South of 39 Deg. 30 Min. 25.43 Sec.  
Longitude: \_\_\_\_\_ Feet West of -80. Deg. 32 Min. 18.70 Sec.

Well Type: OIL X GAS \_\_\_\_\_

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.  
1 Bridge Street or Owner 1 Bridge Street  
Monongah, WV 26554 Monongah, WV 26554  
Agent David Roddy Coal Operator \_\_\_\_\_  
Permit Issued Date 05/06/2021 or Owner \_\_\_\_\_

AFFIDAVIT


STATE OF WEST VIRGINIA,  
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 5th day of October, 2021, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye and Gas Block	992	645'		
Expandable Cement	645'	Surface		
8 5/8" Casing	838'	Unknown	0'	Unknown
16" Conductor	Surface	110'	0'	110'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented and that the work of plugging and filling said well was completed on the 20th day of October, 2021.

And further deponents saith not. Matthew A. Yearsley  
Kevin S. Wright



Sworn and subscribe before me this 1st day of Nov, 2021

My commission expires: 09/15/22  
[Signature]  
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Bryan Harris Title: Inspector 04/08/2022

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
WEST VIRGINIA LAND RESOURCES INC.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
MAGNOLIA LAND PARTNERS LLC.  
Lease or Property Owner  
104 S 20<sup>TH</sup> ST STE A PHILADELPHIA, PA 19103  
Address

WEST VIRGINIA LAND RESOURCES INC.  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address  
BIG RUN, W.VA  
Well Location  
GRANT  
District  
WETZEL  
County  
7250  
Well No.  
I.D. MORGAN  
Farm


STATE INSPECTOR SUPERVISING PLUGGING Bryan Harris Inspector  
AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:  
MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 5<sup>th</sup> day of October, 2021 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned the hole with a 12 1/4" bit from the surface to 443'. Reduced the hole to 9 7/8" at 443'. Cleaned the hole with a 9 7/8" bit from 350' to the top of the existing 8 5/8" casing at 838'. Reduced the hole to 7 7/8" at 838'. Cleaned the hole with a 7 7/8" bit from 838' to a total depth of 992'. Cut the existing 8 5/8" casing at 981', 931' and 881'. A diligent effort was made to pull the 8 5/8" casing by pulling 150% of the string weight but all attempts were unsuccessful. Left an unknown amount of 8 5/8" casing in the hole for 838' to an unknown depth. Cleaned a 9 7/8" hole through the Pittsburgh Coal Seam (774.2' - 780.4') Left 110' of 16" conductor in the hole from the surface to 110'.		8 5/8" Casing	0'	Unknown
		16" Conductor	0'	110'
<b>Cemented the hole from 992' to the surface as follows:</b> From 992' to 645' with 170 sacks of Thixotropic Cement with Green Dye and a gas blocker additive. Tagged top of Thixotropic plug at 645'. Cemented the hole from 645' to the surface with 460 sacks of Expandable Cement. Cement did circulate at the surface. A total of 630 sacks of cement were used to fill the hole from 992' to the surface.				
<b>Coal Seams</b>		<b>Description of Monument</b>		
<u>Pittsburgh</u>	<u>774.2' - 780.4'</u>	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 20<sup>th</sup> day of October, 2021

And further deponents saith not.



Sworn to and subscribed before me this 13<sup>th</sup> day of Nov, 2021

Matthew A. Yearsley  
Matthew A. Yearsley

Kevin S. Wright  
Kevin S. Wright

[Signature]  
Notary Public

04/08/2022

My commission expires: 09/15/22

Permit No. 47-103-03402  
Well No. 7250  
Latitude: 39° 30' 25.43"N  
Longitude: -80° 32' 18.70"W