

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: O.P. McIntyre Operator Well No.: 6340

LOCATION: Elevation: 1001.20' Quadrangle: Wallace, W.VA
District: Grant County: Wetzel
Latitude: _____ Feet South of 39 Deg. 29 Min. 27.21 Sec.
Longitude: _____ Feet West of -80 Deg. 29 Min. 44.27 Sec.

Well Type: OIL X GAS _____

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Agent David Roddy Coal Operator _____
or Owner _____
Permit Issued Date 08/24/2021 _____

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 6th day of October, 2021, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye and Gas Block	1112'	704'		
Expandable Cement	704'	Surface		
7" Casing	1144'	Unknown	1144'	Unknown
8 5/8" Casing	1112'	Unknown	588'	Unknown
16" Conductor	Surface	20'	0'	Unknown

Description of monument: 77" of 7" casing with company name, well #, API#, and date cemented and that the work of plugging and filling said well was completed on the 18th day of November, 2021.


And further deponents saith not. Matthew A. Yearsley

Kevin S. Wright

Sworn and subscribe before me this 24th day of Dec, 2021

My commission expires: 09/15/22

Thomas J. Sullivan
Notary Public



Affidavit reviewed by the Office of Oil and Gas: Bryan Harris Title: Inspector

04/08/2022

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

WEST VIRGINIA LAND RESOURCES INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

COASTAL FOREST RESOURCES CO.
Lease or Property Owner
P.O. BOX 1023 HAVANA FL 32333
Address

WEST VIRGINIA LAND RESOURCES INC.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
WALLACE, WV
Well Location
GRANT
District
WETZEL
County
6340
Well No.
O.P. MCINTYRE
Farm


STATE INSPECTOR SUPERVISING PLUGGING Bryan Harris Inspector
AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:
MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 6th day of October, 2021 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleansed out the existing 7" casing with a 6 1/4" bit from the surface to 1206'. Removed 1144' of 7" casing from surface to 1144'. Left an unknown amount of 8 5/8" casing in the hole from 1144' to an unknown depth. Cleaned the hole with 12 1/4" bit from surface to 262'. Reduced the hole to 9 7/8" at 262'. Cleaned the hole with a 9 7/8" bit from 262' to the hole to the top of the existing 8 5/8" casing at 524'. Reduced the hole to 7 7/8" at 524'. Cleaned the hole with a 7 7/8" bit from 524' to 1144'. Removed 588' of 8 5/8" casing from 524' to 1112'. Left unknown amount of 8 5/8" casing in the hole from 1112' to unknown depth. Continued to clean the hole with a 9 7/8" bit from 524' to 1112'. Cleaned a 9 7/8" hole through the Pittsburgh Coal Seam (904.0' - 910.3'). Left 20' of 16" conductor in the hole from the surface to 20'. Left a 6% gel plug in the hole from 1206' to 1112'.		7" Casing	1144'	Unknown
		8 5/8" Casing	588'	Unknown
		16" Conductor	0'	20'
Cemented the hole from 1112' to the surface as follows: From 1112' to 704' with 255 sacks of Thixotropic with Green Dye and a Gas Blocker additive. Tagged top of Thixotropic cement plug at 704'. Cemented the hole from 704' to the surface with 415 sacks of Expandable Cement. Cement did circulate at surface.				
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	<u>904.0' - 910.3'</u>	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 18th day of November, 2021

And further deponents saith not.



Matthew A. Yearsley
Matthew A. Yearsley

Kevin S. Wright
Kevin S. Wright

Sworn to and subscribed before me this 24th day of Dec, 2021

[Signature] 04/08/2022
Notary Public

My commission expires: 09/15/22

Permit No. 47-103-03448
Well No. 6340
Latitude: 39° 29' 27.21"N
Longitude: -80° 29' 44.27"W