

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Fairfield Peterson Operator Well No.: 7191

LOCATION: Elevation: 1501.03' Quadrangle: Folsom, W.VA  
District: Grant County: Wetzel  
Latitude: \_\_\_\_\_ Feet South of 39 Deg. 29 Min. 37.92 Sec.  
Longitude: \_\_\_\_\_ Feet West of -80 Deg. 30 Min. 45.90 Sec.

Well Type: OIL X GAS \_\_\_\_\_

Company West Virginia Land Resources Inc. Coal Operator West Virginia Land Resources Inc.  
1 Bridge Street or Owner 1 Bridge Street  
Monongah, WV 26554 Monongah, WV 26554  
Agent David Roddy Coal Operator \_\_\_\_\_  
or Owner \_\_\_\_\_  
Permit Issued Date 08/24/2021

AFFIDAVIT


STATE OF WEST VIRGINIA,  
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 22nd day of September, 2021, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w Green Dye and Gas Block	1560'	1148'		
Expandable Cement	1148'	Surface		
7" Casing	1560'	Unknown	1560'	Unknown
16" Conductor	Surface	20'	0'	20'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented and that the work of plugging and filling said well was completed on the 5th day of October, 2021.

And further deponents saith not. Matthew A. Yearsley  
Kevin S. Wright



Sworn and subscribe before me this 18th day of Oct, 2021  
My commission expires: 09/15/22  
[Signature]  
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Bryan Harris Title: Inspector

03/18/2022

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES, INC  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
WEST VIRGINIA LAND RESOURCES, INC  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
CNX LAND LLC  
Lease or Property Owner  
1000 CONSOL ENERGY DRIVE, CANONSBURG, PA 15317  
Address

WEST VIRGINIA LAND RESOURCES, INC  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address  
FOLSOM W.VA  
Well Location  
GRANT  
District  
WETZEL  
County  
7191  
Well No.  
FAIRFIELD PETERSON  
Farm


STATE INSPECTOR SUPERVISING PLUGGING Bryan Harris 10/25/21  
AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:  
MATTHEW A. YEARSLEY and KEVIN S WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 22<sup>nd</sup> day of September, 2021 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleansed a 6 1/4" hole through the existing 7" casing from the surface to 1560'. Removed 1560" of 7" casing from surface to 1560'. Attempted to remove remaining casing by pulling 150% of string weight. All attempts to remove the remaining 7" casing were unsuccessful. Left an unknown amount of 7" casing in the hole from 1560' to an unknown depth. Cleaned the hole with a 12 1/4" bit from surface to 293'. Reduced the hole to 9 7/8" at 293'. Cleaned the hole with a 9 7/8" bit from 293' to the top of the remaining 7" casing at 1560'. Cleaned a 9 7/8" hole through the Pittsburgh Coal Seam (1348.7' to 1354.9'). Left 20' of 16" conductor in the hole from the surface to 20'.		7" Casing	1560'	Unknown
		16" Conductor	0'	20'
<b>Cemented the hole from 1560' to surface as follows:</b> From 1560' to 1148' with 335 sacks Thixotropic Cement with Green Dye and a Gas Blocker additive. From 1148' to the surface with 620 sacks of Expandable Cement. Cement did circulate at the surface. A total of 955 sacks of cement were used to fill the hole from 1560' to the surface.				
<b>Coal Seams</b>		<b>Description of Monument</b>		
<u>Pittsburgh</u>	1348.7' – 1354.9'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 5<sup>th</sup> day of October, 2021

And further deponents saith not.



Sworn to and subscribed before me this 18<sup>th</sup> day of Oct, 2021

Matthew A. Yearsley

Matthew A. Yearsley

Kevin S. Wright

Kevin S. Wright

[Signature]  
Notary Public

03/18/2022

My commission expires: 09/15/22

Permit No. 47-103-03450  
Well No. 7191  
Latitude: 39° 29' 37.92"N  
Longitude: -80° 30' 45.90"W