

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: E. Litman Operator Well No.: 8197

LOCATION: Elevation: 1378' Quadrangle: Hundred WV
District: Church County: Wetzel
Latitude: _____ Feet South of 39 Deg. 39 Min. 03.75 Sec.
Longitude: _____ Feet West of -80 Deg. 24 Min. 08.76 Sec.

Well Type: OIL _____ GAS X

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Agent David Roddy Coal Operator _____
or Owner _____
Permit Issued Date 10/26/2021

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 17th day of May, 2022, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/Green Dye and Gas Blocker	1505'	1017'		
Expandable Cement	1017'	Surface		
7" Casing			10' Milled	0'
8 5/8" Casing	624'	Unknown	0'	Unknown
16" Conductor	Surface	20'	0'	20'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented and that the work of plugging and filling said well was completed on the 3rd day of June, 2022.

And further deponents saith not. Matthew A. Yearsley
Kevin S. Wright



Sworn and subscribe before me this 14th day of Jun, 2022

My commission expires: 09/15/22
[Signature]
Notary Public

RECEIVED
Office of Oil and Gas

Affidavit reviewed by the Office of Oil and Gas: Kenneth Greynolds
Digitally signed by Kenneth Greynolds
DN: CN = Kenneth Greynolds, email = Kenneth.L.Greynolds@wv.gov, C = AD, O = WVDEP, OU = Oil and Gas
Date: 2022.06.21 09:35:52 -0400

Title: _____

JUN 24 2022

WV Department of
Environmental Protection
02/23/2024

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATED, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
COASTAL FOREST RESOURCES
Lease or Property Owner
P.O. BOX 1023 HAVANA, FL 32333
Address

WEST VIRGINIA LAND RESOURCES, INC.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
BIG RUN, W.VA
Well Location
GRANT
District
WETZEL
County
7242
Well No.
B.W. PETERSON
Farm

STATE INSPECTOR SUPERVISING PLUGGING Kenneth Greynolds

Digitally signed by Kenneth Greynolds
DN: CN = Kenneth Greynolds, email = Kenneth.L.Greynolds@wv.gov C = AD O = WVDEP Oil & Gas
Date: 2022.05.11 08:34:53 -0400

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 5th day of April, 2022 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
Cleaned the hole with a 12 1/4" bit from surface to 174'. Reduced the hole to 9 7/8" at 174'. Cleaned the hole with a 9 7/8" bit from 174' to 1101'. Reduced the hole to 6 1/4" at 1101'. Cleaned the hole with a 6 1/4" bit from 1101' to 1152'. Tagged 8 5/8" casing at 1152'. Continued to clean a 6 1/4" hole through the 8 5/8" casing from 1152' to 1293'. Cut the 8 5/8" casing at 1196.1', and 1246.1'. Attempted to pull 8 5/8" casing from 1152' by pulling 150% of string weight. All attempts to pull the 8 5/8" casing were unsuccessful. Left unknown amount of 8 5/8" casing in hole from 1152' to an unknown depth. Cleaned a 9 7/8" hole through the Pittsburgh Coal Seam (1040.0' - 1046.1'). Left 12' of 16" conductor in the hole from the surface to 12'. Cemented hole from 1293' back to the surface as follows: From 1293' to 840' with 190 sacks of Thixotropic Cement with Green Dye and a Gas Blocker additive. Tagged the top of the Thixotropic Cement plug at 840'. Cemented the hole from 840' to surface with 405 sacks of Expandable Cement. Cement did circulate at surface. A total of 595 sacks of cement were used to fill the hole from 1293' back to surface.	8 5/8" Casing 16" Conductor	0' 0'	Unknown 12'	
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	<u>1040.0' - 1046.1'</u>	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 2nd day of May, 2022

And further deponents saith not.



Matthew A. Yearsley
Matthew A. Yearsley

Kevin S. Wright
Kevin S. Wright

Sworn to and subscribed before me this 2nd day of May, 2022

[Signature]
Notary Public

My commission expires: 09/15/22

Permit No. 47-103-03486
Well No. 7242
Latitude: 39° 30' 03.34"N
Longitude: -80° 31' 46.94"W

RECEIVED
Office of Oil and Gas
JUN 24 2022
WV Department of
Environmental Protection
02/23/2024