

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: E. Litman Operator Well No.: 8195

LOCATION: Elevation: 1466.85' Quadrangle: Hundred WV
District: Church County: Wetzel
Latitude: _____ Feet South of 39 Deg. 39 Min. 07.36 Sec.
Longitude: _____ Feet West of -80 Deg. 24 Min. 17.62 Sec.

Well Type: OIL GAS _____

Company	<u>West Virginia Land Resources Inc</u>	Coal Operator	<u>West Virginia Land Resources Inc</u>
	<u>1 Bridge Street</u>	or Owner	<u>1 Bridge Street</u>
	<u>Monongah, WV 26554</u>		<u>Monongah, WV 26554</u>
Agent	<u>David Roddy</u>	Coal Operator	_____
Permit Issued Date	<u>10/25/2021</u>	or Owner	_____


AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 26th day of April, 2022, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Expanding Cement w/Gas Blocker	2603'	1849'	3/4" Sucker Rod Cable - 3295'	0'
Expanding Cement	1849'	1509'	2 3/8" Tubing - 3333'	0'
Thixotropic Cement w/ Green Dye	1509'	1100'	5 1/2" Casing - 2603'	231'
Expanding Cement	1100'	Surface	7" Casing - 1845'	665'
			8 5/8" Casing - 1199'	222'
			16" Conductor - 0'	20'

Description of monument: 77" of 7" casing with company name, well #, API#, and date cemented and that the work of plugging and filling said well was completed on the 13th day of May, 2022.



Matthew A. Yearsley
Kevin S. Wright

Sworn and subscribed before me this 14th day of June, 2022

JUN 24 2022
WV Department of Environmental Protection

My commission expires: 09/15/22
Notary Public

Kenneth Greynolds
Digitally signed by Kenneth Greynolds
DN: CN = Kenneth Greynolds email = Kenneth.L.greynolds@wv.gov C = AD O = WVDEP OU = Oil and Gas
Date: 2022.06.21 08:28:59 -0400

Affidavit reviewed by the Office of Oil and Gas: _____ Title: _____

02/23/2024

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
WEST VIRGINIA LAND RESOURCES INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
WILLIAM E LEMLEY
Lease or Property Owner
12121 MASON DIXON HWY, BURTON WV 26562
Address

WEST VIRGINIA LAND RESOURCES INC
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
HUNDRED W.VA, PA
Well Location
CHURCH
District
WETZEL
County
8195
Well No.
E. LITMAN
Farm

STATE INSPECTOR SUPERVISING PLUGGING Kenneth Greynolds

Digitally signed by Kenneth Greynolds
DN: CN = Kenneth Greynolds email = Kenneth.L.Greynolds@wv.gov C = AD O
= WDEP OU = Oil and Gas
Date: 2022.06.21 08:29:56 -0400

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, Inc well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 26th day of April, 2022 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Removed 3295' of 3/4" sucker rod cable. Removed 3333' of 2 3/8" tubing. Removed 2603' of 5 1/2" casing. Left 231' of 5 1/2" casing in hole from 2603' to 2834'. Left 6% gel plug in the hole from 3333' to 2603'. Cemented the bottom hole from 2603' back to 1849' with 160 sacks Expandable Cement with a Gas Blocker additive. Tagged top of the bottom hole plug at 1849'. Removed 1845' of 7" casing from the surface to 1845'. Left 665' of 7" casing in hole from 1845' to 2510'. Attempted to remove remaining 7" casing by pulling of 150% of the string weight but all attempts were unsuccessful. Removed 1199' of 8 5/8" casing from 354' to 1199'. Left 222' of 8 5/8" casing in hole from 1553' to 1775'. Cleaned a 9 7/8" hole from the surface to 1553'. Cleaned 7 7/8" hole through the remaining 8 5/8" casing from 1553' to 1845'. Cleaned 6 1/4" hole through the remaining 7" casing from 1845' to the top of the bottom hole plug at 1849'. Cleaned a 9 7/8" hole through Pittsburgh Coal Seam (1300.0' - 1308.3'). Left 20' of 16" conductor in the hole from the surface to 20'. Cemented the hole from 1849' back to the surface as follows; From 1849' to 1509' with 95 sacks of Expandable Cement. From 1509' to 1100' with 235 sacks of Thixotropic Cement with Green Dye. From 1100' to the surface with 700 sacks of Expandable Cement. Cement did circulate. A total of 1095 sacks of cement were used to fill the hole from 2603' to the surface.	Sucker Rod Cable	3295'	0'	
	2 3/8" Tubing	3,333'	0'	
	5 1/2" Casing	2,603'	231'	
	7" Casing	1,845'	665'	
	8 5/8" Casing	1,553'	222'	
	16" Conductor	0'	20'	
Coal Seams	Description of Monument			
<u>Pittsburgh</u>	<u>1300.0' - 1308.3'</u>	<u>77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.</u>		

... and that the work of plugging and filling said well was completed on the 13th day of May, 2022

And further deponents saith not.



Sworn to and subscribed before me this 14th day of Jun, 2022

My commission expires: 09/15/22

Matthew A. Yearsley
Matthew A. Yearsley
Kevin S. Wright
Kevin S. Wright
[Signature]
Notary Public

Permit No. 47-103-03464
Well No. 8195
Latitude: 39° 39' 07.36"N
Longitude: -80° 24' 17.62"W

JUN 24 2022
WV Department of Environmental Protection

02/23/2024