

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: I.D. Morgan Operator Well No.: 7325

LOCATION: Elevation: 883' Quadrangle: Big Run WV
District: Grant County: Wetzel
Latitude: _____ Feet South of 39 Deg. 30 Min. 28.61 Sec.
Longitude: _____ Feet West of -80 Deg. 31 Min. 07.70 Sec.

Well Type: OIL GAS _____

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Coal Operator _____
Agent David Roddy or Owner _____
Permit Issued Date 10/26/2021 _____

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 20th day of January, 2022, and the well was plugged and filled in the following manner:

| TYPE | FROM | TO | PIPE REMOVED | LEFT |
|--|---------|---------|--------------|---------|
| Thixotropic w/ Green Dye and Gas Block | 943' | 496' | | |
| Expandable Cement | 496' | Surface | | |
| 7" Casing | 819' | Unknown | 0' | Unknown |
| 16" Conductor | Surface | 30' | 0' | 30' |
| | | | | |
| | | | | |

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented and that the work of plugging and filling said well was completed on the 8th day of February, 2022.

And further deponents saith not. Matthew A. Yearsley
Kevin S. Wright



Sworn and subscribe before me this 18th day of Feb, 202022

My commission expires: 09/15/22 [Signature]
Notary Public

Affidavit reviewed by the Office of Oil and Gas: _____ Title: _____

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
NICHOLAS E & DEBORAH EINSMINGER
Lease or Property Owner
43 KIMBERLY CIRCLE, FAIRMONT, WV 26554
Address

WEST VIRGINIA LAND RESOURCES, INC.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
BIG RUN, WV
Well Location
GRANT
District
WETZEL
County
7325
Well No.
I.D. MORGAN
Farm

STATE INSPECTOR SUPERVISING PLUGGING _____

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 20th day of January, 2022 and that the well was plugged in the following manner:

| Sand or Zone Record Formation | Filling Material | Casing/Tubing Size | Casing Pulled | Casing Left In |
|---|------------------|--|---------------|--------------------|
| Cleaned the hole with a 12 1/4" bit from the surface to 439'. Reduced the hole to 9 7/8" at 439'. Cleaned the hole with 9 7/8" bit from 439' to 819'. Tagged the top of the existing 7" casing at 819'. Reduced the hole to 6 1/4" at 819'. Cleaned the hole with a 6 1/4" bit through the 7" casing from 819' to 943'. Attempted to remove the 7" casing by pulling 150% of the string weight. All attempts were unsuccessful. Left an unknown amount of 7" casing in the hole from 819' to unknown depth. Cut the remaining 7" casing at 903' and 853'. Cleaned a 9 7/8" hole through the Pittsburgh Coal Seam (696.5' - 703.0'). Left 30' of 16" conductor pipe in the hole from the surface to 30'. | | 7" Casing 16" Conductor | 0' 0' | Unknown 30' |
| Cemented the hole from 943' to surface as follows: From 943' to 496' with 210 sacks of Thixotropic Cement w/ Green Dye and Gas Blocker additive. Tagged the top of Thixotropic plug at 496'. Cemented the hole from the top of the Thixotropic cement plug at 496' to the surface with 380 sacks of Expandable Cement. Cement did circulate at the surface. A total 590 sacks of cement were used to fill the hole from 943' to the surface. | | | | |
| Coal Seams | | Description of Monument | | |
| <u>Pittsburgh</u> | 696.5' - 703.0' | 77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level. | | |
| | | | | |
| | | | | |

... and that the work of plugging and filling said well was completed on the 8th day of February, 2022

And further deponents saith not.



Matthew A. Yearsley

Matthew A. Yearsley

Kevin S. Wright

Kevin S. Wright

Sworn to and subscribed before me this 18th day of Feb, 2022

[Signature]

Notary Public

My commission expires: 09/15/22

Permit No. 47-103-03466
Well No. 7325
Latitude: 39° 30' 28.61"N
Longitude: -80° 31' 07.70"W