

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: B.W. Peterson Operator Well No.: 7242

LOCATION: Elevation: 1240.95' Quadrangle: Big Run, W.VA
District: Grant County: Wetzel
Latitude: _____ Feet South of 39 Deg. 30 Min. 03.34 Sec.
Longitude: _____ Feet West of -80 Deg. 31 Min. 46.94 Sec.

Well Type: OIL _____ GAS X

Company	<u>West Virginia Land Resources, Inc.</u>	Coal Operator	<u>West Virginia Land Resources, Inc.</u>
	<u>1 Bridge Street</u>	or Owner	<u>1 Bridge Street</u>
	<u>Monongah, WV 26554</u>		<u>Monongah, WV 26554</u>
Agent	<u>David Roddy</u>	Coal Operator	_____
		or Owner	_____
Permit Issued Date	<u>03/07/2022</u>		_____

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 5th day of April, 2022, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye and Gas Block	1293'	840'		
Expandable Cement	840'	Surface		
8 5/8" Casing	1152'	Unknown	0'	Unknown
16" Conductor	Surface	12'	0'	12'

Description of monument: 77" of 7" casing with company name, well #, API#, and date cemented and that the work of plugging and filling said well was completed on the 2nd day of May, 2022.


And further deponents saith not. Kevin S. Wright

Matthew A. Yearsley

Sworn and subscribe before me this 9th day of May, 2022

My commission expires: 09/15/22

[Signature]
Notary Public



Affidavit reviewed by the Office of Oil and Gas: Kenneth Greynolds

Title: _____

RECEIVED
Office of Oil and Gas
JUN 24 2022

02/23/2024

WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OIL AND GAS WELLS DIVISION

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
WEST VIRGINIA LAND RESOURCES INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
COASTAL FOREST RESOURCES CO.
Lease or Property Owner
P.O. BOX 1023, HAVANA, FL 32333
Address

WEST VIRGINIA LAND RESOURCES INC
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
BIG RUN W.VA
Well Location
GRANT
District
WETZEL
County
7275
Well No.
B. W. PETERSON
Farm

STATE INSPECTOR SUPERVISING PLUGGING Kenneth Greynolds

Digitally signed by Kenneth Greynolds
DN: cn = Kenneth Greynolds email = Kenneth.L.Greynolds@wv.gov, c = AD O =
WVDEP OJ = Oil and Gas
Date: 2022.05.21 08:33:55 -0400

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 4th day of May, 2022 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
	Cleaned the hole with 12 1/4" bit from the surface to 180'. Reduced the hole to 9 7/8" at 180'. Cleaned the hole with 9 7/8" bit from 180' to the top of the existing 8 5/8" casing at 959'. Reduced the hole to 6 1/4" at 959'. Cleaned out the 8 5/8" casing with a 6 1/4" bit from 959' to 1194'. Cleaned a 6 1/4" through the Pittsburgh Coal Seam (983.0' to 990.2'). Cut the 8 5/8" casing at 1000.2'. Attempted to pull 8 5/8" casing from 959' to 1000.2' by pulling 150% of string weight but all attempts were unsuccessful. Additional cuts were placed in the 8 5/8" casing at 1190.2', 1140.2', 1090.2', 1040.2', 1000.2', 995.2', 990.2', 988.2', 986.2', 984.6', 983', 978', 973'. Left an unknown amount of 8 5/8" casing in the hole from 959' to an unknown depth. Left 13' of 16" conductor in hole from the surface to 13'.	8 5/8" Casing 16" Conductor	0' 0'	Unknown 13'
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	983.0' - 990.2'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 27th day of May, 2022

And further deponents saith not.



Sworn to and subscribed before me this 14th day of Jun., 2022

Matthew A. Yearsley

Matthew A. Yearsley

Kevin S. Wright

Kevin S. Wright

[Signature]
Notary Public

My commission expires: 09/15/22

Permit No. 47-103-03489
Well No. 7275
Latitude: 39° 30' 02.26"N
Longitude: -80° 31' 36.65"W

RECEIVED
Office of Oil and Gas

JUN 24 2022

WV Department of
Environmental Protection
02/23/2024