

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Robert Smith Operator Well No.: 7278

LOCATION: Elevation: 1069.55' Quadrangle: Big Run W.VA

District: Grant County: Wetzel

Latitude: \_\_\_\_\_ Feet South of 39 Deg. 30 Min. 02.03 Sec.

Longitude: \_\_\_\_\_ Feet West of -80 Deg. 30 Min. 03.40 Sec.

Well Type: OIL X GAS \_\_\_\_\_

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.  
1 Bridge Street or Owner 1 Bridge Street  
Monongah, WV 26554 Monongah, WV 26554

Agent David Roddy Coal Operator \_\_\_\_\_  
Permit Issued Date 09/06/2022 or Owner \_\_\_\_\_

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of Monongalia ss:


Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 12th day of October, 2022, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye and Gas Block	1156'	719'	7" Casing - 0'	Unknown
Expandable Cement	719'	Surface	16" Conductor - 0'	20'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented and that the work of plugging and filling said well was completed on the 26th day of October, 2022.

And further deponents saith not. Matthew A. Yearsley  
Kevin S. Wright

Sworn and subscribe before me this 17 day of November, 2022



My commission expires: June 8, 2027  
Christopher Andrew Willis  
Notary Public

Affidavit reviewed by the Office of Oil and Gas: \_\_\_\_\_ Title: \_\_\_\_\_



AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
WEST VIRGINIA LAND RESOURCES INC  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
EDGAR D. & EDGAR D. BYARD JR.  
Lease or Property Owner  
2198 DEAD FALL RD. SMITHFIELD, WV 26562  
Address

WEST VIRGINIA LAND RESOURCES INC  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address  
BIG RUN W.VA  
Well Location  
GRANT  
District  
WETZEL  
County  
7278  
Well No.  
ROBERT SMITH  
Farm

STATE INSPECTOR SUPERVISING PLUGGING \_\_\_\_\_


AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:  
MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 12<sup>th</sup> day of October, 2022 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
<u>Formation</u>				
Cleaned a 12 1/4" hole from the surface to 330'. Reduced the hole to 9 7/8" at 330'. Cleaned a 9 7/8" hole from 330' to the top of the existing 7" casing at 1062'. Reduced the hole to 6 1/4" at 1062'. Cleaned a 6 1/4" hole from 1062' to 1156'. Attempted to remove existing 7" casing from 1062' by pulling 150% of the string weight but all attempts were unsuccessful. Left an unknown amount of 7" casing in the hole from 1062' to an unknown depth. Perforated remaining 7" casing with 6 shots at each of the following depths: 1021.6' and 1071.6'. Cleaned a 9 7/8" hole through the Pittsburgh Coal Seam (915.1' - 921.6'). Left 20' of 16" conductor pipe in the hole from the surface to 20'.  <u>Cemented the hole from 1156' to the surface as follows:</u> From 1156' to 719' with 220 sacks of Thixotropic Cement with Green Dye and a Gas Blocker additive. Tagged top of Thixotropic cement plug at 719'. Cemented the hole from 719' to the surface with 400 sacks of Expandable Cement. Cement did circulate at the surface. A total of 620 sacks of cement were used to fill the hole from 1156' to the surface.	7" Casing  16" Conductor	0'  0'	Unknown  23'	
<u>Coal Seams</u>		<u>Description of Monument</u>		
<u>Pittsburgh</u>	915.1' - 921.6'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 26<sup>th</sup> day of October, 2022

And further deponents saith not.



*Matthew A. Yearsley*

Matthew A. Yearsley

*Kevin S. Wright*

Kevin S. Wright

Sworn to and subscribed before me this 17 day of November, 2022

*Christopher Andrew Willis*  
Notary Public

My commission expires: June 8, 2027

Permit No. 47-103-03525  
Well No. 7278  
Latitude: 39° 30' 02.03"N  
Longitude: -80° 30' 03.40"W