

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: G.W. Price Operator Well No.: 7321

LOCATION: Elevation: 1092.52 Quadrangle: Folsom, WV
District: Grant County: Wetzel
Latitude: _____ Feet South of 39 Deg. 29 Min. 49.26 Sec.
Longitude: _____ Feet West of -80 Deg. 30 Min. 20.16 Sec.

Well Type: OIL _____ GAS X

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Agent David Roddy Coal Operator _____
Permit Issued Date 09/22/2022 or Owner _____

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 19th day of October, 2022, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic Cement w/ Gas Blocker	1100'	980'	16" Conductor - 0'	23'
Pea Gravel and Sand	980'	965'		
Thixotropic Cement w/ Fluid Loss Additive	965'	913'		
Thixotropic Cement	913'	813'		
Expandable Cement	813'	Surface		

Description of monument: 77" of 7" casing with company name, well #, API#, and date cemented and that the work of plugging and filling said well was completed on the 28th day of October, 2022.

And further deponents saith not. Matthew A. Yearsley
Kevin S. Wright



Sworn and subscribe before me this 30 day of December, 2022

My commission expires: June 8, 2027

Christopher Andrew Willis
Notary Public

Affidavit reviewed by the Office of Oil and Gas: _____ Title: WV Oil and Gas Inspector

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
LORAN PAUL HIGGINS ETAL
Lease or Property Owner
1011 LAKEWAY DRIVE, NICEVILLE, FL 32578
Address

WEST VIRGINIA LAND RESOURCES, INC.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
FOLSOM W.VA
Well Location
GRANT
District
WETZEL
County
7321
Well No.
G.W. PRICE
Farm

STATE INSPECTOR SUPERVISING PLUGGING _____

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 19th day of October, 2022 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
	Cleaned the hole with a 12 1/4" bit from the surface to 318'. Reduced the hole to 9 7/8" at 318'. Cleaned the hole with a 9 7/8" bit from 318' to 910'. Started losing circulation in the Pittsburgh Coal Seam at 910'. Reduced the hole to 6 1/4" at 910'. Cleaned the hole with a 6 1/4" bit without circulation from 910' to the MSHA approved attainable bottom at 1100'. Cleaned a 6 1/4" hole through the Pittsburgh Coal Seam (974' - 980'). Left 23' of 16" conductor pipe in the hole from the surface to 23'. Cemented the hole from 1100' to the surface as follows: From 1100' to 980' with 70 sacks of Thixotropic Cement with a Gas Blocker additive. Tagged top of Thixotropic Cement plug at 980'. Due to extreme circulation issues, 56 sacks of pea gravel and 4 sacks of sand were placed through the Pittsburgh Coal Seam from 980' to 965'. Cemented the hole from 965' to 913' with 35 sacks of Thixotropic Cement and 50 pounds of fluid loss additive. Tagged top of Thixotropic cement plug at 913'. Cemented the hole from 913' to 813' with 65 sacks of Thixotropic Cement. Tagged top of Thixotropic Cement plug at 813'. Cemented the hole from 813' to the surface with 570 sacks of Expandable Cement. Cement did circulate at the surface.	16" Conductor	0'	23'
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	<u>974' - 980'</u>	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 28th day of October, 2022

And further deponents saith not.



Matthew A. Yearsley

Matthew A. Yearsley

Kevin S. Wright

Kevin S. Wright

Sworn to and subscribed before me this 30 day of December, 2022

Christopher Andrew Willis
Notary Public

My commission expires: June 8, 2027

Permit No. 47-103-03535
Well No. 7321
Latitude: 39° 29' 49.26"N
Longitude: -80° 30' 20.16"W