

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
WEST VIRGINIA LAND RESOURCES INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
MAGNOLIA LAND PARTNERS LLC.
Lease or Property Owner
104 S 20TH ST STE A PHILADELPHIA, PA 19103
Address

WEST VIRGINIA LAND RESOURCES INC
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
BIG RUN W.VA
Well Location
GRANT
District
WETZEL
County
7257
Well No.
I. D. MORGAN
Farm

STATE INSPECTOR SUPERVISING PLUGGING _____


AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:
MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 20th day of January, 2023 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
	Cleaned a 12 1/4" hole from the surface to 133'. Ran 112' of 10 3/4" in the hole and cemented the 10 3/4" casing to the surface.	10 3/4" Casing	0'	112'
	Cleaned a 9 7/8" hole from 133' to 1163'. Cleaned a 9 7/8" hole through the Pittsburgh Coal Seam (906' - 912'). Left 112' of 10 3/4" casing on the hole from the surface to 112'. Left 20' of 13 3/8" casing in the hole from the surface to 20'.	13 3/8" Conductor	0'	20'
Cemented the hole from 1163' to the surface as follows: From 1163' to 706' with 270 sacks of Thixotropic Cement with Green Dye and a Gas Blocker additive. Tagged top of Thixotropic cement plug at 706'. Cemented the hole from 706' to the surface with 390 sacks of Expandable Cement. Cement did circulate at the surface. A total of 660 sacks of cement were used to fill the hole from 1163' to the surface.				
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	906' - 912'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 14th day of February, 2023

And further deponents saith not.



Matthew A. Yearsley
Matthew A. Yearsley

Kevin S. Wright
Kevin S. Wright

Sworn to and subscribed before me this 17 day of March 2023

Christopher Andrew Willis
Notary Public

My commission expires: June 8, 2027

Permit No. 47-103-03539
Well No. 7257
Latitude: 39° 30' 26.09"N
Longitude: -80° 31' 57.09"W