

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: B.W. Peterson Operator Well No.: 7428

LOCATION: Elevation: 1269.6' Quadrangle: Big Run W.VA
District: Grant County: Wetzel
Latitude: _____ Feet South of 39 Deg. 30 Min. 59.24 Sec.
Longitude: _____ Feet West of -80 Deg. 31 Min. 03.18 Sec.

Well Type: OIL _____ GAS X

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Agent David Roddy Coal Operator _____
or Owner _____
Permit Issued Date _____

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 22nd day of May, 2023, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye and Gas Block	1320'	885'	16" Conductor - 0'	16'
Expandable Cement	885'	Surface		

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented and that the work of plugging and filling said well was completed on the 15th day of June, 2023.

And further deponents saith not. Matthew A. Yearsley
Kevin S. Wright

Sworn and subscribe before me this 7th day of July, 2023

My commission expires: June 8, 2027 Christopher Willis
Notary Public



Affidavit reviewed by the Office of Oil and Gas: _____ Title: _____

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

WEST VIRGINIA LAND RESOURCES INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
JOHN DALE COEN
Lease or Property Owner
666 S LINDEN AVE. ALLIANCE, OH 44601
Address

WEST VIRGINIA LAND RESOURCES INC
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
BIG RUN W.VA
Well Location
GRANT
District
WETZEL
County
7428
Well No.
B.W. PETERSON
Farm

STATE INSPECTOR SUPERVISING PLUGGING _____

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 22nd day of May, 2023 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
	Cleaned a 12 1/4" hole from the surface to 248'. Cleaned a 9 7/8" hole from 248' to 1270'. Cleaned a 7 7/8" hole from 1270' to 1320'. Cleaned a 9 7/8" hole through the Pittsburgh Coal Seam (1085.0' - 1090.5'). Left 16' of 16" conductor pipe in the hole from the surface to 20'. Cemented the hole from 1320' to the surface as follows: From 1320' to 885' with 230 sacks of Thixotropic Cement with Green Dye and a Gas Blocker additive. Tagged top of Thixotropic cement plug at 885'. Cemented the hole from 885' to the surface with 500 sacks of Expandable Cement. Cement did circulate at the surface. A total of 730 sacks of cement were used to fill the hole from 1320' to the surface.	16" Conductor	0'	16'
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	1085.0' - 1090.5'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 15th day of June, 2023

And further deponents saith not.

Matthew A. Yearsley

Matthew A. Yearsley

Kevin S. Wright


Kevin S. Wright

Sworn to and subscribed before me this 7th day of July, 2023

[Signature]
Notary Public

My commission expires:

June 8, 2027



Permit No. 47-103-03547

Well No. 7428

Latitude: 39° 30' 59.24"N

Longitude: -80° 31' 03.18"W