

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Dave Norris Operator Well No.: 7454

LOCATION: Elevation: 1086' Quadrangle: Big Run W.VA  
District: Grant County: Wetzel  
Latitude: \_\_\_\_\_ Feet South of 39 Deg. 31 Min. 00.35 Sec.  
Longitude: \_\_\_\_\_ Feet West of -80 Deg. 31 Min. 11.71 Sec.

Well Type: OIL \_\_\_\_\_ GAS X

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.  
1 Bridge Street or Owner 1 Bridge Street  
Monongah, WV 26554 Monongah, WV 26554  
Agent David Roddy Coal Operator \_\_\_\_\_  
Permit Issued Date 03/09/2023 or Owner \_\_\_\_\_

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 6th day of June, 2023, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye and Gas Block	1225'	740'	16" Conductor - 0'	20'
Expandable Cement	740'	Surface		


Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented and that the work of plugging and filling said well was completed on the 19th day of June, 2023.

And further deponents saith not. Matthew A. Yearsley  
Kevin S. Wright

Sworn and subscribe before me this 7th day of July, 2023

My commission expires: June 8, 2027

Christopher Andrew Willis  
Notary Public



Affidavit reviewed by the Office of Oil and Gas: \_\_\_\_\_ Title: \_\_\_\_\_

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address

WEST VIRGINIA LAND RESOURCES INC  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address

R.L. ENSMINGER EST. & NILA ENSMINGER  
Lease or Property Owner  
10100 SCHNEITER CIR. ANCHORAGE, AK 99507  
Address

WEST VIRGINIA LAND RESOURCES INC  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address

BIG RUN W.VA  
Well Location  
GRANT  
District  
WETZEL  
County  
7454  
Well No.  
DAVE NORRIS  
Farm

STATE INSPECTOR SUPERVISING PLUGGING \_\_\_\_\_

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 6<sup>th</sup> day of June, 2023 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
	Cleaned a 12 1/4" hole from the surface to 382'. Cleaned a 9 7/8" hole from 384' to 1225'. Cleaned a 9 7/8" hole through the Pittsburgh Coal Seam (874.0' – 880.0'). Left 20' of 16" conductor pipe in the hole from the surface to 20'.  <b>Cemented the hole from 1225' to the surface as follows:</b> From 1225' to 740' with 345 sacks of Thixotropic Cement with Green Dye and a Gas Blocker additive. Tagged top of Thixotropic Cement plug at 740'. Cemented the hole from 740' to the surface with 590 sacks of Expandable Cement. Cement did circulate at the surface. A total of 935 sacks of cement were used to fill the hole from 1225' to the surface.	16" Conductor	0'	20'
<b>Coal Seams</b>		<b>Description of Monument</b>		
<u>Pittsburgh</u>	<u>874.0' – 880.0'</u>	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 19<sup>th</sup> day of June, 2023

And further deponents saith not.

*Matthew A. Yearsley*

Matthew A. Yearsley

*Kevin S. Wright*


Kevin S. Wright

Sworn to and subscribed before me this 7<sup>th</sup> day of July, 2023

*Christopher Andrew Willis*  
Notary Public

My commission expires:

June 8, 2027



Permit No. 47-103-03568

Well No. 7454

Latitude: 39° 31' 00.35"N

Longitude: -80° 31' 11.71"W