

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: L.S. Walters Operator Well No.: 7297

LOCATION: Elevation: 1346.83' Quadrangle: Big Run W. VA  
District: Grant County: Wetzel  
Latitude: 39.51221 Feet South of 39 Deg. 30 Min. 43.96 Sec.  
Longitude: -80.52555 Feet West of -80 Deg. 31 Min. 31.98 Sec.

Well Type: OIL X GAS \_\_\_\_\_

Company West Virginia Land Resources, Inc Coal Operator West Virginia Land Resources, Inc  
1 Bridge Street or Owner 1 Bridge Street  
Monongah, WV 26554 Monongah, WV 26554  
Agent David Roddy Coal Operator \_\_\_\_\_  
Permit Issued Date 5/4/2023 or Owner \_\_\_\_\_

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of Wetzel ss:

Matthew A. Yearsley and Delbert Moore being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 14th day of September, 2023, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye/ Gas Blocker	1442'	941'		
Expandable Cement	941'	Surface		
8-5/8" Casing	1422'	474'	0'	474'
16" Conductor	20'	Surface	0'	20'

Description of monument: 77" of 7" casing with company name, well #, API # and date cemented and that the work of plugging and filling said well was completed on the 29th day of September, 2023.

And further deponents saith not. Matthew A. Yearsley  
Delbert L. Moore

Sworn and subscribe before me this 2<sup>nd</sup> day of November, 2023

My commission expires: August 17, 2025 [Signature]  
Notary Public



Affidavit reviewed by the Office of Oil and Gas: \_\_\_\_\_ Title: \_\_\_\_\_



AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES, INC  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
WEST VIRGINIA LAND RESOURCES, INC  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
YVONNE R. MCFADDEN  
Lease or Property Owner  
249 BUCK RUN RD. SMITHFIELD, WV 26437  
Address

WEST VIRGINIA LAND RESOURCES, INC  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address  
BIG RUN, WV  
Well Location  
GRANT  
District  
WETZEL  
County  
7297  
Well No.  
L.S. WALTERS  
Farm

STATE INSPECTOR SUPERVISING PLUGGING: Stephen McCoy

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of WETZEL ss:

MATTHEW A. YEARSLEY and DELBERT MOORE being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 14<sup>th</sup> day of September, 2023 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
	Cleaned hole with a 12-1/4" from the surface to 552'. Reduced hole to 9-7/8" at 552'. Cleaned with 9-7/8" bit from 552 to 948' tagging the 8-5/8" casing. Cleaned through 8-5/8" casing from 948' to 1442'. Cleaned 7-7/8" hole through Pittsburgh Coal Seam from 1141 to 1147.5'. Made a diligent effort to remove 8 5/8 casing by pulling 150% string weight from 948' to 1347.5'. All attempts were unsuccessful. Cut remaining 8 5/8 casing at the following depths: 1347.5', 1297.5', 1247.5', 1197.5', 1157.5', 1152.5', 1147.5', 1143.5', 1141', 1136', 1131', 1091', 1041'.	8-5/8" Casing 16" Conductor	0' 0'	474' 20'
<b>Cemented the hole from 1142' to Surface as follows:</b> Cemented from 1442' to 941' with 150 sacks of Thixotropic Cement with green dye and a gas blocker additive. Cemented from 941 to surface with 555 sacks of expanding cement. Cement did circulate at surface. Left 474' of 8-5/8" casing in well from 948' to 1422'. Left 20' of 16" conductor in well from 20' to surface				
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	<u>1141'-1147.5'</u>	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 29<sup>th</sup> day of September, 2023

And further deponents saith not.

Matthew A. Yearsley  
Matthew A. Yearsley


Delbert L. Moore  
Delbert Moore

Sworn to and subscribed before me this 9<sup>th</sup> day of November, 2023

Christopher Andrew Willis  
Notary Public

My commission expires:

June 8, 2027



Permit No. 47-103-03579-00-00  
Well No. 7297  
Latitude: 39° 30' 43.96"N  
Longitude: -80° 31' 31.98"W

Stephen McCoy